



April 20, 2004

State of Utah
Division of Oil, Gas & Mining
Attn: Diana Whitney
1594 West North Temple - Suite 1210
P.O. Box 145801
Salt Lake City, Utah 84114-5801

RECEIVED
APR 21 2004
DIV. OF OIL, GAS & MINING

RE: Applications for Permit to Drill: Ashley State 10-2-9-15, 11-2-9-15, 12-2-9-15, 13-2-9-15, 14-2-9-15, and 15-2-9-15.

Dear Diana:

Enclosed find APD's on the above referenced wells. When these APD's are approved, please contact Brad Mecham to set up a State On-Site. If you have any questions, feel free to give either Brad or myself a call.

Sincerely,

Mandie Crozier
Regulatory Specialist

mc
enclosures

STATE OF UTAH

DIVISION OF OIL, GAS AND MINING

001

APPLICATION FOR PERMIT TO DRILL, DEEPEN

1a. TYPE OF WORK **DRILL** ☐ **DEEPEN** ☒

1b. TYPE OF WELL

OIL ☒ GAS ☐ OTHER ☐ SINGLE ZONE ☐ MULTIPLE ZONE ☒

2. NAME OF OPERATOR

Inland Production Company

3. ADDRESS AND TELEPHONE NUMBER:

Route #3 Box 3630, Myton, UT 84052**Phone: (435) 646-3721**

4. LOCATION OF WELL (FOOTAGE)

At Surface **SW/SE 537' FSL 2051' FEL 568524X 40.65419**
At proposed Producing Zone **4433871Y -110.19642**

14. DISTANCE IN MILES AND DIRECTION FROM NEAREST TOWN OR POST OFFICE*

Approximately 16.1 Miles southwest of Myton, UT

15. DISTANCE FROM PROPOSED* LOCATION TO NEAREST PROPERTY OR LEASE LINE, FT. (Also to nearest drlg. unit line, if any)

Approx 537' f/lse line & 537' f/unit line

18. DISTANCE FROM PROPOSED LOCATION* TO NEAREST WELL, DRILLING, COMPLETED, OR APPLIED FOR ON THIS LEASE, FT.

Approximately 1224'

16. NO. OF ACRES IN LEASE

621.07

17. NO. OF ACRES ASSIGNED TO THIS WELL

Approximately 40

19. PROPOSED DEPTH

6500'

20. ROTARY OR CABLE TOOLS

Rotary

21. ELEVATIONS (Show whether DF, RT, GR, etc.)

6020' GL

22. APPROX. DATE WORK WILL START*

2nd Quarter 2004

23. PROPOSED CASING AND CEMENTING PROGRAM

SIZE OF HOLE	SIZE OF CASING	WEIGHT/FOOT	SETTING DEPTH	QUANTITY OF CEMENT
12 1/4	8 5/8	24#	290'	155 sx +/- 10%
7 7/8	5 1/2	15.5#	TD	275 sx lead followed by 450 sx tail
				See Detail Below

DESCRIBE PROPOSED PROGRAM: If proposal is to deepen, give data on present productive zone and proposed new productive zone. If proposal is to drill or deepen directionally, give pertinent data on subsurface locations and measured and true vertical depths. Give blowout preventer program, if any.

*The actual cement volumes will be calculated off of the open hole logs, plus 15% excess:

SURFACE PIPE - 155 sx Class G Cement +/I 10%, w/ 2% CaCl₂ & 1/4#/sk Cello-flake
Weight: 15.8 PPG YIELD: 1.17 Cu Ft/sk H₂O Req: 5 gal/sk

LONG STRING - Lead: Premium Lite II Cement + 3lbs/sk BA-90 + 3% KCl + .25 lbs/sk Cello Flake + 2 lbs/sk Kol Seal +
10% Bentonite + .5% Sodium Metasilicate
Weight: 11.0 PPG YIELD: 3.43 Cu Ft/sk H₂O Req: 21.04 gal/sk

Tail: 50-50 Poz-Class G Cement + 3% KCl + .25 lbs/sk Cello Flake + 2% Bentonite + .3% Sodium Metasilicate
Weight: 14.2 PPG YIELD: 1.59 Cu Ft/sk H₂O Req: 7.88 gal/sk

24. Name & Signature *Mandie Crozier* Title: Regulatory Specialist

Date: 4/22/04

(This space for State use only)

API Number Assigned:

43-013-32579

APPROVAL:

Approved by the
Utah Division of
Oil, Gas and Mining

Date:

By:

*See Instructions On Reverse Side

5. LEASE DESIGNATION AND SERIAL NO.

ML-43538

6. IF INDIAN, ALLOTTEE OR TRIBE NAME

N/A

7. UNIT AGREEMENT NAME

Ashley

8. FARM OR LEASE NAME

Ashley

9. WELL NO.

Ashley State 15-2-9-15

10. FIELD AND POOL OR WILDCAT

Monument Butte

11. QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:

**SW/SE
Sec. 2, T9S, R15E**

12. County

Duchesne

13. STATE

UT

RECEIVED


APR 21 2004


DIV. OF OIL, GAS & MINING

T9S, R15E, S.L.B.&M.

INLAND PRODUCTION COMPANY

WELL LOCATION, ASHLEY UNIT 15-2,
LOCATED AS SHOWN IN THE SW 1/4 SE
1/4 OF SECTION 2, T9S, R15E, S.L.B.&M.
DUCHESE COUNTY, UTAH.



 = SECTION CORNERS LOCATED

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SW)



THIS IS TO CERTIFY THAT THE ABOVE PLAND WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEY
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST OF
MY KNOWLEDGE AND BELIEF.

STACY W.
STEWART

REGISTERED LAND SURVEYOR
REGISTRATION NO. 169377
STATE OF UTAH

TRI STATE LAND SURVEYING & CONSULTING

180 NORTH VERNAL AVENUE - VERNAL, UTAH 84078
(435) 781-2501

SCALE: 1" = 1000'

SURVEYED BY: D.J.S.

DATE: 3-15-04

DRAWN BY: J.R.S.

NOTES:

FILE #

From: Ed Bonner
To: Whitney, Diana
Date: 5/5/2004 11:26:07 AM
Subject: Well Clearance

The following wells have been given cultural resource clearance by the Trust Lands Cultural Resources Group:

Westport Oil & Gas Company
NBU 922-29M
Watts 923-2D
State 1022-36J

Inland Production Company
Ashley State 2-2-9-15
Ashley State 3-2-9-15
Ashley State 4-2-9-15
Ashley State 5-2-9-15
Ashley State 6-2-9-15
Ashley State 7-2-9-15
Ashley State 10-2-9-15
Ashley State 11-2-9-15
Ashley State 12-2-9-15
Ashley State 13-2-9-15
Ashley State 14-2-9-15
Ashley State 15-2-9-15

If you have any questions regarding this matter please give me a call.

CC: Garrison, LaVonne; Hill, Brad; Hunt, Gil

**CULTURAL RESOURCE INVENTORY OF
INLAND RESOURCES' 500 ACRES IN
TOWNSHIP 9S, RANGE 15 E, SECTIONS 2 AND 3,
DUCHESNE COUNTY, UTAH**

by

**Katie Simon
and
Keith R. Montgomery**

Prepared For:

**State of Utah
School and Institutional Trust Lands Administration**

and

**Bureau of Land Management
Vernal Field Office
Vernal, Utah**

Prepared Under Contract With:

**Inland Resources, Inc.
410 17th Street, Suite 700
Denver, CO 80202**

Prepared By:

**Montgomery Archaeological Consultants
P.O. Box 147
Moab, Utah 84532**

MOAC Report NO. 03-83

November 11, 2003

**United States Department of Interior (FLPMA)
Permit No. 03-UT-60122**

**State of Utah Antiquities Project (Survey)
Permit No. U-03-MQ-0751b,s**

ABSTRACT

In August, 2003, a cultural resource inventory of a 500 acre parcel for well development including access roads and pipelines was performed by Montgomery Archaeological Consultants for Inland Production Company. The project area is situated in the Pleasant Valley region of the Uintah Basin, in the Well's Draw vicinity, and consists of one parcel for block survey. The legal description is T 9S, R 15E, Section 2 and the NW 1/4 and SW 1/4, along with the NE 1/4 and SE 1/4 of the NE 1/4 and the NE 1/4 and SE 1/4 of the SE 1/4 of Section 3. A total of 500 acres were inventoried for cultural resources of which 462 acres are located on public lands administered by the Bureau of Land Management (BLM), Vernal Field Office, and 36.5 acres are on State of Utah School and Institutional Trust Lands Administration land.

The archaeological survey resulted in the documentation of thirteen historic temporary camps (42Dc1624, 42Dc1625, 42Dc1626, 42Dc1627, 42Dc1628, 42Dc1629, 42Dc1630, 42Dc1631, 42Dc1632, 42Dc1633, 42Dc1634, 42Dc1635, and 42Dc1636) and one isolated artifact. These thirteen sites represent temporary range camps having a restricted class of cultural materials. The artifacts present at these sites are dominated by tin cans and bottle glass dating from 1903 to the present. Features are limited to thermally altered rock concentrations or hearths, stove platforms, and depleted wood pile remnants. Additional investigations at these sites would fail to provide information relevant to historic research domains of the area as most sites are limited artifact scatters and all thermal features retain minimal integrity and depth potential. In addition, most sites are limited activity range camps, which are common site types in the area. For these reasons, all thirteen sites are recommended as not eligible to the NHRP.

Base on these findings, determination fo "no historic properties affected" is recommended for this project pursuant to Section 106, CFR 800.

TABLE OF CONTENTS

ABSTRACT	i
TABLE OF CONTENTS	ii
LIST OF TABLES	ii
LIST OF FIGURES	ii
INTRODUCTION	1
DESCRIPTION OF PROJECT AREA	3
Cultural Overview	3
SURVEY METHODOLOGY	6
INVENTORY RESULTS	7
Archaeological Sites	7
Isolated Finds of Artifacts	10
NATIONAL REGISTER OF HISTORIC PLACES EVALUATION	10
REFERENCES CITED	12
APPENDIX A: INTERMOUNTAIN ANTIQUITIES COMPUTER SYSTEM (IMACS) SITE FORMS	14

LIST OF TABLE

1. Cultural Resources and NRHP Assessment	11
---	----

LIST OF FIGURE

1. Inventory Area of Inland Resources' 500 Acre Parcel Showing Cultural Resources ...	2
---	---

INTRODUCTION

In August, 2003, a cultural resource inventory of a 500 acre parcel for well development including access roads and pipelines was performed by Montgomery Archaeological Consultants Inc. (MOAC) for Inland Production Company. The project area is situated in the Pleasant Valley region of the Uintah Basin, in the Well's Draw vicinity, and consists of one parcel for block survey. The legal description is T 9S, R 15E, Section 2 and the NW 1/4 and SW 1/4, along with the NE 1/4 and SE 1/4 of the NE 1/4 and the NE 1/4 and SE 1/4 of the SE 1/4 of Section 3 (Figure 1). A total of 500 acres were inventoried for cultural resources of which 462 acres are located on public lands administered by the Bureau of Land Management (BLM), Vernal Field Office, and 36.5 acres are on State of Utah School and Institutional Trust Lands Administration land.

The objective of the inventory was to locate, document and evaluate any cultural resources within the project area pursuant to a determination of "no effect" to historic properties in accord with Section 106 of 36 CFR 800, the National Historic Preservation Act of 1966 (as amended). Also, the inventory was implemented to attain compliance with a number of federal and state mandates, including the National Environmental and Historic Preservation Act of 1969, the Archaeological and Historic Conservation Act of 1972, the Archaeological Resources Protection Act of 1979 and the American Indian Religious Freedom Act of 1978.

The fieldwork was performed between August 8th and 19th by Keith R. Montgomery, Principal Investigator for Montgomery Archaeological Consultants, aided in the field by Greg Woodall and Eli Jones. The inventory was conducted under the auspices of U.S.D.I. (FLPMA) Permit No. 03-UT-60122 and State of Utah Antiquities Project (Survey) No. U-03-MQ-0751b.

A file search for previous projects and documented cultural resources was conducted by Melissa Elkins at the BLM Vernal Field Office on August 7, 2003 and at the Utah State Historic Preservation Office on August 13, 2003. These consultations indicated that one cultural resource inventory has been conducted within the immediate project area. In August 1984, Grand River Consultants, Inc. conducted a survey for an access road to Wells Draw State 4-2. No cultural resources were found (Hartley 1984). In addition, three archaeological projects have been completed in the vicinity. Montgomery Archaeological Consultants (MOAC) completed a survey for Inland Production Company in 2000, in T 9S, R 15E, Sec. 11. Two historic temporary camps (42Dc1319 is one of these), and one isolated find of artifact were documented (Montgomery and Ball 2000). In July, 2001, a cultural resource inventory of a 534 acre parcel for Inland Production Company's Ashley Unit, T9S, R15E, Sec. 10 and 11 was performed by MOAC. This investigation resulted in the documentation of ten historic temporary camps (42Dc1397, 42Dc1398, 42Dc1399, 42Dc1400, 34Dc1401, 42Dc1402, 42Dc1403, 42Dc1404, 42Dc1405, and 42Dc1406), and a previously recorded historic site (42Dc1319). One of these sites (42Dc1403) was recommended as eligible to the NRHP under Criterion (D) and it was recommended that this site be avoided by development (Elkins and Montgomery 2001). In the fall of 2002, MOAC surveyed yet another group of parcels for Inland including Parcel #9, which is located in the eastern half of Section of 11, T9S, R15E. This parcel's inventory resulted in the documentation of the following two sites: 42Dc1530—an historic temporary camp, and 42Dc1531—an historic trash scatter.




Figure 1. Inventory Area of Inland Resources' 500 Acre Parcel Showing Cultural Resources

DESCRIPTION OF PROJECT AREA

Environmental Setting

The project area lies in the Pleasant Valley area of the Uinta Basin, approximately 13 miles south of Myton, Utah. The inventory area consists of a 500 acre parcel, allocated for development of well locations, including access roads and pipelines. The legal description for this parcel is T9S, R15E, Section 2 and the NW 1/4 and SW 1/4, along with the NE 1/4 and SE 1/4 of the NE 1/4 and the NE 1/4 and SE 1/4 of the SE 1/4 of Section 3 (Figure 1). Topographically, this area consists of highly dissected sandstone and mudstone rock formations and broad sandy silt ridges (Stokes 1986). The elevation ranges from 5910 to 6100 asl. Wells Draw, a broad southerly-flowing drainage with sandstone and siltstone rimrock formations to the north and low terraces to the south, lies east of the project area. The project area lies within the Upper Sonoran life zone, dominated by a shadscale community intermixed with Shadscale, small rabbitbrush, galleta grass, blue gamma grass, winter fat, spiny horsebrush, globemallow, prickly pear, greasewood, buckwheat, and sand verbena. A riparian zone exists along the washes, and includes cottonwood, Russian olive, cattail, and tamarisk. Modern disturbances to the landscape include well locations, access roads, pipelines, and livestock grazing.

Cultural Overview

The cultural-chronological sequence represented in the study area includes the Paleoindian, Archaic, Fremont, Protohistoric, and Euro-American stages. The earliest inhabitants of the region are representative of the Paleoindian stage (ca. 12,000-8,000 B.P.). This stage is characterized by the adaptation to terminal Pleistocene environments and by the exploitation of big game fauna. The presence of Paleoindian hunters in the Uinta Basin region is implied by the discovery of Clovis and Folsom fluted points (ca. 12,000 B.P. - 10,000 B.P.), as well as the more recent Plano Complex lanceolate points (ca. 10,000 B.P. - 7,000 B.P.). However, no such artifacts have been recovered in stratigraphic or chronometrically controlled contexts in northeastern Utah.

The Archaic stage (ca. 8,000 B.P. - 1,500 B.P.) is characterized by peoples depending on a foraging subsistence strategy, seasonally exploiting a wide spectrum of plant and animal species in different ecozones. The shift to an Archaic lifeway was marked by the appearance of new projectile point types perhaps reflecting the development of the atlatl in response to a need to pursue smaller and faster game (Holmer 1986). In the Uinta Basin, evidence of widespread Early Archaic exploitation is relatively sparse compared to the subsequent Middle and Late Archaic periods. Early Archaic (ca. 6000-3000 B.C.) sites in the basin include sand dune sites and rockshelters clustered mainly in the lower White River drainage as well as along the Green River in the Browns Park and Flaming Gorge (Spangler 1995:373). Projectile points recovered from Uinta Basin contexts include Pinto Series, Humboldt, Elko Series, Northern Side-notched, Hawken Side-notched, Sudden Side-notched and Rocker Base Side-notched points. Excavated sites in the area with Early Archaic components include Deluge Shelter in Dinosaur National Monument, and open campsites along the Green River and on the Diamond Mountain plateau (Spangler 1995:374). The Middle Archaic period (ca. 3000-500 B.C.) is characterized by improved climatic conditions and increased human populations on the northern Colorado Plateau. Several stratified Middle Archaic

sites have been excavated and dozens of sites have been documented in the Uinta Basin. Middle Archaic sites in the area reflect cultural influences from the Plains, although a Great Basin and/or northern Colorado Plateau influence is represented in the continuation of the Elko Series projectile points. Subsistence data from Middle Archaic components indicate gathering and processing of plants as well as faunal exploitation (e.g., mule deer, antelope, bighorn sheep, cottontail rabbit, muskrat, prairie dog, beaver and birds). The Late Archaic period (ca. 500 B.C.-A.D. 550) in the Uinta Basin is distinguished by the continuation of Elko Series atlatl points with the addition of semi-subterranean residential structures at base camps. By about A.D. 100, maize horticulture and Rose Springs arrow points had been added to the Archaic lifeway. In the Uinta Basin, the earliest evidence of Late Archaic architecture occurs at the Cocklebur Wash Site (42Un1476) where a temporary structure, probably a brush shelter, yielded a date of 316 B.C. The structure was probably associated with seasonal procurement of wild floral resources gathered along Cliff Creek.

The Formative stage (A.D. 500-1300) is recognized in the area by the Uinta Fremont as first termed by Marwitt (1970). This stage is characterized by reliance upon domesticated corn and squash, increasing sedentism, and in its later periods, substantial habitation structures, pottery, and bow and arrow weapon technology. Based on the evidence from Caldwell Village, Boundary Village, Deluge Shelter, Mantles Cave and others, the temporal range of the Uinta Fremont appears to be from A.D. 650 to 950. This variant is characterized by shallow, saucer-shaped pithouse surface structures with randomly placed postholes and off-center firepits, some of which were adobe-rimmed. Traits considered unique or predominate to the Uinta Basin include calcite-tempered pottery, two-handled wide-mouth vessels, Utah type metates, the use of gilsonite for pottery repair, settlement on tops of buttes and large-shouldered bifaces (Shields 1970).

Archaeological evidence suggests that Numic peoples appeared in east-central Utah at approximately A.D. 1100 or shortly before the disappearance of Formative-stage peoples (Reed 1994). The archaeological remains of Numic-speaking Utes consist primarily of lithic scatters with low quantities of brown ware ceramics, rock art, and occasional wickiups. The brown ware ceramics appear to be the most reliable indicator of cultural affiliation, as Desert Side-notched and Cottonwood Triangular points were manufactured by other cultural groups beside the Ute (Horn, Reed, and Chandler 1994:130). The Ute appear to have been hunter and gatherers exploiting various fauna and flora resources. According to macrobotanical and faunal data from dated components deer, elk, pronghorn, bison, and small game were acquired (Reed 1994:191). Plant materials thought to have been exploited for food include goosefoot, grass seeds, pinyon nuts, juniper berries, squawbush berries and leaves, hackberry seeds and possibly saltbush seeds, knotweed, chokecherry, and chickweed (Ibid 191).

The cultural history of the Eastern Ute, comprising the bands living east of the Green River, has been divided into four phases (Reed 1988). The earliest and most tenuous phase is the Chipeta Phase, dated between ca. 1250 and 1400. Diagnostic artifacts include Desert Side-notched, Cottonwood Triangular, and small corner-notched arrow points and possibly Shoshonean knives. The Canalla phase (ca. A.D. 1400-1650) designates the period between the appearance of well-dated Uncompahgre brown ware ceramics and the adoption of an equestrian lifeway. Diagnostic artifacts include Uncompahgre Brown Ware ceramics, Desert Side-notched and Cottonwood Triangular points, and Shoshonean knives. The pedestrian hunter and gatherers probably lived in wickiups. Near the end of the phase, some groups may have obtained trade items from Spanish settlements in New Mexico (Horn, Reed, and Chandler 1994:131). The Antero phase (ca. A.D. 1650-1881) represents a shift to a fully equestrian lifestyle and integration of

Euroamerican trade goods into Ute material culture. The horse permitted hunting of bison on the Plains and led to an increase in the importance of raiding for economic gain (Ibid 131). Euroamerican trade goods became important, and tepees as well as wickiups were inhabited. The early Utes in Uintah County were Uinta-ats, a small band of a few hundred members (Burton 1996:20). In pre-horse days, Ute family groups lived largely independently of others with key gathering, hunting, and fishing sites being communal and granted to all, within both the local and extralocal Ute communities (Ibid 340). According to Smith's (1974) informants both deer and buffalo were important game for the White River Ute band. Before the buffalo became extinct in the Uintah Basin in the 1830s, the Ute would make trips northeast of Fort Bridger in the vicinity of what is now Rock Springs and Green River, Wyoming using the horse to surround and drive the buffalo over a precipice (Callaway, Janetski, and Stewart 1986; Smith 1974). All Ute groups made tripod or conical houses with a three or four-pole foundation and a circular ground plan some 10 to 15 feet in diameter with covering brush or bark.

The first Euro-Americans in the Uinta Basin were Spanish missionaries, traveling between Santa Fe, New Mexico up through western Colorado, towards the Utah Valley, and on to California. In 1776, under the leadership of Fray Francisco Atanasio Dominguez and Fray Silvestre Velez de Escalante, the Spanish commenced to explore a northern route from Santa Fe to the garrison of Monterey on the California coast (Spangler et al. 1995). Euro-American traders were another early factor in the history of the Uinta Basin. Some of these were Spaniards, who continued to visit the region until the Mexican war of independence in 1821, when most Spanish were expelled from the Southwest. It was the beaver trade in the early part of the nineteenth century, that cemented trade with Ute and Shoshone in the area, and resulted in the establishment of trading posts along the major rivers in the area, including the Duchesne, Green, and Uinta (Spangler et al. 1995).

The settlement of the Uinta Basin differs from that of much of Utah in that early settlement in the area occurred around Indian "agencies" assigned to the Uinta and Ouray Reservations, rather than under the direction of the Mormon church (Spangler et al. 1995). These agencies consisted of cabins and a trading post with farms cropping up around the agency, and were directed by a government Indian agent. The first agency was constructed at the mouth of Daniels Canyon in 1864, and was moved several times before 1868. The Mormon church, under Brigham Young consigned survey parties to the Uinta Basin in the early 1860s, determining that the land was not very suitable for cultivation. For this reason, Mormon occupation of the area occurred later than in many parts of the state. By 1876, only a handful of ranchers, had settled the area, to be joined that year by a group of Mormons. They formed a settlement around the ranch of Pardon Dodds, an Indian agent, located in Dry Fork Canyon; later to become known as Old Ashley Town (Burton 1996). Another small group of Mormon settlers arrived in 1878, camping near the confluence of Ashley Creek, and naming their settlement Incline. In 1878, additional Mormon settlers ventured into the area; locating near what is today Vernal. With agrarian pursuits being the focus of the majority of the Mormon communities in the region, water became a leading priority. In 1880 the Rock Point Canal and Irrigation Company built a six-mile long canal from the mouth of Ashley Canyon to various homesteads in the region. The Ashley Upper Irrigation Canal was constructed in 1880 with the purpose of yielding water from the Ashley Creek to Bingham Corner. Settlement increased rapidly, and many different water projects were initiated. Most of the canals and reservoirs in the region were built after 1905 by the Uintah Irrigation Project and the Dry Gulch Irrigation Company (Spangler et al. 1995).

SURVEY METHODOLOGY

An intensive pedestrian survey was performed for this project which is considered 100% coverage. The 500 acre parcel was examined for cultural resources by the archaeologists walking parallel transects spaced no more than 15 m apart. Ground visibility was considered good. A total of 500 acres were inventoried for cultural resources of which 462 acres are located on public lands administered by the Bureau of Land Management (BLM), Vernal Field Office, and 36.5 acres are on State of Utah School and Institutional Trust Lands Administration land.

Cultural resources were recorded as an archaeological site or isolated find of artifacts. Archaeological sites were defined as spatially definable areas with features and/or ten or more artifacts. Sites were documented by the archaeologists walking transects across the site, spaced no more than 3 m apart, and marking the locations of cultural materials with pinflags. This procedure allowed clear definition of site boundaries and artifact concentrations. At the completion of the surface inspection, a Trimble Geo XT Global Positioning System (GPS) and/or a Brunton compass was employed to point-provenience diagnostic artifacts and other relevant features in reference to the site datum, a steel rebar stamped with a temporary site number. Archaeological sites were plotted on a 7.5' USGS quadrangle, photographed, with site data entered on an Inter-mountain Antiquities Computer System (IMACS, 1990 version) inventory form (Appendix A). Isolated finds are defined as individual artifacts or light scatter of items, which lack sufficient material culture to warrant IMACS forms, or to derive interpretation of human behavior in a cultural and temporal context. No isolated artifacts were found during the cultural inventory for this project.

INVENTORY RESULTS

The archaeological survey resulted in the documentation of thirteen historic temporary camps (42Dc1624, 42Dc1625, 42Dc1626, 42Dc1627, 42Dc1628, 42Dc1629, 42Dc1630, 42Dc1631, 42Dc1632, 42Dc1633, 42Dc1634, 42Dc1635, and 42Dc1636) and the recordation of one isolated find (IF-A).

Archaeological Sites

Smithsonian Site No.: 42Dc1624

Temporary Site No.: 03-83-12

Eligibility: Not Eligible

Description: This is a temporary historic range camp situated on a finger ridge overlooking a major drainage. It measures 80 by 20 meters (1257 sq. m). The site consists of one wood pile feature and an artifact scatter including one sanitary can, two matchstick filler cans (ca. 1935-1945 and 1915-1930), a rifle cartridge with "REM_UMC 30-30", two hay bail wire pieces, and one tobacco tin.

Smithsonian Site No.: 42Dc1625

Temporary Site No.: 03-83-14

Eligibility: Not Eligible

Description: This is a temporary historic camp situated on a narrow ridge with drainages bordering it to the north and south. It measures 180 by 90 meters (12723 sq. m) and consists of two wood pile features and one stove platform feature along with an artifact scatter. The artifact scatter includes 13 matchstick filler cans with dates ranging from 1915-1975, 15 non-diagnostic sanitary commodity cans, two spice cans, eight external friction, vertical pocket tobacco tins, one lid fragment, 12 can fragments, one screw-top jar lid, one enamel plate, one metal buckle, a harness, and three galvanized washtub fragments.

Smithsonian Site No.: 42Dc1626

Temporary Site No.: 03-83-11

Eligibility: Not Eligible

Description: This is a short-term range camp situated on a dissected ridge line and is composed of an artifact scatter and two wood pile features. The site measures 40 by 20 (628 sq. m). Artifacts include one purple medicine bottle, eight matchstick filler cans, six hole-in-cap cans, and five sanitary cans. These cans date from 1903 (1 1/16" dia. cap hole-in-cap) to 1975 (3 15/16" tall matchstick filler). There are two external friction, wire hinged lid tobacco tins, one external friction baking powder lid (2 5/16 dia.), lard bucket, one external friction 6" dia. coffee can lid, four tin can fragments, and three hay bail wire fragments.

Smithsonian Site No.: 42Dc1627

Temporary Site No.: 03-83-9

Eligibility: Not Eligible

Description: This is a temporary historic range camp situated below a ridge and on a gently sloping bench overlooking a drainage. It measures 25 by 20 meters (393 sq.m). The site consists of one sanitary can, two matchstick filler "Punch Here" cans (ca. 1935-1945), and one wood pile feature (F1).

Smithsonian Site No.: 42Dc1628
Temporary Site No.: 03-83-8
Eligibility: Not Eligible

Description: This is a temporary historic range camp situated on a low ridge top area with three small drainages. It measures 40 by 60 (1885 sq. m) and consists of deteriorated wood pile feature (F1) and an artifact scatter that includes one sanitary can, one matchstick filler can, 11 can fragment, six pieces of bailing wire, one leather fragment, and one unmarked crown bottle cap. This site is located approximately 30 meters northwest of 42Gr1629, a historic artifact scatter.

Smithsonian Site No.: 42Dc1629
Temporary Site No.: 03-83-7
Eligibility: Not Eligible

Description: This site is situated on a ridge top area and consists of an historic artifact scatter six milk cans embossed with "Punch Here," two tobacco tins, two sanitary cans, a coffee can, one spice can, and wood fragments from a broken crate, and a broom handle. The site measures 40 by 80 meters (2513 sq. m).

Smithsonian Site No.: 42Dc1630
Temporary Site No.: 03-83-5
Eligibility: Not Eligible

Description: This site is situated in an area of low dissected ridges and consists of approximately 35 historic trash items and the remains of a wood pile (F1). It measures 80 by 50 meters (3146 sq. m). Observed artifacts include 15 fragments of a clear jar, two lantern glass fragments, one hay bale wire tie, two pry out friction can lids, one crimped seam can with an internal friction lid, two shirt pocket tobacco tins (wire hinge/cap over type), one sanitary can and eleven milk cans. The occupation appears to date between 1910 and 1921.

Smithsonian Site No.: 42Dc1631
Temporary Site No.: 03-83-4
Eligibility: Not Eligible

Description: This is a range camp situated on a low dissected ridge on flat bench lands and consists of a small historic artifact scatter and four features. It measures 120 by 60 meters (5655 sq. m). The features consist of one wood pile (F1), one stone stove platform (F4), and a small and a large deflated hearth. The artifact scatter includes 21 milk cans (five of which are "Punch Here" embossed milk cans), seven sanitary food cans, 14 wire ties (hay bale), metal strap fragment, metal button ("HAWK BRAND" with embossed bird figure), a sanitary can lid, two galvanized wash tub fragments, 30 clear glass fragments, five tobacco tins (shirt pocket, wire hinge with cap over), metal buckle/slider, three horseshoe nails, galvanized wash tub ("3"), galvanized wash tub (no embossing), two suspender strap clasps, and wood chips. The site is assessed to date between 1915 and 1945.

Smithsonian Site No.: 42Dc1632
Temporary Site No.: 03-83-6
Eligibility: Not Eligible

Description: This is a limited activity historic site situated on a small bench in a drainage in the Uinta Basin. It measures 20 by 40 m (628 sq. m) and consists of an artifact scatter of eight hole-in-cap, four sanitary cans, one cut around lid and a 30 cm. long wood chunk. The 4 6/16" tall, 1" cap diameter milk can dates between 1903 and 1914.

Smithsonian Site No.: 42Dc1633
Temporary Site No.: 03-83-10
Eligibility: Not Eligible

Description: This site is a temporary historic camp situated on a low ridge. It measures 40 by 20 meters (628 sq. m). The site consists of an artifact scatter including 15 sanitary cans, 15 matchstick filler cans, one hole-in-cap milk can, one lard bucket and various lids. The earliest and latest dates for the can scatter and the entire site are 1903 (hole-in-cap) and 1970 (matchstick filler 3 15/16) based on milk can chronology. All other diagnostics fall between these with the majority of milk cans and both glass bottles dating 1933-1970 with overlapping dates of 1935-1945. Exceptions are the hole-in-cap can and one milk can, which fall outside this period at 1903-1908 and 1915-1930 respectively. There is one clear glass liquor bottle (ca. 1933-1954), and four clear glass jug fragments (ca. 1940). Other artifacts include three bailing wire fragments, a harness rigging fragment (chain links and leather), rubber tire fragments, and two galvanized wash tubs. Five features were observed including three wood piles (F1, F2, and F4) of varying sizes and two stove platform features (F2 and F5) of thermally altered, local sandstone slabs. No surficial soil staining or charcoal was observed in F2 or F5. Stove platform F3 and wood pile F4 are situated near each other near the center of the site area.

Smithsonian Site No.: 42Dc1634
Temporary Site No.: 03-83-1
Eligibility: Not Eligible

Description: This is a limited activity range camp situated on a low dissected ridge among flat bench lands and consists of a small historic artifact scatter and possible hearth area. It measures 20 by 40 meters (628 sq. m). Artifacts consists of one 1915-1930 milk can and a purple glass fragment.

Smithsonian Site No.: 42Dc1635
Temporary Site No.: 03-83-2
Eligibility: Not Eligible

Description: This is a temporary range camp located on a broad, flat ridge top and consists of a small historic artifact scatter and wood pile feature. The site measures 30 by 52 meters (1225 sq. m). Artifacts include two matchstick filler milk cans, one of which is a 1935-1945 "Punch Here" embossed can.

Smithsonian Site No.: 42Dc1636
Temporary Site No.: 03-83-3
Eligibility: Not Eligible

Description: This is a limited activity range camp situated on a flat ridge overlooking several drainages. It measures 20 by 10 meters (157 sq. m) and consists of one milk can, one hay bale wire and tie, and a wood pile feature. The occupation appears to date between 1930 and 1975.

Isolated Find of Artifact

The Isolated Find A (IF-A) is located in the NE/SW/SW of Section 2, T9S, R15E; UTM 567826E/4433982N. It is a brown opaque chert knife base fragment with black inclusions in the material (4.3 x 3.2 x 0.6 cm).

NATIONAL REGISTER OF HISTORIC PLACES EVALUATION

The National Register Criteria for Evaluation of Significance and procedures for nominating cultural resources to the National Register of Historic Places (NRHP) are outlined in 36 CFR 60.4 as follows:

The quality of significance in American history, architecture, archaeology, and culture is present in districts, sites, buildings, structures, and objects of State and local importance that possess integrity of location, design, setting, material, workmanship, feeling, and association, and that they:

- a)...are associated with events that have made a significant contribution to the broad patterns of our history; or
- b)...are associated with the lives of persons significant to our past; or
- c)...embody the distinctive characteristics of a type, period, or method of construction; or that represents the work of a master, or that possess high artistic values, or that represent a significant and distinguishable entity whose components may lack individual distinction; or
- d)...have yielded or may be likely to yield information important in prehistory or history.

The thirteen sites (42Dc1624, 42Dc1625, 42Dc1626, 42Dc1627, 42Dc1628, 42Dc1629, 42Dc1630, 42Dc1631, 42Dc1632, 42Dc1633, 42Dc1634, 42Dc1635, and 42Dc1636) represent temporary range camps having a restricted class of cultural materials. The diagnostic artifacts present at these sites are dominated by tin cans and bottle glass dating from 1903 to the present. Features are limited to thermally altered rock concentrations or hearths, stove platforms, and depleted wood pile remnants. Additional investigations at these sites would fail to provide information relevant to historic research domains of the area as most sites are limited artifact scatters and all thermal features retain minimal integrity and depth potential. In addition, most sites are limited activity range camps, which are common site types in the area. For these reasons, all thirteen sites are recommended as not eligible to the NHRP.

Table 1. Cultural Resources and NRHP Assessment

Site Number	Legal Description	Site Type	NRHP Assessment
42Dc1624	NE/NW/NE of Sec. 2, T9S, R15E	Temporary Camp	Not Eligible
42Dc1625	NE/NE/NW of Sec. 2, T9S, R15E	Temporary Camp	Not Eligible
42Dc1626	SE/NW/NW of Sec. 2, T9S, R15E	Temporary Camp	Not Eligible
42Dc1627	SE/SW/NW of Sec. 2, T9S, R15E	Temporary Camp	Not Eligible
42Dc1628	SW/SW/NE of Sec. 2, T9S, R15E	Temporary Camp	Not Eligible
42Dc1629	SE/SW/NE, SW/SW/NE, NW/NW/SE, NE/NW/SE of Sec. 2, T9S, R15E	Can Scatter	Not Eligible
42Dc1630	SW/NW/SE of Sec. 2, T9S, R15E	Temporary Camp	Not Eligible
42Dc1631	NW/SE/SW of Sec. 2, T9S, R15E	Temporary Camp	Not Eligible
42Dc1632	SE/NE/SE of Sec. 3, T9S, R15E	Can Scatter	Not Eligible
42Dc1633	NW/SE/SW of Sec. 2, T9S, R15E	Temporary Camp	Not Eligible
42Dc1634	SE/SW/SE, NW/SW/SE of Sec. 2, T9S, R15E	Temporary Camp	Not Eligible
42Dc1635	NE/SW/SW of Sec. 2, T9S, R15E	Temporary Camp	Not Eligible
42Dc1636	NW/SW/SW of Sec. 2, T9S, R15E	Temporary Camp	Not Eligible

REFERENCES CITED

- Burton, D.K.
1996 *A History of Uintah County*. Utah State Historical Society, Uintah County Commission.
- Callaway, D., J. Janetski, and O.C. Stewart
1986 Ute. In *Great Basin*, edited by Warren L. D'Azevedo, pp. 336-367. Handbook of North American Indians, Volume II: Great Basin, edited by William C. Sturtevant, Smithsonian Institution, Washington
- Elkins, M. and K.R. Montgomery
2001 Cultural Resource Inventory of Inland's Ashley Unit, T9S, R15E, Sections 10 and 11, Duchesne County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Report No. U-01-MQ-0445b.
- Hartley, J.D.
1984 Archaeological Survey for Lomax Exploration Company's Antelope Canyon 6-23 Duchesne County, Utah. Grand River Consultants, Inc., Grand Junction, Colorado. Report No. U-84-12-0225b.
- Holmer, R.
1986 Projectile Points of the Intermountain West. In *Anthropology of the Desert West: Essays in Honor of Jesse D. Jennings*, edited by Carol J. Condie and Don D. Fowler, pp. 89-116. *University of Utah Anthropological Papers* No. 110. Salt Lake City.
- Horn, J.C., A.D. Reed, and S.M. Chandler
1994 Grand Resource Area Class I Cultural Resource Inventory. Alpine Archaeological Consultants, Inc. Montrose. Bureau of Land Management, Moab, Utah.
- Marwitt, J.P.
1970 Median Village and Fremont Culture Regional Variation. *University of Utah Anthropological Papers* No. 95. Salt Lake City.
- Montgomery, K.R. and S. Ball
2000 Cultural Resource Inventory of Inland Production Company's Wells Draw 320 Acre Parcel in Township 9S, Range 15E, Section 11, Duchesne County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Report No. U-00-MQ-0610b.

- Reed A.D.
1988 Ute Cultural Chronology. In Archaeology of the Eastern Ute: A Symposium edited by Paul R. Nickens, pp 79-101. Colorado Council of Professional Archaeologists Occasional Papers No. 1. Denver.
- 1994 The Numic Occupation of Western Colorado and Eastern Utah during the Prehistoric and Protohistoric Periods. In *Across the West: Human Population Movement and the Expansion of the Numa*, edited by D.B. Madsen and D. Rhode, pp. 188-199. University of Utah Press, Salt Lake City.
- Shields, W.F.
1970 The Fremont Culture in the Uinta Basin. Paper presented at the Fremont Culture Symposium, 35th Annual Meeting of the Society for American Archaeology, Mexico City.
- Smith, A.M.
1974 *Ethnography of the Northern Utes*. Papers in Anthropology No. 17. Museum of New Mexico Press.
- Spangler, J.D., M. Rands and S.A. Bilbey
1995 Paradigms and Perspectives, A Class I Overview of Cultural Resources in the Uinta Basin and Tavaputs Plateau, Volume II. Uinta Research, Salt Lake City, Utah.
- Stokes, W.L.
1986 *Geology of Utah*. Utah Museum of Natural History, University of Utah, Salt Lake City.

APPENDIX A

**INTERMOUNTAIN ANTIQUITIES COMPUTER SYSTEM (IMACS)
SITE INVENTORY FORMS**

On File At:

**Utah Division of State History
Salt Lake City, Utah**

and

**U.S. Bureau of Land Management
Vernal Field Office**

INLAND PRODUCTION COMPANY
ASHLEY STATE 15-2-9-15
SW/SE SECTION 2, T9S, R15E
DUCHESNE COUNTY, UTAH

TEN POINT DRILLING PROGRAM

1. **GEOLOGIC SURFACE FORMATION:**

Uinta formation of Upper Eocene Age

2. **ESTIMATED TOPS OF IMPORTANT GEOLOGIC MARKERS:**

Uinta	0 – 1700'
Green River	1700'
Wasatch	6500'

3. **ESTIMATED DEPTHS OF ANTICIPATED WATER, OIL, GAS OR MINERALS:**

Green River Formation 1700' – 6500' – Oil

4. **PROPOSED CASING PROGRAM:**

Surface Casing: 8-5/8" J-55 24# w/ST&C collars; set at 290' (New)

Production Casing: 5-1/2" J-55, 15.5# w/LT&C collars; set at TD (New or used, inspected).

5. **MINIMUM SPECIFICATIONS FOR PRESSURE CONTROL:**

The operator's minimum specifications for pressure control equipment are as follows:

An 8" Double Ram Hydraulic unit with a closing unit will be utilized. Function test of BOP's will be check daily.

Refer to **Exhibit C** for a diagram of BOP equipment that will be used on this well.

6. **TYPE AND CHARACTERISTICS OF THE PROPOSED CIRCULATION MUDS:**

The well will be drilled with air mist system to 3200', then from 3200' +/- to TD a fresh water/polymer system will be utilized. If necessary, to control formation fluids, the system will be weighted with the addition of bentonite gel, and if conditions warrant, barite. This fresh water system typically will contain Total Dissolved Solids (TDS) of less than 3000 PPM. Neither potassium chloride nor chromates will be utilized in the fluid system. The anticipated mud weight is 8.4 ppg and weighted as necessary for gas control.

AIR DRILLING

In the event that the proposed location is to be "Air Drilled", Inland requests a variance to regulations requiring a straight run blooie line. Inland proposes that the flowline will contain two (2) 90-degree turns. Inland also requests a variance to regulations requiring an automatic igniter or continuous pilot light on the blooie line. Inland requests authorization to ignite as needed, and the flowline at 80'.

Inland Production Company requests that the spark arrest, exhaust, or water cooled exhaust be waived under the Special Drilling Operations of Onshore Order #2.

MUD PROGRAM

Surface – 3200’
3200’ – TD’

MUD TYPE

fresh water or air/mist system
fresh water system

From surface to \pm 3200 feet will be drilled with either fresh water or an air/mist system, depending on the drilling contractor's preference. From about 3200 feet, or in the case of the air/mist system when hole conditions dictate, to TD, a fresh water system will be utilized. Clay inhibition and hole stability will be achieved with a KCL substitute additive. This fresh water system will typically contain Total Dissolved Solids (TDS) of less than 3000 PPM. Anticipated mud weight is 8.4 lbs/gal. If necessary to control formation fluids or pressure, the system will be weighted with the addition of bentonite gel, and if pressure conditions warrant, with barite. No chromate additives will be used in the mud system.

7. **AUXILIARY SAFETY EQUIPMENT TO BE USED:**

Auxiliary safety equipment will be a Kelly Cock, bit float, and a TIW valve with drill pipe threads.

8. **TESTING, LOGGING AND CORING PROGRAMS:**

The logging program will consist of a Dual Induction, Gamma Ray and Caliper log from TD to base of surface casing @ 290’ +/-, and a Compensated Neutron-Formation Density Log from TD to 3500’ +/- . A cement bond log will be run from PBTD to cement top. No drill stem testing or coring is planned for this well.

9. **ANTICIPATED ABNORMAL PRESSURE OR TEMPERATURE:**

The anticipated maximum bottom hole pressure is 2000 psi. It is not anticipated that abnormal temperatures will be encountered; or that any other abnormal hazards such as H₂S will be encountered in this area.

10. **ANTICIPATED STARTING DATE AND DURATION OF THE OPERATIONS:**

It is anticipated that the drilling operations will commence the second quarter of 2004, and take approximately seven (7) days from spud to rig release.

INLAND PRODUCTION COMPANY
ASHLEY STATE 15-2-9-15
SW/SE SECTION 2, T9S, R15E
DUCHESNE COUNTY, UTAH

THIRTEEN POINT SURFACE PROGRAM

1. EXISTING ROADS

See attached **Topographic Map "A"**

To reach Inland Production Company well location site Ashley State 15-2-9-15 located in the SW¼ SE¼ Section 2, T9S, R15E, S.L.B. & M., Duchesne County, Utah:

Proceed in a southwesterly direction out of Myton, Utah along Highway 40 approximately 1.6 miles to the junction of this highway and Utah State Highway 53; proceed southerly along Utah State Highway 53 approximately 1.8 miles to its junction with State Highway 216, proceed in a southwesterly direction for another 8.1 miles to its junction with an existing road to the southwest; proceed southwesterly approximately 2.9 miles to its junction with an existing road to the northwest; proceed northwesterly and then northeasterly approximately 1.7 miles to its junction with the beginning of the proposed access road to the east; proceed easterly along the proposed access road approximately 429' to the proposed well location.

The highways mentioned in the foregoing paragraph are bituminous surfaced roads to the point where Highway 216 exists to the South, thereafter the roads are constructed with existing materials and gravel. The highways are maintained by Utah State road crews. All other roads are maintained by County crews.

The aforementioned dirt oil field service roads and other roads in the vicinity are constructed out of existing native materials that are prevalent to the existing area they are located in and range from clays to a sandy-clay shale material.

The roads for access during the drilling, completion and production phase will be maintained at the standards required by the State of Utah, or other controlling agencies. This maintenance will consist of some minor grader work for smoothing road surfaces and for snow removal.

2. PLANNED ACCESS ROAD

Approximately 429' of access road is proposed. See attached **Topographic Map "B"**.

The proposed access road will be an 18' crown road (9' either side of the centerline) with drainage ditches along either side of the proposed road whether it is deemed necessary in order to handle any run-off from normal meteorological conditions that are prevalent to this area. The maximum grade will be less than 8%.

There will be no culverts required along this access road. There will be barrow ditches and turnouts as needed along this road.

There are no fences encountered along this proposed road. There will be no new gates or cattle guards required.

All construction material for this access road will be borrowed material accumulated during construction of the access road.

3. **LOCATION OF EXISTING WELLS**

Refer to **EXHIBIT B**.

4. **LOCATION OF EXISTING AND/OR PROPOSED FACILITIES**

It is anticipated that this well will be a producing oil well.

There will not be a tank battery at this location. A Central Battery will be located at the proposed Ashley State 10-2-9-15 location.

The Flow Lines from this well will run along access roads leading to the Central Battery located at the proposed Ashley State 10-2-9-15 location. **See attached Topographic Map "D"**.

All permanent (on site for six (6) months or longer) structures, constructed or installed (including pumping units), will be painted Desert Tan. All facilities will be painted within six months of installation.

5. **LOCATION AND TYPE OF WATER SUPPLY**

Fresh water purchased from the Johnson Water District will be used for drilling. A temporary poly pipeline may be used for water transportation from our existing supply line from Johnson Water District, or trucked from Inland Production Company's injection facilities – **EXHIBIT A**.

There will be no water well drilled at this site.

6. **SOURCE OF CONSTRUCTION MATERIALS**

All construction material for this location shall be borrowed material accumulated during construction of the location site and access road.

A mineral material application is not required for this location.

7. **METHODS FOR HANDLING WASTE DISPOSAL**

A small reserve pit (90' x 40' x 8' deep, or less) will be constructed from native soil and clay materials. The reserve pit will receive the processed drill cutting (wet sand, shale & rock) removed from the wellbore. Any drilling fluids, which do accumulate in the pit as a result of shale-shaker carryover, cleaning of the sand trap, etc., will be promptly reclaimed. All drilling fluids will be fresh water based, typically containing Total Dissolved Solids of less than 3000 PPM. No potassium chloride, chromates, trash, debris, nor any other substance deemed hazardous will be placed in this pit. Therefore, it is proposed that no synthetic liner be required in the reserve pit. However, if upon constructing the pit there is insufficient fine clay and silt present, a liner will be used for the purpose of reducing water loss through percolation.

Inland requests approval that a flare pit not be constructed or utilized on this location.

A portable toilet will be provided for human waste.

A trash basket will be provided for garbage (trash) and hauled away to an approved disposal site at the completion of the drilling activities.

Immediately upon first production, all produced water will be confined to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte,

Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Inland's secondary recovery project.

Water not meeting quality criteria, is disposed at Inland's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.

8. **ANCILLARY FACILITIES:**

There are no ancillary facilities planned for at the present time and none foreseen in the near future.

9. **WELL SITE LAYOUT:**

See attached Location Layout Sheet.

Fencing Requirements

All pits will be fenced according to the following minimum standards:

- a) A 39-inch net wire shall be used with at least one strand of barbed wire on top of the net.
- b) The net wire shall be no more than two (2) inches above the ground. The barbed wire shall be three (3) inches above the net wire. Total height of the fence shall be at least forty-two (42) inches.
- c) Corner posts shall be centered and/or braced in such a manner to keep tight at all times
- d) Standard steel, wood or pipe posts shall be used between the corner braces. Maximum distance between any two posts shall be no greater than sixteen (16) feet.
- e) All wire shall be stretched, by using a stretching device, before it is attached to the corner posts.

The reserve pit fencing will be on three (3) sides during drilling operations and on the fourth side when the rig moves off location. Pits will be fenced and maintained until cleanup.

10. **PLANS FOR RESTORATION OF SURFACE:**

a) **Producing Location**

Immediately upon well completion, the location and surrounding area will be cleared of all unused tubing, equipment, debris, material, trash and junk not required for production.

The reserve pit and that portion of the location not needed for production facilities/operations will be recontoured to the approximated natural contours. Weather permitting, the reserve pit will be reclaimed within one hundred twenty (120) days from the date of well completion. Before any dirt work takes place, the reserve pit must have all fluids and hydrocarbons removed.

b) **Dry Hole Abandoned Location**

At such time as the well is plugged and abandoned, the operator shall submit a subsequent report of abandonment and the State of Utah will attach the appropriate surface rehabilitation conditions of approval.

11. **SURFACE OWNERSHIP:** State of Utah

12. **OTHER ADDITIONAL INFORMATION:**

- a) Inland Production Company is responsible for informing all persons in the area who are associated with this project that they will be subject to prosecution for knowingly disturbing historic or archaeological sites, or for collecting artifacts. If historic or archaeological materials are uncovered during construction, Inland is to immediately stop work that might further disturb such materials and contact the Authorized Officer.
- b) Inland Production will control noxious weeds along rights-of-way for roads, pipelines, well sites or other applicable facilities. On State administered land it is required that a Pesticide Use Proposal shall be submitted and given approval prior to the application of herbicides or other possible hazardous chemicals.
- c) Drilling rigs and/or equipment used during drilling operations on this well site will not be stacked or stored on State Lands after the conclusion of drilling operations or at any other time without State authorization. However, if State authorization is obtained, it is only a temporary measure to allow time to make arrangements for permanent storage on commercial facilities.

The Archaeological Cultural Resource Survey for this area is attached.

Additional Surface Stipulations

All lease and/or unit operations will be conducted in such a manner that full compliance is made with all applicable laws and regulations, Onshore Oil and Gas Orders, the approved plan of operations and any applicable Notice to Lessees. A copy of these conditions will be furnished to the field representative to ensure compliance.

Hazardous Material Declaration

Inland Production Company guarantees that during the drilling and completion of the Ashley State 15-2-9-15, Inland will not use, produce, store, transport or dispose 10,000# annually of any of the hazardous chemicals contained in the Environmental Protection Agency's consolidated list of chemicals subject to reporting under Title III Superfund Amendments and Reauthorization Act (SARA) of 1986. Inland also guarantees that during the drilling and completion of the Ashley State 15-2-9-15 Inland will use, produce, store, transport or dispose less than the threshold planning quantity (T.P.Q.) of any extremely hazardous substances as defined in 40 CFR 355.

A complete copy of the approved APD, if applicable, shall be on location during the construction of the location and drilling activities.

Inland Production Company or a contractor employed by Inland Production shall contact the State office at (801) 722-3417, 48 hours prior to construction activities.

The State office shall be notified upon site completion prior to moving on the drilling rig.

13. **LESSEE'S OR OPERATOR'S REPRESENTATIVE AND CERTIFICATION:**

Representative

Name: Brad Mecham
Address: Inland Production Company
Route 3, Box 3630
Myton, UT 84052
Telephone: (435) 646-3721

Certification

Please be advised that INLAND RESOURCES, INC. is considered to be the operator of well #15-2-9-15, SW/SE Section 2, T9S, R15E, LEASE #ML-43538, Duchesne County, Utah and is responsible under the terms and conditions of the lease for the operations conducted upon the leased lands. Bond coverage is provided by Hartford Accident #4471291.

I hereby certify that the proposed drill site and access route have been inspected, and I am familiar with the conditions which currently exist; that the statements made in this plan are true and correct to the best of my knowledge; and that the work associated with the operations proposed here will be performed by Inland Resources, Inc. and its contractors and subcontractors in conformity with this plan and the terms and conditions under which it is approved. This statement is subject to the provisions of the 18 U.S.C. 1001 for the filing of a false statement.


4/22/04
Date

Mandie Crozier
Mandie Crozier
Regulatory Specialist
Inland Production Company

INLAND PRODUCTION COMPANY

ASHLEY UNIT 15-2

Section 2, T9S, R15E, S.L.B.&M.



SURVEYED BY: C.D.S.

SCALE: 1" = 50'

DRAWN BY: J.R.S.





DATE: 3-15-04

Tri State
Land Surveying, Inc.

(435) 781-2501

180 NORTH VERNAL AVE. VERNAL, UTAH 84078

INLAND PRODUCTION COMPANY
CROSS SECTIONS
ASHLEY UNIT 15-2



NOTE:
UNLESS OTHERWISE NOTED
ALL CUT/FILL SLOPES ARE
AT 1.5:1

ESTIMATED EARTHWORK QUANTITIES (No Shrink or swell adjustments have been used) (Expressed in Cubic Yards)				
ITEM	CUT	FILL	6" TOPSOIL	EXCESS
PAD	3,630	3,630	Topsoil is not included in Pad Cut	0
PIT	640	0		640
TOTALS	4,270	3,630	890	640

SURVEYED BY: C.D.S.

SCALE: 1" = 50'

DRAWN BY: J.R.S.


DATE: 3-15-04

Tri State
Land Surveying, Inc.
(435) 781-2501
180 NORTH VERNAL AVE. VERNAL, UTAH 84078

INLAND PRODUCTION COMPANY

TYPICAL RIG LAYOUT

ASHLEY UNIT 15-2



SURVEYED BY: C.D.S.

SCALE: 1" = 50'


DRAWN BY: J.R.S.

DATE: 3-15-04

Tri State
Land Surveying, Inc.

(435) 781-2501

180 NORTH VERNAL AVE. VERNAL, UTAH 84078



Ashley Unit 15-2
SEC. 2, T9S, R15E, S.L.B.&M.




Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1 = 100,000
 DRAWN BY: L.C.S.
 DATE: 04-14-2004

Legend
 — Existing Road
 — Proposed Access

TOPOGRAPHIC MAP

"A"



Ashley Unit 15-2
SEC. 2, T9S, R15E, S.L.B.&M.




Tri-State
Land Surveying Inc.
(435) 781-2501
180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: L.C.S.
DATE: 04-14-2004

Legend
Existing Road
Proposed Access

TOPOGRAPHIC MAP
"B"



Ashley Unit 15-2
SEC. 2, T9S, R15E, S.L.B.&M.



Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'

DRAWN BY: bgm


DATE: 04-14-2004

Legend

- Roads
- Existing Gas Line
- Proposed Gas Line
- Existing Water Line
- Proposed Water Line

TOPOGRAPHIC MAP

"C"



Ashley Unit 15-2
SEC. 2, T9S, R15E, S.L.B.&M.



Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078


SCALE: 1" = 2,000'
DRAWN BY: bgm
DATE: 04-16-2004


Legend

- Roads
- Proposed Gas Line

TOPOGRAPHIC MAP

"D"





Ashley Unit 15-2
SEC. 2, T9S, R15E, S.L.B.&M.



Tri-State
Land Surveying Inc.
 (435) 781-2501
 180 North Vernal Ave. Vernal, Utah 84078

SCALE: 1" = 2,000'
DRAWN BY: L.C.S.
DATE: 04-14-2004

Legend

- Proposed Location
- One-Mile Radius
- Existing Well Pad

Exhibit "B"

2-M SYSTEM

Blowout Prevention Equipment Systems




EXHIBIT C

003

WORKSHEET
APPLICATION FOR PERMIT TO DRILL

APD RECEIVED: 04/21/2004

API NO. ASSIGNED: 43-013-32579

WELL NAME: ASHLEY ST 15-2-9-15OPERATOR: INLAND PRODUCTION (N5160)CONTACT: MANDIE CROZIERPHONE NUMBER: 435-646-3721

PROPOSED LOCATION:

SWSE 02 090S 150E

SURFACE: 0537 FSL 2051 FEL

BOTTOM: 0537 FSL 2051 FEL

DUCHESNE

MONUMENT BUTTE (105)

LEASE TYPE: 3 - State

LEASE NUMBER: ML-43538 *ok*

SURFACE OWNER: 3 - State

PROPOSED FORMATION: GRRV

COALBED METHANE WELL? NO

INSPECT LOCATN BY: / /

Tech Review	Initials	Date
Engineering	<i>DRD</i>	<i>5/24/04</i>
Geology		
Surface		

LATITUDE: 40.05419

LONGITUDE: 110.19662

RECEIVED AND/OR REVIEWED:

☒ Plat

☒ Bond: Fed[] Ind[] Sta[3] Fee[]
 (No. 4471291 *ok*)

☒ Potash (Y/N)

☒ Oil Shale 190-5 (B) or 190-3 or 190-13

☒ Water Permit
 (No. MUNICIPAL)

☒ RDCC Review (Y/N)
 (Date: _____)

☒ Fee Surf Agreement (Y/N)

LOCATION AND SITING:

____ R649-2-3.

Unit ASHLEY

____ R649-3-2. General
 Siting: 460 From Qtr/Qtr & 920' Between Wells

____ R649-3-3. Exception

☒ Drilling Unit
 Board Cause No: 242-1
 Eff Date: 8-25-98
 Siting: Suspends General Siting


____ R649-3-11. Directional Drill

COMMENTS:

Needs update to (05-04-04)

STIPULATIONS:

① STATEMENT OF BASIS



OPERATOR: INLAND PROD INC (N5160)

SEC. 2 T.9S, R.15E

FIELD: MONUMENT BUTTE (105)

COUNTY: DUCHESNE

CAUSE: 242-1 / 8-25-1998



Utah Oil Gas and Mining

Well Status

- + GAS INJECTION
- o GAS STORAGE
- x LOCATION ABANDONED
- + NEW LOCATION
- x PLUGGED & ABANDONED
- x PRODUCING GAS
- o PRODUCING OIL
- o SHUT-IN GAS
- o SHUT-IN OIL
- x TEMP. ABANDONED
- o TEST WELL
- + WATER INJECTION
- + WATER SUPPLY
- + WATER DISPOSAL

Unit Status

- EXPLORATORY
- GAS STORAGE
- NF PP OIL
- NF SECONDARY
- PENDING
- PI OIL
- PP GAS
- PP GEOTHERML
- PP OIL
- SECONDARY
- TERMINATED

Field Status

- ABANDONED
- ACTIVE
- COMBINED
- INACTIVE
- PROPOSED
- STORAGE
- TERMINATED



PREPARED BY: DIANA WHITNEY
DATE: 26-APRIL-2004

DIVISION OF OIL, GAS AND MINING
APPLICATION FOR PERMIT TO DRILL
STATEMENT OF BASIS

OPERATOR: Inland Production company
WELL NAME & NUMBER: Ashley State 15-2-9-15
API NUMBER: 43-013-32579
LOCATION: 1/4,1/4 SW/SE Sec: 2 TWP: 9S RNG: 15E 537 FSL 2051 FEL

Geology/Ground Water:

Inland proposes to set 290' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 400'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of section 2. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. The proposed casing and cement program should adequately protect any useable ground water and nearby wells.

Reviewer: Brad Hill **Date:** 05/10/04

Surface:

An onsite of the surface area was done on said date to address issues and take input regarding construction and drilling of this well. Ed Bonner with SITLA was notified of the onsite investigation; Floyd Bartlett of the Utah Division of Wildlife was also notified. Bartlett attended and provided input from wildlife and a reclamation seed mixture for revegetation. Bartlett noted no impact on sage grouse or burrowing owls. A shallow drainage crosses location from the south on the west side of location and will need diverted around location. No other surface issues or construction problems were noted. This well is a legally spaced well and falls within the 200' window of tolerance allowed by division spacing rules. Mecham claims they will construct the reserve pit and see whether there is enough clay in the pit to hold water. If so, they will fill the pit with fresh water and check for seepage before drilling and line pit if it doesn't hold.

Reviewer: Dennis L. Ingram **Date:** May 5, 2004

Conditions of Approval/Application for Permit to Drill:

None.

ON-SITE PREDRILL EVALUATION
Division of Oil, Gas and Mining

OPERATOR: Inland Production Company
WELL NAME & NUMBER: Ashley State #15-2-9-15
API NUMBER: 43-013-32579
LEASE: ML-43538 FIELD/UNIT: Ashley
LOCATION: 1/4, 1/4 SW/SE Sec: 2 TWP: 9S RNG: 15E 537 FSL 2051 FEL
LEGAL WELL SITING: F SEC. LINE; F 1/4, 1/4 LINE; F ANOTHER WELL.
GPS COORD (UTM): X =0568529 E; Y =4433870 N SURFACE OWNER: SITLA

PARTICIPANTS

Dennis L. Ingram (DOGM); Brad Mecham (Inland); Floyd Bartlett (UDWR)

REGIONAL/LOCAL SETTING & TOPOGRAPHY

Well site is proposed approximately 15 miles southwest of Myton, Utah and accessed from the Pleasant Valley, Wells Draw road off Highway 40, in tabletop, rolling hill type habitat that dips to the north and east. This region is arid and has shallow washes that drain from the southwest to the northeast. The Old Indian Treaty Boundary cuts across the southeast corner of this section in a north/northeasterly fashion.

SURFACE USE PLAN

CURRENT SURFACE USE: Grazing, recreation, wildlife use

PROPOSED SURFACE DISTURBANCE: Proposed 429' of new access road plus location measuring 149'x 290' and additional use for reserve pit, reserve pit spoils and topsoil storage.

LOCATION OF EXISTING WELLS WITHIN A 1 MILE RADIUS: 1-10; 8-10; 9-10; 9-2; 16-2; 1-11; 2-11; 3-11; 4-11; 5-11; 6-11; 7-11; 8-11; 9-11; 11-11; 12-11; 15-11; 16-11; 3-12; 12-12; 4-1; 5-1; 6-1; 11-1; 12-1; 14-1.

LOCATION OF PRODUCTION FACILITIES AND PIPELINES: Pump jack on location and production piped to the 10-2 central battery.

SOURCE OF CONSTRUCTION MATERIAL: Native cut and fill

ANCILLARY FACILITIES: None requested.

WASTE MANAGEMENT PLAN:

Submitted to division with application to drill.

ENVIRONMENTAL PARAMETERS

AFFECTED FLOODPLAINS AND/OR WETLANDS: None

FLORA/FAUNA: Shadscale/blacksage habitat typical of region-good ground cover, also has some winter fat, globe mallow, and bluegamma. Primary antelope habitat, possible sage grouse, prairie dogs and other small mammals and birds of prey.

SOIL TYPE AND CHARACTERISTICS: Tan fine-grained sandy loam with some clays and underlying shale.

SURFACE FORMATION & CHARACTERISTICS: Uinta Formation

EROSION/SEDIMENTATION/STABILITY: Minor erosion, some sedimentation, no stability problems.

PALEONTOLOGICAL POTENTIAL: None observed during onsite visit

RESERVE PIT

CHARACTERISTICS: Proposed on south side of location in cut with wellhead adjacent and west of pit and prevailing winds, measuring 40'x 80'x 8' deep.

LINER REQUIREMENTS (Site Ranking Form attached): 15 points

SURFACE RESTORATION/RECLAMATION PLAN

According to SITLA at time of reclamation or according to agreement

SURFACE AGREEMENT: Yes

CULTURAL RESOURCES/ARCHAEOLOGY: Arch survey was done and submitted to the division with Application to Drill

OTHER OBSERVATIONS/COMMENTS

Location surface slopes to north and east, drainages to the north and east, drainage from the west cuts across location western portion of location, inactive sage grouse lek SE/QTR section 12, Ferruginous hawk nests 1.5 miles east along Wells Draw, no raptors seen or observed during onsite, may create water impounded below rocky shelf in drainage south and west of location.

ATTACHMENTS

Photos of this location were taken and placed on file.

Dennis L. Ingram
DOGM REPRESENTATIVE

May 5, 2004 10:45 A.M.
DATE/TIME

**Evaluation Ranking Criteria and Ranking Score
For Reserve and Onsite Pit Liner Requirements**

<u>Site-Specific Factors</u>	<u>Ranking</u>	<u>Site Ranking</u>
Distance to Groundwater (feet)		
>200	0	
100 to 200	5	
75 to 100	10	
25 to 75	15	
<25 or recharge area	20	<u>0</u>
Distance to Surf. Water (feet)		
>1000	0	
300 to 1000	2	
200 to 300	10	
100 to 200	15	
< 100	20	<u>0</u>
Distance to Nearest Municipal Well (feet)		
>5280	0	
1320 to 5280	5	
500 to 1320	10	
<500	20	<u>0</u>
Distance to Other Wells (feet)		
>1320	0	
300 to 1320	10	
<300	20	<u>0</u>
Native Soil Type		
Low permeability	0	
Mod. permeability	10	
High permeability	20	<u>10</u>
Fluid Type		
Air/mist	0	
Fresh Water	5	
TDS >5000 and <10000	10	
TDS >10000 or Oil Base Mud Fluid	15	
containing significant levels of hazardous constituents	20	<u>5</u>
Drill Cuttings		
Normal Rock	0	
Salt or detrimental	10	<u>0</u>
Annual Precipitation (inches)		
<10	0	
10 to 20	5	
>20	10	<u>0</u>
Affected Populations		
<10	0	
10 to 30	6	
30 to 50	8	
>50	10	<u>0</u>
Presence of Nearby Utility		
Conduits		
Not Present	0	
Unknown	10	
Present	15	<u>0</u>

Final Score 15 (Level ii Sensitivity)


Sensitivity Level I = 20 or more; total containment is required.

Sensitivity Level II = 15-19; lining is discretionary.

Sensitivity Level III = below 15; no specific lining is required.

05-04 Inland Ashley St 15-2-9-15

Casing Schematic



Well name:

05-04 Inland Ashley St 15-2-9-15Operator: **Inland Production Company**String type: **Surface**

Project ID:

43-013-32579Location: **Duchesne County****Design parameters:****Collapse**Mud weight: 8.400 ppg
Design is based on evacuated pipe.**Minimum design factors:****Collapse:**

Design factor 1.125

Burst:

Design factor 1.00

Environment:H2S considered? No
Surface temperature: 65 °F
Bottom hole temperature: 69 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 290 ft

Cement top: Surface

BurstMax anticipated surface pressure: 0 psi
Internal gradient: 0.436 psi/ft
Calculated BHP 127 psi

No backup mud specified.

Tension:8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)Tension is based on buoyed weight.
Neutral point: 253 ft

Non-directional string.

Re subsequent strings:Next setting depth: 6,500 ft
Next mud weight: 8.400 ppg
Next setting BHP: 2,836 psi
Fracture mud wt: 19.250 ppg
Fracture depth: 290 ft
Injection pressure 290 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	290	8.625	24.00	J-55	ST&C	290	290	7.972	14
Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	127	1370	10.826	127	2950	23.31	6	244	40.12 J

Prepared by: Clinton Dworshak
Utah Div. of Oil & MiningPhone: 801-538-5280
FAX: 801-359-3940Date: May 19, 2004
Salt Lake City, Utah**Remarks:**

Collapse is based on a vertical depth of 290 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

Well name:	05-04 Inland Ashley St 15-2-9-15		
Operator:	Inland Production Company		
String type:	Production	Project ID:	43-013-32579
Location:	Duchesne County		

Design parameters:
Collapse

Mud weight: 8.400 ppg
Design is based on evacuated pipe.

Minimum design factors:
Collapse:

Design factor 1.125

Burst:

Design factor 1.00

Environment:

H2S considered? No
Surface temperature: 65 °F
Bottom hole temperature: 156 °F
Temperature gradient: 1.40 °F/100ft
Minimum section length: 300 ft

Cement top: 1 ft

Burst

Max anticipated surface pressure: 0 psi
Internal gradient: 0.436 psi/ft
Calculated BHP 2,836 psi

No backup mud specified.

Tension:

8 Round STC: 1.80 (J)
8 Round LTC: 1.80 (J)
Buttress: 1.60 (J)
Premium: 1.50 (J)
Body yield: 1.50 (B)

Non-directional string.

Tension is based on air weight.
Neutral point: 5,674 ft

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Internal Capacity (ft³)
1	6500	5.5	15.50	J-55	LT&C	6500	6500	4.825	203.7

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (Kips)	Tension Strength (Kips)	Tension Design Factor
1	2836	4040	1.424	2836	4810	1.70	101	217	2.15 J

Prepared by: Clinton Dworshak
Utah Div. of Oil & Mining

Phone: 801-538-5280
FAX: 801-359-3940

Date: May 19,2004
Salt Lake City, Utah

Remarks:

Collapse is based on a vertical depth of 6500 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Engineering responsibility for use of this design will be that of the purchaser.

United States Department of the Interior

BUREAU OF LAND MANAGEMENT

Utah State Office

P.O. Box 45155

Salt Lake City, Utah 84145-0155

IN REPLY REFER TO:

3160

(UT-922)

April 26, 2004

Memorandum

To: Assistant District Manager Minerals, Vernal District
From: Michael Coulthard, Petroleum Engineer
Subject: 2004 Plan of Development Ashley Unit,
Duchesne County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2003 within the Ashley Unit, Duchesne County, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ Green River)		
43-013-32574	Ashley State 10-2-9-15 Sec 2 T09S R15E 2093 FSL 2056 FEL	
43-013-32575	Ashley State 11-2-9-15 Sec 2 T09S R15E 1982 FSL 2078 FWL	
43-013-32576	Ashley State 12-2-9-15 Sec 2 T09S R15E 1978 FSL 0638 FWL	
43-013-32577	Ashley State 13-2-9-15 Sec 2 T09S R15E 0661 FSL 0670 FWL	
43-013-32578	Ashley State 14-2-9-15 Sec 2 T09S R15E 0525 FSL 2017 FWL	
43-013-32579	Ashley State 15-2-9-15 Sec 2 T09S R15E 0537 FSL 2051 FEL	
43-013-32580	Ashley State 2-2-9-15 Sec 2 T09S R15E 0672 FNL 1978 FEL	
43-013-32581	Ashley State 3-2-9-15 Sec 2 T09S R15E 0640 FNL 1358 FWL	
43-013-32582	Ashley State 4-2-9-15 Sec 2 T09S R15E 0773 FNL 0459 FWL	
43-013-32583	Ashley State 5-2-9-15 Sec 2 T09S R15E 1997 FNL 0462 FWL	
43-013-32584	Ashley State 6-2-9-15 Sec 2 T09S R15E 1870 FNL 1630 FWL	
43-013-32585	Ashley State 7-2-9-15 Sec 2 T09S R15E 2008 FNL 2254 FEL	

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File - Ashley Unit
Division of Oil Gas and Mining
Agr. Sec. Chron
Fluid Chron

MCoulthard:mc:4-26-04



State of Utah

Department of
Natural ResourcesROBERT L. MORGAN
*Executive Director*Division of
Oil, Gas & MiningLOWELL P. BRAXTON
*Division Director*OLENE S. WALKER
*Governor*GAYLE F. McKEACHNIE
Lieutenant Governor

May 24, 2004

Inland Production Company
Rt. #3, Box 3630
Myton, UT 84052Re: Ashley State 15-2-9-15 Well, 537' FSL, 2051' FEL, SW SE, Sec. 2, T. 9 South,
R. 15 East, Duchesne County, Utah

Gentlemen:

Pursuant to the provisions and requirements of Utah Code Ann. § 40-6-1 *et seq.*, Utah Administrative Code R649-3-1 *et seq.*, and the attached Conditions of Approval, approval to drill the referenced well is granted.

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date. The API identification number assigned to this well is 43-013-32579.

Sincerely,

A handwritten signature in black ink, appearing to read "John R. Baza".
John R. Baza
Associate Directorpab
Enclosurescc: Duchesne County Assessor
SITLA
Bureau of Land Management, Vernal District Office

Operator: Inland Production Company
Well Name & Number Ashley State 15-2-9-15
API Number: 43-013-32579
Lease: ML-43538

Location: SW SE **Sec.** 2 **T.** 9 South **R.** 15 East

Conditions of Approval

1. General

Compliance with the requirements of Utah Admin. R. 649-1 *et seq.*, the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

2. Notification Requirements

The operator is required to notify the Division of Oil, Gas and Mining of the following actions during drilling of this well:

- 24 hours prior to cementing or testing casing
- 24 hours prior to testing blowout prevention equipment
- 24 hours prior to spudding the well
- within 24 hours of any emergency changes made to the approved drilling program
- prior to commencing operations to plug and abandon the well

The following are Division of Oil, Gas and Mining contacts and their work telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at (801) 538-5338
- Carol Daniels at (801) 538-5284 (spud)

3. Reporting Requirements

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

4. Compliance with the State of Utah Antiquities Act forbids disturbance of archeological, historical, or paleontological remains. Should archeological, historical or paleontological remains be encountered during your operations, you are required to immediately suspend all operations and immediately inform the Trust Lands Administration and the Division of State History of the discovery of such remains.

5. Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis. (Copy Attached)

DIVISION OF OIL, GAS AND MINING**SPUDDING INFORMATION**Name of Company: INLAND PRODUCTION COMPANYWell Name: ASHLEY ST 15-2-9-15Api No: 43-013-32579 Lease Type: STATESection 02 Township 09S Range 15E County DUCHESNEDrilling Contractor ROSS DRILLING RIG # 15**SPUDDED:**Date 06/14/04Time 10:00 AMHow DRY**Drilling will commence:** _____Reported by FLOYD MITCHELLTelephone # 1-435-823-3610Date 06/22/2004 Signed CHD

006

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS, AND MINING

1. SUNDRY NOTICES AND REPORTS ON WELLS (Do not use this form for proposals to drill or to deepen or plug back to a different reservoir. Use "APPLICATION FOR PERMIT—" for such proposals.) OIL <input type="checkbox"/> GAS <input type="checkbox"/> WELL <input checked="" type="checkbox"/> WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NO. ML-43538	
2. NAME OF OPERATOR INLAND PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBAL NAME N/A	
3. ADDRESS OF OPERATOR Rt. 3 Box 3630, Myton Utah 84052 435-646-3721		7. UNIT AGREEMENT NAME ASHLEY (GR RVR)	
4. LOCATION OF WELL (Report location clearly and in accordance with any State requirements.* See also space 17 below.) At surface SW/SE Section 2, T9S R15E 537 FSL 2051 FEL		8. FARM OR LEASE NAME ASHLEY STATE 15-2-9-15	
14. API NUMBER 43-013-32579		9. WELL NO. ASHLEY STATE 15-2-9-15	
15. ELEVATIONS (Show whether DF, RT, GR, etc.) 6020 GL		10. FIELD AND POOL, OR WILDCAT MONUMENT BUTTE	
12. COUNTY OR PARISH DUCHESNE		11. SEC., T., R., M., OR BLK. AND SURVEY OR AREA SW/SE Section 2, T9S R15E	
13. STATE UT		16. Check Appropriate Box To Indicate Nature of Notice, Report, or Other Data	
NOTICE OF INTENTION TO: TEST WATER SHUT-OFF <input type="checkbox"/> PULL OR ALTER CASING <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> MULTIPLE COMPLETE <input type="checkbox"/> SHOOT OR ACIDIZE <input type="checkbox"/> ABANDON* <input type="checkbox"/> REPAIR WELL <input type="checkbox"/> (OTHER) <input type="checkbox"/>		SUBSEQUENT REPORT OF: WATER SHUT-OFF <input type="checkbox"/> REPAIRING WELL <input type="checkbox"/> FRACTURE TREATMENT <input type="checkbox"/> ALTERING CASING <input type="checkbox"/> SHOOTING OR ACIDIZING <input type="checkbox"/> ABANDONMENT* <input type="checkbox"/> (OTHER) <input checked="" type="checkbox"/> <u>Weekly Status</u> (Note: Report results of multiple completion on Well Completion or Recompletion Report and Log form.)	
17. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. (Clearly state all pertinent details, and give pertinent dates, including estimated date of starting any proposed work. If well is directionally drilled, give subsurface locations and measured and true vertical depths for all markers and zones pertinent to this work.)* On 06/14/04 MIRU Ross # 15. Spud well @ 10:00 AM. Drill 307' of 12 1/4" hole with air mist. TIH w/ 7 Jt's 85/8" J-55 24# csgn. Set @ 313.01'/KB. On 06/18/04. Cement with 150 sks of Class "G" w/ 2% CaCL2 + 1/4# sk Cello-Flake Mixed @ 15.8 ppg > 1.17 cf/sk yeild. 4 bbls cement returned to surface. WOC.			
18. I hereby certify that the foregoing is true and correct SIGNED <u>Floyd Mitchell</u> TITLE <u>Drilling Foreman</u> DATE <u>06/19/04</u> Floyd Mitchell			
cc: BLM (This space for Federal or State office use)			
APPROVED BY _____ TITLE _____ DATE _____ CONDITIONS OF APPROVAL, IF ANY:			

* See Instructions On Reverse Side

RECEIVED
JUN 22 2004

DIV. OF OIL, GAS & MINING

INLAND PRODUCTION COMPANY - CASING & CEMENT REPORT

8 5/8 CASING SET AT 313.01

LAST CASING 8 5/8" SET AT 314'
 DATUM 12' KB
 DATUM TO CUT OFF CASING _____
 DATUM TO BRADENHEAD FLANGE _____
 TD DRILLER 307 LOGGER _____
 HOLE SIZE 12 1/4

OPERATOR Inland Production Company
 WELL Ashley State 15-2-9-15
 FIELD/PROSPECT Monument Butte
 CONTRACTOR & RIG # Ross # 15

LOG OF CASING STRING:

PIECES	OD	ITEM - MAKE - DESCRIPTION	WT / FT	GRD	THREAD	CONDT	LENGTH
		42.15' SH jt					
		WHI - 92 csg head			8rd	A	0.95
7	8 5/8"	Maverick ST&C csg	24#	J-55	8rd	A	301.16
		GUIDE shoe			8rd	A	0.9

CASING INVENTORY BAL.	FEET	JTS	TOTAL LENGTH OF STRING	303.01
TOTAL LENGTH OF STRING	303.01	7	LESS CUT OFF PIECE	2
LESS NON CSG. ITEMS	1.85		PLUS DATUM TO T/CUT OFF CSG	12
PLUS FULL JTS. LEFT OUT	0		CASING SET DEPTH	313.01
TOTAL	301.16	7	} COMPARE	
TOTAL CSG. DEL. (W/O THRDS)	301.16	7		
TIMING	1ST STAGE			
BEGIN RUN CSG. Spud	6/14/2004	10:00 AM	GOOD CIRC THRU JOB	YES
CSG. IN HOLE	6/16/2004	5:00 PM	Bbls CMT CIRC TO SURFACE	4
BEGIN CIRC	6/18/2004	8:57 AM	RECIPROCATED PIPE IN/A	
BEGIN PUMP CMT	6/18/2004	9:11 AM	DID BACK PRES. VALVE HOLD ?	N/A
BEGIN DSPL. CMT	6/18/2004	9:30	BUMPED PLUG TO	405 PSI
PLUG DOWN	Cemented	9:30 AM	6/18/2004	

CEMENT USED	CEMENT COMPANY- B. J.		
STAGE	# SX	CEMENT TYPE & ADDITIVES	
1	150	Class "G" w/ 2% CaCL2 + 1/4#/sk Cello-Flake mixed @ 15.8 ppg 1.17 cf/sk yield	

CENTRALIZER & SCRATCHER PLACEMENT	SHOW MAKE & SPACING
Centralizers - Middle first, top second & third for 3	

COMPANY REPRESENTATIVE Floyd Mitchell

DATE 6/19/2004

RECEIVED

JUN 22 2004

007

RECEIVED

JUN 28 2004

DIV. OF OIL, GAS & MINING

OPERATOR: INLAND PRODUCTION COMPANY

OPERATOR ACCT. NO. N5160

ADDRESS: RT. 3 BOX 3630

MYTON, UT 84052

STATE OF UTAH

DIVISION OF OIL, GAS AND MINING

ENTITY ACTION FORM -FORM 6

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	14204	43-013-32579	Ashley State 15-2-9-15	SW/SE	2	9S	15E	Duchesne	June 14, 2004	6/30/04 K

WELL 1 COMMENTS:

GRUV

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
A	99999	14205	43-013-32578	Ashley State 14-2-9-15	SE/SW	2	9S	15E	Duchesne	June 18, 2004	6/30/04 K

WELL 2 COMMENTS:

GRUV

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
B	99999	12704	43-013-32507	BlackJack Federal 4-10-9-17	NW/NW	10	9S	17E	Duchesne	June 18, 2004	6/30/04 K

WELL 3 COMMENTS:

GRUV

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		

WELL 4 COMMENTS:

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		


WELL 5 COMMENTS:

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comments section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/98)



Kebbie S. Jones

Production Clerk
TitleJune 28, 2004
Date

PAGE 02

INLAND

4356462-1

09:38

06/28/2004

009

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:

ML43538

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

SUNDRY NOTICES AND REPORTS ON WELLS

not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

7. TYPE OF WELL:

OIL WELL ☒GAS WELL ☐

OTHER

7. UNIT OR CA AGREEMENT NAME:

ASHLEY SEC 2

8. WELL NAME and NUMBER:

ASHLEY STATE 15-2-9-15

9. NAME OF OPERATOR:

Inland Production Company

9. API NUMBER:

4301332579

10. ADDRESS OF OPERATOR:

Route 3 Box 3630

CITY Myton

STATE UT

ZIP 84052

PHONE NUMBER

435.646.3721

10. FIELD AND POOL, OR WILDCAT:

Monument Butte

11. LOCATION OF WELL:

FOOTAGES AT SURFACE: 537 FSL 2051 FEL

COUNTY: Duchesne

QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SW/SE, 2, T9S, R15E

STATE: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION			
	TYPE OF ACTION			
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON	
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 07/28/2004	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL	
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Weekly Status Report	
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION		

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Status report for time period 07/16/04– 07/28/04

Subject well had completion procedures initiated in the Green River formation on 7/16/04 without the use of a service rig over the well. A cement bond log was run and a total of five Green River intervals were perforated and hydraulically fracture treated w/ 20/40 mesh sand. Perf intervals were #1 (5880-5900') (4 JSPF); #2 (5698-5701'), (5670-5674') (All 4 JSPF); #3 (5360-5380') (4 JSPF); #4 (4664-4674') (4 JSPF); #5 (4545-4556') (4 JSPF). Composite flow-through frac plugs were used between stages. Fracs were flowed back through chokes. A service rig was moved on well on 7/26/04. Bridge plugs were drilled out. Well was cleaned out to PBTD @ 6126'. Zones were swab tested for sand cleanup. A BHA & production tubing string were run in and anchored in well. End of tubing string @ 5972.78'. A new 1 1/2" bore rod pump was run in well on sucker rods. Well was placed on production via rod pump on 7/28/04.

NAME (PLEASE) Mamie Bryson

TITLE Production Clerk

SIGNATURE *Mamie Bryson*

DATE July 29, 2004

This space for State use only)

RECEIVED

JUL 30 2004

DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML43538

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

ASHLEY SEC 2

8. WELL NAME and NUMBER:

ASHLEY STATE 15-2-9-15

9. API NUMBER:

4301332579

10. FIELD AND POOL, OR WILDCAT:

Monument Butte

1. TYPE OF WELL:

OIL WELL ☒

GAS WELL ☐

OTHER

2. NAME OF OPERATOR:

Inland Production Company

3. ADDRESS OF OPERATOR:

Route 3 Box 3630

CITY Myton

STATE UT

ZIP 84052

PHONE NUMBER

435.646.3721

4. LOCATION OF WELL:

FOOTAGES AT SURFACE: 537 FSL 2051 FEL

COUNTY: Duchesne

OTR/OTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SW/SE, 2, T9S, R15E

STATE: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF ACTION

TYPE OF SUBMISSION

TYPE OF ACTION

☒ NOTICE OF INTENT
(Submit in Duplicate)

Approximate date work will

07/28/2004

☐ SUBSEQUENT REPORT
(Submit Original Form Only)

Date of Work Completion:

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☐ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☐ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/STOP)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARITLY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLAIR

☒ WATER DISPOSAL

☐ WATER SHUT-OFF

☐ OTHER: -

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Formation water is produced to a steel storage tank. If the production water meets quality guidelines, it is transported to the Ashley, Monument Butte, Jonah, and Beluga water injection facilities by company or contract trucks. Subsequently, the produced water is injected into approved Class II wells to enhance Inland's secondary recovery project.

Water not meeting quality criteria, is disposed at Inland's Pariette #4 disposal well (Sec. 7, T9S R19E) or at State of Utah approved surface disposal facilities.


**Accepted by the
Utah Division of
Oil, Gas and Mining
FOR RECORD ONLY**

NAME (PLEASE

Mandie Crozier

TITLE Regulatory Specialist

SIGNATURE



DATE August 04, 2004

(This space for State use only)

RECEIVED
AUG 05 2004
DIV. OF OIL, GAS & MINING



Office of the Secretary of State

The undersigned, as Secretary of State of Texas, does hereby certify that the attached is a true and correct copy of each document on file in this office as described below:

Newfield Production Company
Filing Number: 41530400

Articles of Amendment

September 02, 2004

In testimony whereof, I have hereunto signed my name officially and caused to be impressed hereon the Seal of State at my office in Austin, Texas on September 10, 2004.



A handwritten signature in black ink, appearing to read "G. Connor".

Secretary of State

ARTICLES OF AMENDMENT
TO THE
ARTICLES OF INCORPORATION
OF
INLAND PRODUCTION COMPANY

FILED
In the Office of the
Secretary of State of Texas

SEP 02 2004
Corporations Section

Pursuant to the provisions of Article 4.04 of the Texas Business Corporation Act (the "TBCA"), the undersigned corporation adopts the following articles of amendment to the articles of incorporation:

ARTICLE 1 – Name

The name of the corporation is Inland Production Company.

ARTICLE 2 – Amended Name

The following amendment to the Articles of Incorporation was approved by the Board of Directors and adopted by the shareholders of the corporation on August 27, 2004.

The amendment alters or changes Article One of the Articles of Incorporation to change the name of the corporation so that, as amended, Article One shall read in its entirety as follows:

"ARTICLE ONE – The name of the corporation is Newfield Production Company."

ARTICLE 3 – Effective Date of Filing

This document will become effective upon filing.

The holder of all of the shares outstanding and entitled to vote on said amendment has signed a consent in writing pursuant to Article 9.10 of the TBCA, adopting said amendment, and any written notice required has been given.

IN WITNESS WHEREOF, the undersigned corporation has executed these Articles of Amendment as of the 1st day of September, 2004.

INLAND RESOURCES INC.

By: Susan G. Riggs
Susan G. Riggs, Treasurer

Inland Resources Inc.

September 2, 2004

State of Utah, Division of Oil, Gas and Mining
Attn: Ms. Carol Daniels
P.O. Box 145801
Salt Lake City, Utah 84144-5801

Attn: Ms. Carol Daniels

ST
Ashley 15-2-9-15 (43-013-32579)
Duchesne County, Utah


Ashley 7-11-9-15 (43-013-32215)
Duchesne County, Utah

Dear Ms. Carol Daniels

Enclosed is a Well Completion or Recompletion Report and Log form (Form 3160-4). We are no longer sending Log copies since Pat Grissom of Phoenix Surveys is already doing so.

If you should have any questions, please contact me at (303) 382-4449.

Sincerely,



Brian Harris
Engineering Tech

Enclosures

cc: Bureau of Land Management
Vernal District Office, Division of Minerals
Attn: Edwin I. Forsman
170 South 500 East
Vernal, Utah 84078

Well File – Denver
Well File – Roosevelt
Patsy Barreau/Denver
Bob Jewett/Denver
Matt Richmond/Roosevelt

RECEIVED

SEP 07 2004

DIV. OF OIL, GAS & MINING

010

UNITED STATES
DEPARTMENT OF THE INTERIOR
BUREAU OF LAND MANAGEMENT

WELL COMPLETION OR RECOMPLETION REPORT AND LOG*

1a. TYPE OF WORK

OIL WELL ☒ GAS WELL ☐ DRY ☐ Other _____

1b. TYPE OF WELL

NEW WELL ☒ WORK OVER ☐ DEEPEN ☐ PLUG BACK ☐ DIFF. RESVR. ☐ Other _____

2. NAME OF OPERATOR

INLAND RESOURCES INC.

3. ADDRESS AND TELEPHONE NO.

1401 17th St. Suite 1000 Denver, CO 80202

4. LOCATION OF WELL (Report locations clearly and in accordance with any State requirements.)*

At Surface 537' FSL & 2051' FEL (SW SE) Sec. 2, T9S, R15E

At top prod. Interval reported below

At total depth

14. API NO. 43-013-32579 DATE ISSUED 5/24/2004

12. COUNTY OR PARISH Duchesne 13. STATE UT

15. DATE SPUDDED 6/14/2004 16. DATE T.D. REACHED 7/3/2004 17. DATE COMPL. (Ready to prod.) 7/28/2004 18. ELEVATIONS (DF, RKB, RT, GR, ETC.)* 6020' GL 6032' KB 19. ELEV. CASINGHEAD

20. TOTAL DEPTH, MD & TVD 6160' 21. PLUG BACK T.D., MD & TVD 6126' 22. IF MULTIPLE COMPL., HOW MANY* 23. INTERVALS DRILLED BY -----> 23. ROTARY TOOLS X 23. CABLE TOOLS

24. PRODUCING INTERVAL(S), OF THIS COMPLETION--TOP, BOTTOM, NAME (MD AND TVD)*

Green River 4545'-5900'

25. WAS DIRECTIONAL SURVEY MADE No

26. TYPE ELECTRIC AND OTHER LOGS RUN

Dual Induction Guard, SP, Compensated Density, Compensated Neutron, GR, Caliper, Cement Bond Log

27. WAS WELL CORED No

23. CASING RECORD (Report all strings set in well)

CASING SIZE/GRADE	WEIGHT, LB./FT.	DEPTH SET (MD)	HOLE SIZE	TOP OF CEMENT, CEMENTING RECORD	AMOUNT PULLED
8-5/8" - J-55	24#	313'	12-1/4"	To surface with 150 sx Class "G" cmt	
5-1/2" - J-55	15.5#	6150'	7-7/8"	300 sx Premlite II and 400 sx 50/50 Poz	

29. LINER RECORD

SIZE	TOP (MD)	BOTTOM (MD)	SACKS CEMENT*	SCREEN (MD)

30. TUBING RECORD

SIZE	DEPTH SET (MD)	PACKER SET (MD)
2-7/8"	EOT @ 5972'	TA @ 5871'

31. PERFORATION RECORD (Interval, size and number)

INTERVAL	SIZE	SPF/NUMBER	DEPTH INTERVAL (MD)	AMOUNT AND KIND OF MATERIAL USED
(CP3) 5880'-5900"	.41"	4/80	5880'-5900'	Frac w/ 54,059# 20/40 sand in 494 bbls fluid.
(CP.5,1) 5670-74', 5698-5701"	.41"	4/28	5670'-5701'	Frac w/ 34,304# 20/40 sand in 375 bbls fluid.
(LODC) 5360'-5380'	.41"	4/80	5360'-5380'	Frac w/ 39,721# 20/40 sand in 371 bbls fluid.
(DS1) 4664'-4674'	.41"	4/40	4664'-4674'	Frac w/ 29,245# 20/40 sand in 300 bbls fluid.
(PB10) 4545'-4556'	.41"	4/44	4545'-4556'	Frac w/ 28,142# 20/40 sand in 296 bbls fluid.

33.* PRODUCTION

DATE FIRST PRODUCTION 7/28/2004	PRODUCTION METHOD (Flowing, gas lift, pumping--size and type of pump)	DIV. OF OIL, GAS & MINING	WELL STATUS (Producing or shut-in) PRODUCING
DATE OF TEST 2 day ave	HOURS TESTED	CHOKE SIZE	PROD'N. FOR TEST PERIOD
			OIL--BBL. 99 GAS--MCF. Not Measured WATER--BBL. 54 GAS-OIL RATIO
FLOW. TUBING PRESS.	CASING PRESSURE	CALCULATED 24-HOUR RATE	OIL-BBL. GAS--MCF. WATER--BBL. OIL GRAVITY-API (CORR.)

34. DISPOSITION OF GAS (Sold, used for fuel, vented, etc.)

Sold & Used for Fuel

TEST WITNESSED BY

35. LIST OF ATTACHMENTS

36. I hereby certify that the foregoing information is complete and correct as determined from all available records

SIGNED Brian Harris

TITLE Engineering Technician

DATE 9/1/2004

Brian Harris

BDH

*(See Instructions and Spaces for Additional Data on Reverse Side)

37. SUMMARY OF POROUS ZONES: (Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem, tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries);				38. GEOLOGIC MARKERS		
FORMATION	TOP	BOTTOM	DESCRIPTION, CONTENTS, ETC.	NAME	TOP	
					MEAS. DEPTH	TRUE VERT. DEPTH
			Well Name Ashley 15-2-9-15	Garden Gulch Mkr	3728'	
				Garden Gulch 1	3962'	
				Garden Gulch.2	4073'	
				Point 3 Mkr	4332'	
				X Mkr	4605'	
				Y-Mkr	4646'	
				Douglas Creek Mkr	4753'	
				BiCarbonate Mkr	4995'	
				B Limestone Mkr	5099'	
				Castle Peak	5654'	
				Basal Carbonate	6085'	
				Total Depth (LOGGERS	6161'	

011

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING
ENTITY ACTION FORM - FORM 6

OPERATOR: **INLAND PRODUCTION COMPANY**
ADDRESS: **RT. 3 BOX 3630**
MYTON, UT 84052

OPERATOR ACCT. NO. **N5160**

ACTION CODE	CURRENT ENTITY NO.	NEW ENTITY NO.	API NUMBER	WELL NAME	WELL LOCATION					SPUD DATE	EFFECTIVE DATE
					QQ	SC	TP	RG	COUNTY		
C	14212	12419	43-013-32576	Ashley State 12-2-9-15	NW/SW	2	9S	15E	Duchesne		7/1/2004
WELL 1 COMMENTS: <i>GRU</i>											
C	14211	12419	43-013-32577	Ashley State 13-2-9-15	SW/SW	2	9S	15E	Duchesne		7/1/2004
WELL 2 COMMENTS: <i>GRU</i>											
C	14205	12419	43-013-32578	Ashley State 14-2-9-15	SE/SW	2	9S	15E	Duchesne		7/1/2004
WELL 3 COMMENTS: <i>GRU</i>											
C	14204	12419	43-013-32579	Ashley State 15-2-9-15	SW/SE	2	9S	15E	Duchesne		7/1/2004
WELL 4 COMMENTS: <i>GRU</i>											
C	14048	12419	43-013-32396	Ashley Federal 2-14-9-15	NW/NE	14	9S	15E	Duchesne		7/1/2004
WELL 5 COMMENTS: <i>GRU</i>											

ACTION CODES (See instructions on back of form)

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (explain in comment section)

NOTE: Use COMMENT section to explain why each Action Code was selected.

(3/88)

Signature

Production Clerk

Date

Kebbie S. Jones

September 14, 2004
Date

RECEIVED

SEP 15 2004

DIV. OF OIL, GAS & MINING

K

K

K

K

K

K

9/15/04

9/15/04

9/15/04

9/15/04

9/15/04

OPERATOR CHANGE WORKSHEET**012**

Change of Operator (Well Sold)

Designation of Agent/Operator

ROUTING

1. GLH

2. CDW

3. FILE

X Operator Name Change**Merger**

The operator of the well(s) listed below has changed, effective:

9/1/2004**FROM: (Old Operator):**

N5160-Inland Production Company

Route 3 Box 3630

Myton, UT 84052

Phone: 1-(435) 646-3721

TO: (New Operator):

N2695-Newfield Production Company

Route 3 Box 3630

Myton, UT 84052

Phone: 1-(435) 646-3721

CA No.**Unit:****ASHLEY****WELL(S)**

NAME	SEC TWN RNG			API NO	ENTITY NO	LEASE TYPE	WELL TYPE	WELL STATUS	
ASHLEY ST 10-2-9-15	02	090S	150E	4301332574	12419	State	OW	P	K
ASHLEY ST 11-2-9-15	02	090S	150E	4301332575	12419	State	OW	P	K
ASHLEY ST 12-2-9-15	02	090S	150E	4301332576	12419	State	OW	P	K
ASHLEY ST 13-2-9-15	02	090S	150E	4301332577	12419	State	OW	P	K
ASHLEY ST 14-2-9-15	02	090S	150E	4301332578	12419	State	OW	P	K
ASHLEY ST 15-2-9-15	02	090S	150E	4301332579	12419	State	OW	P	K
ASHLEY ST 2-2-9-15	02	090S	150E	4301332580		State	OW	APD	K
ASHLEY ST 3-2-9-15	02	090S	150E	4301332581		State	OW	APD	K
ASHLEY ST 4-2T-9-15	02	090S	150E	4301332582		State	OW	APD	K
ASHLEY ST 5-2-9-15	02	090S	150E	4301332583		State	OW	APD	K
ASHLEY ST 6-2-9-15	02	090S	150E	4301332584		State	OW	APD	K
ASHLEY FED 7-22-9-15	22	090S	150E	4301332487	14453	Federal	OW	DRL	K
ASHLEY FED 1-23-9-15	23	090S	150E	4301332478	14455	Federal	OW	DRL	K
ASHLEY FED 3-23-9-15	23	090S	150E	4301332479	14451	Federal	OW	DRL	K
ASHLEY FED 5-23-9-15	23	090S	150E	4301332480	14452	Federal	OW	DRL	K
ASHLEY FED 7-23-9-15	23	090S	150E	4301332481	14454	Federal	OW	DRL	K
ASHLEY FED 1-24-9-15	24	090S	150E	4301332482		Federal	OW	APD	K
ASHLEY FED 3-24-9-15	24	090S	150E	4301332483		Federal	OW	APD	K
ASHLEY FED 5-24-9-15	24	090S	150E	4301332484		Federal	OW	APD	K
ASHLEY FED 7-24-9-15	24	090S	150E	4301332485		Federal	OW	APD	K

OPERATOR CHANGES DOCUMENTATION

Enter date after each listed item is completed

1. (R649-8-10) Sundry or legal documentation was received from the **FORMER** operator on: 9/15/20042. (R649-8-10) Sundry or legal documentation was received from the **NEW** operator on: 9/15/20043. The new company was checked on the **Department of Commerce, Division of Corporations Database** on: 2/23/20054. Is the new operator registered in the State of Utah: YES Business Number: 755627-01435. If **NO**, the operator was contacted on:

6a. (R649-9-2)Waste Management Plan has been received on: IN PLACE
6b. Inspections of LA PA state/fee well sites complete on: waived

7. **Federal and Indian Lease Wells:** The BLM and or the BIA has approved the merger, name change, or operator change for all wells listed on Federal or Indian leases on: BLM BIA

8. **Federal and Indian Units:**
The BLM or BIA has approved the successor of unit operator for wells listed on: n/a

9. **Federal and Indian Communization Agreements ("CA"):**
The BLM or BIA has approved the operator for all wells listed within a CA on: na/

10. **Underground Injection Control ("UIC")** The Division has approved UIC Form 5, **Transfer of Authority to Inject**, for the enhanced/secondary recovery unit/project for the water disposal well(s) listed on: 2/23/2005

DATA ENTRY:

1. Changes entered in the Oil and Gas Database on: 2/28/2005
2. Changes have been entered on the Monthly Operator Change Spread Sheet on: 2/28/2005
3. Bond information entered in RBDMS on: 2/28/2005
4. Fee/State wells attached to bond in RBDMS on: 2/28/2005
5. Injection Projects to new operator in RBDMS on: 2/28/2005
6. Receipt of Acceptance of Drilling Procedures for APD/New on: waived

FEDERAL WELL(S) BOND VERIFICATION:

1. Federal well(s) covered by Bond Number: UT 0056

INDIAN WELL(S) BOND VERIFICATION:

1. Indian well(s) covered by Bond Number: 61BSBDH2912

FEE & STATE WELL(S) BOND VERIFICATION:

1. (R649-3-1) The **NEW** operator of any fee well(s) listed covered by Bond Number 61BSBDH2919
2. The **FORMER** operator has requested a release of liability from their bond on: n/a*
The Division sent response by letter on: n/a

LEASE INTEREST OWNER NOTIFICATION:

3. (R649-2-10) The **FORMER** operator of the fee wells has been contacted and informed by a letter from the Division of their responsibility to notify all interest owners of this change on: n/a

COMMENTS:

*Bond rider changed operator name from Inland Production Company to Newfield Production Company - received 2/23/05

DIVISION OF OIL, GAS AND MINING
UNDERGROUND INJECTION CONTROL PROGRAM
PERMIT
STATEMENT OF BASIS

Applicant: Newfield Production Company **Well:** Ashley 15-2-9-15

Location: 2/9S/15E **API:** 43-013-32579

Ownership Issues: The proposed well is located on land owned by the State of Utah (SITLA). The well is located in the Ashley Unit. Lands in the one-half mile radius of the well are administered by SITLA. The Federal Government and SITLA are the mineral owners within the area of review. Newfield and other various individuals hold the leases in the unit. Newfield has provided a list of all surface, mineral and lease holders in the half-mile radius. Newfield is the operator of the Ashley Unit. Newfield has submitted an affidavit stating that all owners and interest owners have been notified of their intent.

Well Integrity: The proposed well has surface casing set at 313 feet and has a cement top at the surface. A 5 ½ inch production casing is set at 6,150 feet. A cement bond log demonstrates adequate bond in this well up to 620 feet. A 2 7/8 inch tubing with a packer will be set at 4,510 feet. A mechanical integrity test will be run on the well prior to injection. There are 8 producing wells and 1 injection well in the area of review. All of the wells have evidence of adequate casing and cement. No corrective action will be required.

Ground Water Protection: According to Technical Publication No. 92 the base of moderately saline water is at a depth of approximately 500 feet. Injection shall be limited to the interval between 4,073 feet and 6,085 feet in the Green River Formation. All of these perforations will not be opened initially. Each time that new perforations are added and the packer is moved or disturbed an MIT shall be run to provide evidence of mechanical integrity. Information submitted by Newfield indicates that the fracture gradient for the 15-2-9-15 well is .79 psi/ft. which was the lowest reported fracture gradient for the injection zone. The resulting minimum fracture pressure for the proposed injection interval is 2,003 psig. The requested maximum pressure is 2,003 psig. The anticipated average injection pressure is 1100 psig. Injection at this pressure should not initiate any new fractures or propagate existing fractures in the adjacent confining intervals. Any ground water present should be adequately protected.

Ashley 15-2-9-15

page 2

Oil/Gas& Other Mineral Resources Protection: The Board of Oil, Gas & Mining approved the Ashley Unit August 25, 1998 . Correlative rights issues were addressed at this time. Previous reviews in this area indicate that other mineral resources in the area have been protected or are not at issue.

Bonding: Bonded with the State of Utah.

Actions Taken and Further Approvals Needed: A notice of agency action has been sent to the Salt Lake Tribune and the Uinta Basin Standard. A casing/tubing pressure test will be required prior to injection. It is recommended that approval of this application be granted.

Note: Applicable technical publications concerning water resources in the general vicinity of this project have been reviewed and taken into consideration during the permit review process.

Reviewer(s): Brad Hill Date 043/19/2005

Newspaper Agency Corporation

143 SOUTH MAIN ST.

P.O. BOX 45838

SALT LAKE CITY, UTAH 84145

FED. TAX I.D. # 87-0217663

The Salt Lake Tribune

DESERET
Morning News

CUSTOMER'S
COPY

PROOF OF PUBLICATION

CUSTOMER NAME AND ADDRESS	ACCOUNT NUMBER	DATE
DIV OF OIL-GAS & MINING 1594 W NORTH TEMP #1210 P.O. BOX 145801 SALT LAKE CITY, UT 84114	D5385340L-07	03/10/05

ACCOUNT NAME	
DIV OF OIL-GAS & MINING	
TELEPHONE	INVOICE NUMBER
801-538-5340	TL8202Q6Z91
SCHEDULE	
START 03/10/05 END 03/10/05	
CUST. REF. NO.	
CAPTION	
BEFORE THE DIVISION OF OIL, GA	
SIZE	
53 LINES 2.00 COLUMN	
TIMES	RATE
1	1.25
MISC. CHARGES	AD CHARGES
.00	137.50
TOTAL COST	
137.50	

BEFORE THE DIVISION OF OIL, GAS AND MINING
DEPARTMENT OF NATURAL RESOURCES
STATE OF UTAH
NOTICE OF AGENCY ACTION
CASE NO. UC 319

IN THE MATTER OF THE APPLICATION OF NEWFIELD EXPLORATION COMPANY FOR ADMINISTRATIVE APPROVAL OF THE ASHLEY STATE 9-2-9-15, ASHLEY STATE 15-2-15 AND THE ASHLEY FEDERAL 11-15-9-15 WELLS LOCATED IN SECTIONS 2 AND 15, TOWNSHIP 9 SOUTH, RANGE 15 EAST, DUCHESE COUNTY, UTAH, AS CLASS INJECTION WELLS

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Newfield Exploration Company for administrative approval of the Ashley State 9-2-9-15, Ashley State 15-2-15 and the Ashley Federal 11-15-9-15 wells, located in Sections 2 and 15, Township 9 South, Range 15 East, Duchesne County, Utah, for conversion to Class II injection wells. The adjudicative proceeding will be conducted informally according to Utah Admin. Rule R64-10, Administrative Procedures.

Selective zones in the Green River Formation will be used for water injection. The maximum requested injection pressure and rate will be determined based on fracture gradient information submitted by Newfield Exploration Company.

Any person desiring to object to the proposed application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for this proceeding is John R. Baza, Associate Director at PO Box 14580 Salt Lake City, Utah 84114-5801, phone number (801) 538-5340. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedure rules. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 2nd day of March, 2005.

STATE OF UTAH
DIVISION OF OIL, GAS & MINING
John R. Baza
Associate Director

8202Q6Z9

AFFIDAVIT OF PUBLICATION


AS NEWSPAPER AGENCY CORPORATION LEGAL BOOKKEEPER, I CERTIFY THAT THE ATTACHED ADVERTISEMENT OF BEFORE THE DIVISION OF OIL, GA FOR DIV OF OIL-GAS & MINING WAS PUBLISHED BY THE NEWSPAPER AGENCY CORPORATION, AGENT FOR THE SALT LAKE TRIBUNE AND DESERET NEWS, DAILY NEWSPAPERS PRINTED IN THE ENGLISH LANGUAGE WITH GENERAL CIRCULATION IN UTAH, AND PUBLISHED IN SALT LAKE CITY, SALT LAKE COUNTY IN THE STATE OF UTAH.

PUBLISHED ON START 03/10/05 END 03/10/05

SIGNATURE

DATE


03/10/05



THIS IS NOT A STATEMENT BUT A "PROOF OF PUBLICATION"
PLEASE PAY FROM BILLING STATEMENT.

COPY

Newfield Ashley State 9-2-9-15 /UIC-319.3



NEWFIELD



February 18, 2005

Mr. Dan Jarvis
State of Utah
Division of Oil, Gas and Mining
Post Office Box 145801
Salt Lake City, Utah 84114-5801

UIC - ~~319.2~~
319.2

RE: Permit Application for Water Injection Well
Ashley State #15-2-9-15
Monument Butte Field, Ashley Unit, Lease #ML-43538
Section 2 -Township 9S-Range 15E
Duchesne County, Utah

Dear Mr. Jarvis:

Newfield Production Company herein requests approval to convert the Ashley State #15-2-9-15 from a producing oil well to a water injection well in the Monument Butte (Green River) Field, Ashley Unit.

I hope you find this application complete; however, if you have any questions or require additional information, please contact me at (303) 893-0102.

Sincerely,

David Gerbig
Operations Engineer

RECEIVED
FEB 25 2005
DIV. OF OIL, GAS & MINING

NEWFIELD PRODUCTION COMPANY
APPLICATION FOR APPROVAL OF CLASS II INJECTION WELL
ASHLEY STATE #15-2-9-15
MONUMENT BUTTE FIELD (GREEN RIVER) FIELD
ASHLEY UNIT
LEASE #ML-43538
FEBRUARY 18, 2005


TABLE OF CONTENTS

LETTER OF INTENT	
COVER PAGE	
TABLE OF CONTENTS	
UIC FORM 1 – APPLICATION FOR INJECTION WELL	
WELLBORE DIAGRAM OF PROPOSED INJECTION	
WORK PROCEDURE FOR INJECTION CONVERSION	
COMPLETED RULE R615-5-1 QUESTIONNAIRE	
COMPLETED RULE R615-5-2 QUESTIONNAIRE	
ATTACHMENT A	ONE-HALF MILE RADIUS MAP
ATTACHMENT A-1	WELL LOCATION PLAT
ATTACHMENT B	LIST OF SURFACE OWNERS WITHIN ONE-HALF MILE RADIUS
ATTACHMENT C	CERTIFICATION FOR SURFACE OWNER NOTIFICATION
ATTACHMENT E	WELLBORE DIAGRAM – ASHLEY STATE #15-2-9-15
ATTACHMENT E-1	WELLBORE DIAGRAM – ASHLEY STATE #9-2-9-15
ATTACHMENT E-2	WELLBORE DIAGRAM – ASHLEY STATE #10-2-9-15
ATTACHMENT E-3	WELLBORE DIAGRAM – ASHLEY STATE #11-2-9-15
ATTACHMENT E-4	WELLBORE DIAGRAM – ASHLEY STATE #12-2-9-15
ATTACHMENT E-5	WELLBORE DIAGRAM – ASHLEY STATE #13-2-9-15
ATTACHMENT E-6	WELLBORE DIAGRAM – ASHLEY STATE #14-2-9-15
ATTACHMENT E-7	WELLBORE DIAGRAM – ASHLEY STATE #16-2-9-15
ATTACHMENT E-8	WELLBORE DIAGRAM – ASHLEY UNIT #13-1
ATTACHMENT E-9	WELLBORE DIAGRAM – ASHLEY UNIT #4-12-9-15
ATTACHMENT E-10	WELLBORE DIAGRAM – ASHLEY FEDERAL #1-11-9-15
ATTACHMENT E-11	WELLBORE DIAGRAM – ASHLEY #2-11-9-15
ATTACHMENT E-12	WELLBORE DIAGRAM – ASHLEY #3-11-9-15
ATTACHMENT E-13	WELLBORE DIAGRAM – ASHLEY #4-11-9-15
ATTACHMENT E-14	WELLBORE DIAGRAM – ASHLEY #6-11-9-15
ATTACHMENT E-15	WELLBORE DIAGRAM – ASHLEY #7-11-9-15
ATTACHMENT E-16	WELLBORE DIAGRAM – ASHLEY #8-11-9-15
ATTACHMENT F	WATER ANALYSIS
ATTACHMENT G	FRACTURE GRADIENT CALCULATIONS
ATTACHMENT G-1	FRACTURE REPORTS DATED 7/23/04
ATTACHMENT H	WORK PROCEDURE FOR PROPOSED PLUG AND ABANDON
ATTACHMENT H-1	WELLBORE DIAGRAM OF PROPOSED PLUGGED WELL

STATE OF UTAH
DIVISION OF OIL, GAS AND MINING

APPLICATION FOR INJECTION WELL - UIC FORM 1

OPERATOR Newfield Production Company
ADDRESS 1401 17th Street, Suite 1000
Denver, Colorado 80202

Well Name and number:		<u>Ashley State #15-2-9-15</u>	
Field or Unit name:		<u>Monument Butte (Green River), Ashley Unit</u>	Lease No. <u>ML-43538</u>
Well Location: QQ	<u>SW/SE</u>	section <u>2</u>	township <u>9S</u> range <u>15E</u> county <u>Duchesne</u>
Is this application for expansion of an existing project? Yes [X] No []			
Will the proposed well be used for:		Enhanced Recovery? Yes [X] No []	
		Disposal? Yes [] No [X]	
		Storage? Yes [] No [X]	
Is this application for a new well to be drilled?	 Yes [] No [X]	
If this application is for an existing well,			
has a casing test been performed on the well?		Yes [] No [X]	
Date of test: _____			
API number: <u>43-013-32579</u>			
Proposed injection interval: from <u>4073</u> to <u>6085</u>			
Proposed maximum injection: rate <u>500 bpd</u> pressure <u>2003</u> psig			
Proposed injection zone contains [x] oil, [] gas, and/or [] fresh water within 1/2 mile of the well.			
<div style="border: 1px solid black; padding: 5px; display: inline-block;">IMPORTANT: Additional information as required by R615-5-2 should accompany this form.</div>			
List of Attachments: <u>Attachments "A" through "H-1"</u>			
I certify that this report is true and complete to the best of my knowledge.			
Name:	<u>David Gerbig</u>	Signature	<u></u>
Title	<u>Operations Engineer</u>	Date	<u>2-21-05</u>
Phone No.	<u>(303) 893-0102</u>		
(State use only)			
Application approved by _____		Title _____	
Approval Date _____			
Comments:			

Ashley State 15-2-9-15

Spud Date: 6/14/04
Put on Production: 7/28/04
GL: 6020' KB: 6032'

Initial Production: BOPD,
MCFD, BWPD

Proposed Injection Wellbore Diagram

SURFACE CASING

CSG SIZE: 8 5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (303.01')
DEPTH LANDED: 313.01' KB
HOLE SIZE: 12 1/4"
CEMENT DATA: 150sxs Class "G" mixed cmt, est 4 bbls cmt to surf.


PRODUCTION CASING

CSG SIZE: 5 1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 144 jts. (6152.43')
DEPTH LANDED: 6150.43' KB
HOLE SIZE: 7 7/8"
CEMENT DATA: 300 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ mix.
CEMENT TOP AT: 80'

TUBING

SIZE/GRADE/WT: 2 7/8" / J-55 / 6.5#
NO. OF JOINTS: 183 jts (5859.84')
TUBING ANCHOR: 5871.84' KB
NO. OF JOINTS: 1 jt (31.52')
SEATING NIPPLE: 2 7/8" (1.10')
SN LANDED AT: 5906.16' KB
NO. OF JOINTS: 2 jts (65.07')
TOTAL STRING LENGTH: EOT @ 5972.78' w/ 12' KB

Cement Top @ 80'



FRAC JOB

07/23/04	5880-5900'	Frac CP3 sands as follows: 54,059# 20/40 sand in 494 bbls lightning Frac 17 fluid. Treated @ avg press of 1663 psi w/avg rate of 24.9 BPM. ISIP 2050 psi. Calc flush: 5878 gal. Actual flush: 5876 gal.
07/23/04	5670-5701'	Frac CP1 and .5 sands as follows: 34,304# 20/40 sand in 375 bbls lightning Frac 17 fluid. Treated @ avg press of 1869 psi w/avg rate of 24.6 BPM. ISIP 2015 psi. Calc flush: 5668 gal. Actual flush: 5670 gal.
07/23/04	5360-5380'	Frac LODC sands as follows: 39,721# 20/40 sand in 371 bbls lightning Frac 17 fluid. Treated @ avg press of 2028 psi w/avg rate of 19.4 BPM. ISIP 2330 psi. Calc flush: 5358 gal. Actual flush: 5359 gal.
07/23/04	4664-4674'	Frac DS1 sands as follows: 29,245# 20/40 sand in 300 bbls lightning Frac 17 fluid. Treated @ avg press of 2265 psi w/avg rate of 24.8 BPM. ISIP 2800 psi. Calc flush: 4662 gal. Actual flush: 4704 gal.
07/23/04	4545-4556'	Frac PB10 sands as follows: 28,142# 20/40 sand in 296 bbls lightning Frac 17 fluid. Treated @ avg press of 2360 psi w/avg rate of 24.7 BPM. ISIP 2500 psi. Calc flush: 4543 gal. Actual flush: 4452 gal.

PERFORATION RECORD

07/16/04	5880-5900'	4 JSPF	80 holes
07/23/04	5698-5701'	4 JSPF	12 holes
07/23/04	5670-5674'	4 JSPF	16 holes
07/23/04	5360-5380'	4 JSPF	80 holes
07/23/04	4664-4674'	4 JSPF	40 holes
07/23/04	4545-4556'	4 JSPF	44 holes

NEWFIELD



Ashley State 15-2-9-15

537' FNL & 2051' FEL

SW/SE Section 2-T9S-R15E

Duchesne Co, Utah

API #43-013-32579; Lease #ML-43538

MHB 07/29/2004

WORK PROCEDURE FOR INJECTION CONVERSION

1. Rig up hot oil truck to casing. Pump water. Unseat pump. Flush rods. Trip out of hole with rods and pump.
2. Trip out of hole with tubing, breaking and doping every connection. Trip in hole with packer and tubing. Rig up water truck to casing. Pump packer fluid. Set packer.
3. Test casing and packer.
4. Rig down and move out.

**REQUIREMENTS FOR INJECTION OF FLUIDS INTO RESERVOIRS
RULE R615-5-1**

- 1. Operations to increase ultimate recovery, such as cycling of gas, the maintenance of pressure, the introduction of gas, water or other substances into a reservoir for the purpose of secondary or other enhanced recovery or for storage and the injection of water into any formation for the purpose of water disposal shall be permitted only by order of the Board after notice and hearing.**
- 2. A request for agency action for authority for the injection of gas, liquified petroleum gas, air, water or any other medium into any formation for any reason, including but not necessarily limited to the establishment of or the expansion of waterflood projects, enhanced recovery projects, and pressure maintenance projects shall contain:**

2.1 The name and address of the operator of the project.

Newfield Production Company
1401 17th Street, Suite 1000
Denver, Colorado 80202

2.2 A plat showing the area involved and identifying all wells, including all proposed injection wells, in the project area and within one-half mile of the project area.

See Attachment A.

2.3 A full description of the particular operation for approval is requested.

Approval is requested to convert the Ashley State #15-2-9-15 from a producing oil well to a water injection well in Monument Butte (Green River) Field, Ashley Unit.

2.4 A description of the pools from which the identified wells are producing or have produced.

The proposed injection well will inject into the Green River Formation.

2.5 The names, description and depth of the pool or pools to be affected.

The injection zone is in the Green River Formation. In the Ashley State #15-2-9-15 well, the proposed injection zone is from Garden Gulch to Basal Limestone (4073' - 6085'). The confining strata directly above and below the injection zones are the Garden Gulch and Castle Peak Members of the Green River Formation, with the Garden Gulch Marker top at 4073' and the Castle Peak top at 5654'.

2.6 A copy of a log of a representative well completed in the pool.

The referenced log for the Ashley State #15-2-9-15 is on file with the Utah Division of Oil, Gas and Mining.

- 2.7 A statement as to the type of fluid to be used for injection, its source and the estimated amounts to be injected daily.**

The primary type and source of fluid to be used for injection will be culinary water from the Johnson Water District supply line. The secondary type of fluid to be used for injection will be culinary water from the Johnson Water District commingled with produced water. The average estimated injection of fluids will be at a rate of 300 BPD, and the estimated maximum injection will be at a rate of 500 BPD.

- 2.8 A list of all operators and surface owners within one-half mile radius of the proposed project.**

See Attachment B.

- 2.9 An affidavit certifying that said operators or owners and surface owners within a one-half mile radius have been provided a copy of the petition for injection.**

See Attachment C.

- 2.10 Any additional information the Board may determine is necessary to adequately review the petition.**

Newfield Production Company will supply any additional information requested by the Utah Division of Oil, Gas and Mining.

- 4.0 Establish recovery projects may be expanded and additional wells placed on injection only upon authority from the Board after notice and hearing or by administrative approval.**

This proposed injection well is on a State lease (Lease #ML-43538) in the Monument Butte (Green River) Field, Ashley Unit, and this request is for administrative approval.

**REQUIREMENTS FOR CLASS II INJECTION WELLS INCLUDING WATER DISPOSAL,
STORAGE AND ENHANCED RECOVERY WELLS
SECTION V – RULE R615-5-2**

- 1. Injection well shall be completed, equipped, operated, and maintained in a manner that will prevent pollution and damage to any USDW, or other resources and will confine injected fluids to the interval approved.**
- 2. The application for an injection well shall include a properly completed Form DOGM-UIC-1 and the following:**

- 2.1 A plat showing the location of the injection well, all abandoned or active wells within a one-half mile radius of the proposed wells, and the surface owner and the operator of any lands or producing leases, respectively, within a one-half mile radius of the proposed injection well.**

See Attachments A and B.

- 2.2 Copies of electrical or radioactive logs, including gamma ray logs, for the proposed well run prior to the installation of casing and indicating resistivity, spontaneous potential, caliper and porosity.**

All logs are on file with the Utah Division of Oil, Gas and Mining.

- 2.3 A copy of a cement bond or comparable log run for the proposed injection well after casing was set and cemented.**

A copy of the cement bond log is on file with the Utah Division of Oil, Gas and Mining.

- 2.4 Copies of logs already on file with the Division should be referenced, but need not be refiled.**

All copies of logs are on file with the Utah Division of Oil, Gas and Mining.

- 2.5 A description of the casing or proposed casing program of the injection well and of the proposed method for testing the casing before use of the well.**

The casing program is 8-5/8", 24#, J-55 surface casing run to 313' GL, and 5-1/2" 15.5# J-55 casing run from surface to 6150' KB. A casing integrity test will be conducted at the time of conversion. See Attachment E.

- 2.6 A statement as to the type of fluid to be used for injection, its source and estimated amounts to be injected daily.**

The primary type and source of fluid to be used for injection will be culinary water from the Johnson Water District supply line. The secondary type of fluid to be used for injection will be culinary water from the Johnson Water District commingled with produced water. The estimated average rate of injection will be 300 BPD, and the estimated maximum rate of injection will be 500 BPD.

- 2.7 Standard laboratory analysis of the fluid to be injected, the fluid in the formation into which the fluid is being injected, and the compatibility of the fluids.**

See Attachment F.

The proposed average and maximum injection pressures.

The proposed average injection pressure will be approximately 1100 psig and the maximum injection pressure will not exceed 2003 psig.

- 2.8 Evidence and data to support a finding that the proposed injection well will not initiate fractures through the overlying strata or a confining interval that could enable the injected fluid or formation fluid to enter the fresh water strata.**

The minimum fracture gradient for the Ashley State #15-2-9-15, for existing perforations (4545' - 5900') calculates at 0.79 psig/ft. The maximum injection pressures will be limited so as not to exceed this gradient. A step rate test will be performed periodically to ensure we are below parting pressure. The proposed maximum injection pressure is 2003 psig. We may add additional perforations between 4073' and 6160'. See Attachments G and G-1.

- 2.9 Appropriate geological data on the injection interval and confining beds, including the geologic name, lithologic description, thickness, depth, and lateral extent.**

In the Ashley State #15-2-9-15, the proposed injection zone (4073' - 6085') is in the Garden Gulch to Basal limestone members of the Green River Formation. The reservoir is a very fine-grained sandstone with minor imbedded shale streaks. The estimated porosity is 13%. The members are composed of porous and permeable lenticular calcareous sandstone and low porosity carbonates and calcareous shale. The porous and lenticular sandstone varies in thickness from 0-31' and is confined to the Monument Butte Field. Outside the Monument Butte Field, the sandstone is composed of tight, very fine, silty, calcareous sandstone, less than 3' thick. The stratum confining the injection zone is composed of tight, moderately calcareous, sandy lacustrine shale. All of the confining strata are impermeable, and will effectively seal off the oil, gas, and water of the injection zone from any strata directly above or below it.

- 2.10 A review of the mechanical condition of each well within a one-half mile radius of the proposed injection well to assure that no conduit exists that could enable fluids to migrate up or down the wellbore and enter the improper intervals.**

See Attachments E through E-16.

Additionally, the injection system will be equipped with high and low pressure shut down devices that will automatically shut in injection waters if a system blockage or leakage occurs. One way check valves will also ensure proper flow management. Relief valves will also be utilized for high-pressure relief.

- 2.11 An affidavit certifying that a copy of the application has been provided to all operators or owners, and surface owners within a one-half mile radius of the proposed injection well.**


See Attachment C.

- 2.12 Any other information that the Board or Division may determine is necessary to adequately review the application.**

Newfield Production Company will supply any requested information to the Board or Division.

ML -43538

URU - 74826



Well Status

- Location
- Surface Spud
- Drilling
- Waiting on Completion
- Producing Oil Well
- ★ Producing Gas Well
- ⊙ Water Injection Well
- ⊙ Dry Hole
- ⊙ Temporarily Abandoned
- ⊙ Plugged & Abandoned
- ⊙ Shut In

Injection system

- high pressure
- - - low pressure
- ... proposed
- return
- - - return proposed

Gas Pipelines

- Gathering lines
- ... Proposed lines
- 1/2 mile radius of 15-2-9-15

Attachment A

Ashley 15-2-9-15
Section 2, T9S-R15E



1/2 Mile Radius Map
Duchesne County

Alamo Plaza Building
1401 17th Street Suite 1000
Denver, Colorado 80202-1247
Phone: (303) 893-0102

January 14, 2005

T9S, R15E, S.L.B.&M.

INLAND PRODUCTION COMPANY

WELL LOCATION, ASHLEY UNIT 15-2,
LOCATED AS SHOWN IN THE SW 1/4 SE
1/4 OF SECTION 2, T9S, R15E, S.L.B.&M.
DUCESNE COUNTY, UTAH.

Attachment A-1




THIS IS TO CERTIFY THAT THE ABOVE PLAND WAS
PREPARED FROM FIELD NOTES OF ACTUAL SURVEY
MADE BY ME OR UNDER MY SUPERVISION AND THAT
THE SAME ARE TRUE AND CORRECT TO THE BEST OF
MY KNOWLEDGE AND BELIEF

REGISTERED LAND SURVEYOR
No. 189377
STACY W. STEWART
REGISTERED LAND SURVEYOR
REGISTRATION No. 189377
STATE OF UTAH

TRI STATE LAND SURVEYING & CONSULTING
180 NORTH VERNAL AVENUE - VERNAL, UTAH 84078
(435) 781-2501

SCALE: 1" = 1000'	SURVEYED BY: D.J.S.
DATE: 3-15-04	DRAWN BY: J.R.S.
NOTES:	FILE #



◆ = SECTION CORNERS LOCATED

BASIS OF ELEV; U.S.G.S. 7-1/2 min QUAD (MYTON SW)

EXHIBIT B

Page 1

#	Land Description	Minerals Ownership & Expires	Minerals Leased By	Surface Rights
1	Township 9 South, Range 15 East Section 1: All Section 3: All Section 10: All Section 11: All Section 12: All	U-74826 HBP	Inland Production Company	(Surface Rights) USA
2	Township 9 South, Range 15 East Section 2: All	ML-43538 HBP	Inland Production Company	(Surface Rights) State of Utah

9-2-9-15INJ

ATTACHMENT C

CERTIFICATION FOR SURFACE OWNER NOTIFICATION

RE: Application for Approval of Class II Injection Well
Ashley State #15-2-9-15

I hereby certify that a copy of the injection application has been provided to all surface owners within a one-half mile radius of the proposed injection well.

Signed: David Gerbig
Newfield Production Company
David Gerbig
Operations Engineer

Sworn to and subscribed before me this 21st day of February, 2005.

Notary Public in and for the State of Colorado: Frank Bahr

My Commission Expires: 8/29/05

Ashley State 15-2-9-15

Spud Date: 6/14/04
 Put on Production: 7/28/04
 GL: 6020' KB: 6032'

Initial Production: BOPD,
 MCFD, BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8 5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts. (303.01')

DEPTH LANDED: 313.01' KB

HOLE SIZE: 12 1/4"

CEMENT DATA: 150sxs Class "G" mixed cmt, est 4 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5 1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 144 jts. (6152.43')

DEPTH LANDED: 6150.43' KB

HOLE SIZE: 7 7/8"

CEMENT DATA: 300 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ mix.

CEMENT TOP AT: 80'

TUBING

SIZE/GRADE/WT.: 2 7/8" / J-55 / 6.5#

NO. OF JOINTS: 183 jts (5859.84')

TUBING ANCHOR: 5871.84' KB

NO. OF JOINTS: 1 jt (31.52')

SEATING NIPPLE: 2 7/8" (1.10')

SN LANDED AT: 5906.16' KB

NO. OF JOINTS: 2 jts (65.07')

TOTAL STRING LENGTH: EOT @ 5972.78' w/ 12' KB

SUCKER RODS

POLISHED ROD: 1 1/2" x 22'

SUCKER RODS: 1-8', 1-6', 1-4' x 3/4" pony rods, 126-3/4" scraped rods, 82-3/4" plain rods, 20-3/4" scraped rods, 6-1 1/2" weight rods.

PUMP SIZE: 2 1/2" x 1 1/2" x 15.5" RHAC pump w/ SM Plunger

STROKE LENGTH: 84"

PUMP SPEED, SPM: 7 SPM

LOGS: DIGL/SP/GR/CAL

FRAC JOB

07/23/04 5880-5900'

Frac CP3 sands as follows:

54,059# 20/40 sand in 494 bbls lightning Frac 17 fluid. Treated @ avg press of 1663 psi w/avg rate of 24.9 BPM. ISIP 2050 psi. Calc flush: 5878 gal. Actual flush: 5876 gal.

07/23/04 5670-5701'

Frac CP1 and .5 sands as follows:

34,304# 20/40 sand in 375 bbls lightning Frac 17 fluid. Treated @ avg press of 1869 psi w/avg rate of 24.6 BPM. ISIP 2015 psi. Calc flush: 5668 gal. Actual flush: 5670 gal.

07/23/04 5360-5380'

Frac LODC sands as follows:

39,721# 20/40 sand in 371 bbls lightning Frac 17 fluid. Treated @ avg press of 2028 psi w/avg rate of 19.4 BPM. ISIP 2330 psi. Calc flush: 5358 gal. Actual flush: 5359 gal.

07/23/04 4664-4674'

Frac DS1 sands as follows:

29,245# 20/40 sand in 300 bbls lightning Frac 17 fluid. Treated @ avg press of 2265 psi w/avg rate of 24.8 BPM. ISIP 2800 psi. Calc flush: 4662 gal. Actual flush: 4704 gal.


07/23/04 4545-4556'

Frac PB10 sands as follows:

28,142# 20/40 sand in 296 bbls lightning Frac 17 fluid. Treated @ avg press of 2360 psi w/avg rate of 24.7 BPM. ISIP 2500 psi. Calc flush: 4543 gal. Actual flush: 4452 gal.

PERFORATION RECORD

07/16/04	5880-5900'	4 JSPF	80 holes
07/23/04	5698-5701'	4 JSPF	12 holes
07/23/04	5670-5674'	4 JSPF	16 holes
07/23/04	5360-5380'	4 JSPF	80 holes
07/23/04	4664-4674'	4 JSPF	40 holes
07/23/04	4545-4556'	4 JSPF	44 holes

**NEWFIELD**

Ashley State 15-2-9-15

537' FNL & 2051' FEL

SW/SE Section 2-T9S-R15E

Duchesne Co, Utah

API #43-013-32579; Lease #ML-43538

Ashley State 9-2-9-15

Spud Date: 7/12/04
Put on Production: 8/19/2004

GL: 5993' KB: 6005'

SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts (303.72')

DEPTH LANDED: 313.72' KB

HOLE SIZE: 12-1/4"

CEMENT DATA: 150 sxs Class "G" cmt, est 3 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 145 jts (6163.01')

DEPTH LANDED: 6157.01' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 285 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ.

CEMENT TOP AT: 220'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#

NO. OF JOINTS: 174 jts (5654.03')

TUBING ANCHOR: 5666.03' KB

NO. OF JOINTS: 3 jts (97.51')

SEATING NIPPLE: 2-7/8" (1.10')

SN LANDED AT: 5766.34' KB

NO. OF JOINTS: 2 jts (64.97')

TOTAL STRING LENGTH: EOT @ 5832.86' KB

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' SM

SUCKER RODS: 6 1-1/2" weight bars; 10-3/4" scraped rods; 115-3/4" plain rods; 99-3/4" scraped rods; 2-8", 1-2" x 3/4" pony rods.


PUMP SIZE: 2-1/2" x 1-1/2" x 12" x 15' RHAC

STROKE LENGTH: 86"

PUMP SPEED, SPM: 6 SPM

LOGS: DIGL/SP/GR/CAL

Wellbore Diagram



Initial Production: BOPD,
MCFD, BWPD

FRAC JOB

8/16/04	5713'-5784'	Frac CP1 and CP.5 sands as follows: 74,491# 20/40 sand in 585 bbls Lightning 17 frac fluid. Treated @ avg press of 1774 psi w/avg rate of 24.7 BPM. ISIP 2100 psi. Calc flush: 5711 gal. Actual flush: 5708 gal.
8/16/04	5412'-5422'	Frac LODC sands as follows: 38,832# 20/40 sand in 373 bbls Lightning 17 frac fluid. Treated @ avg press of 2150 psi w/avg rate of 19.5 BPM. ISIP 2400 psi. Calc flush: 5410 gal. Actual flush: 5410 gal.
8/16/04	5078'-5132'	Frac B1 and B2 sands as follows: 24,910# 20/40 sand in 288 bbls Lightning 17 frac fluid. Treated @ avg press of 1647 psi w/avg rate of 19.7 BPM. ISIP 2000 psi. Calc flush: 5076 gal. Actual flush: 5074 gal.
8/16/04	4581'-4602'	Frac PB10 sands as follows: 17,013# 20/40 sand in 213 bbls Lightning 17 frac fluid. Treated @ avg press of 2187 psi w/avg rate of 19.5 BPM. ISIP 2400 psi. Calc flush: 4579 gal. Actual flush: 4494 gal.

PERFORATION RECORD

8/10/04	5780'-5784'	4 JSPF	16 holes
8/10/04	5744'-5764'	4 JSPF	80 holes
8/10/04	5713'-5721'	4 JSPF	32 holes
8/16/04	5412'-5422'	4 JSPF	40 holes
8/16/04	5122'-5132'	4 JSPF	40 holes
8/16/04	5078'-5084'	4 JSPF	24 holes
8/16/04	4598'-4602'	4 JSPF	16 holes
8/16/04	4581'-4587'	4 JSPF	24 holes

NEWFIELD

Ashley State 9-2-9-15

1981' FSL & 660' FEL

NESE Section 2-T9S-R15E

Duchesne Co, Utah

API #43-013-32438; Lease #ML 43538

Ashley State 10-2-9-15

Spud Date: 06/02/04

Put on Production: 7/16/04

GL: 6069' KB: 6081'

SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts (305.32')

DEPTH LANDED: 315.32' KB

HOLE SIZE: 12-1/4"

CEMENT DATA: 150sxs Class "G" crmt, est 3 bbls crmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 144 jts (6146.13')

DEPTH LANDED: 6144.13' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 275 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ mix.

CEMENT TOP AT: Surface

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#

NO. OF JOINTS: 189 jts (5949.34')

TUBING ANCHOR: 5961.34' KB

NO. OF JOINTS: 1 jt (31.5')

SEATING NIPPLE: 2 7/8" (1.10')

SN LANDED AT: 5995.64' KB

NO. OF JOINTS: 2 jts (62.99')

TOTAL STRING LENGTH: EOT @ 6060.18' w/ 12' KB

SUCKER RODS

POLISHED ROD: 1 1/2" x 22'

SUCKER RODS: 1-8", 1-6", 1-4", 1-2" x 3/4" pony rods, 99-3/4" scraped rods; 124-3/4" plain rods, 10-3/4" scraped rods, 6-1 1/2" weight rods.

PUMP SIZE: 2 1/2" x 1 1/2" x 16" RHAC pump w/ SM Plunger


STROKE LENGTH: 86"

PUMP SPEED, SPM: 6 SPM

LOGS: DIGL/SP/GR/CAL

Wellbore Diagram

Cement Top @ Surface

FRAC JOB

7/07/04	6033'-6038'	Frac CP5 sands as follows: 25,542# 20/40 sand in 319 bbls lightning Frac 17 fluid. Treated @ avg press of 2005 psi w/avg rate of 24.7 BPM. ISIP 2300 psi. Calc flush: 6031 gal. Actual flush: 6065 gal.
7/12/04	5918'-5928'	Frac CP3 sands as follows: 58,042# 20/40 sand in 494 bbls lightning Frac 17 fluid. Treated @ avg press of 1981 psi w/avg rate of 24.5 BPM. ISIP 1680 psi. Calc flush: 5916 gal. Actual flush: 5914 gal.
7/12/04	5382'-5391'	Frac LODC sands as follows: 35,473# 20/40 sand in 370 bbls lightning Frac 17 fluid. Treated @ avg press of 2667 psi w/avg rate of 24.2 BPM. ISIP 2320 psi. Calc flush: 5380 gal. Actual flush: 5376 gal.
7/12/04	5130'-5138'	Frac B2 sands as follows: 30,393# 20/40 sand in 338 bbls lightning Frac 17 fluid. Treated @ avg press of 2817 psi w/avg rate of 24.7 BPM. ISIP 2080 psi. Calc flush: 5128 gal. Actual flush: 5166 gal.
7/12/04	4962'-5054'	Frac B.5 and C sands as follows: 56,741# 20/40 sand in 458 bbls lightning Frac 17 fluid. Treated @ avg press of 2411 psi w/avg rate of 24.3 BPM. ISIP 2245 psi. Calc flush: 4960 gal. Actual flush: 4956 gal.
7/12/04	4815'-4850'	Frac D1 sands as follows: 74,010# 20/40 sand in 562 bbls lightning Frac 17 fluid. Treated @ avg press of 2040 psi w/avg rate of 24.6 BPM. ISIP 2430 psi. Calc flush: 4813 gal. Actual flush: 4855 gal.
7/12/04	4711'-4721'	Frac DS1 sands as follows: 50,328# 20/40 sand in 414 bbls lightning Frac 17 fluid. Treated @ avg press of 2100 psi w/avg rate of 24.8 BPM. ISIP 2350 psi. Calc flush: 4709 gal. Actual flush: 4624 gal.

PERFORATION RECORD

7/02/04	6033-6038'	4 JSPF	20 holes
7/12/04	5918-5928'	4 JSPF	40 holes
7/12/04	5382-5391'	4 JSPF	36 holes
7/12/04	5130-5138'	4 JSPF	32 holes
7/12/04	5050-5054'	4 JSPF	16 holes
7/12/04	5002-5006'	4 JSPF	16 holes
7/12/04	4990-4995'	4 JSPF	20 holes
7/12/04	4962-4972'	4 JSPF	40 holes
7/13/04	4841-4850'	4 JSPF	36 holes
7/13/04	4815-4828'	4 JSPF	52 holes
7/13/04	4711-4721'	4 JSPF	40 holes



Inland Resources Inc.

Ashley State 10-2-9-15

2093' FNL & 2056' FEL

NWSE Section 2-T9S-R15E

Duchesne County, Utah

API #43-013-32574; Lease #ML-43538

Ashley State 11-2-9-15

Spud Date: 6/2/04
Put on Production: 7/27/04
GL: 6028' KB: 6040'

Initial Production: BOPD,
MCFD, BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8 5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts. (300.16')

DEPTH LANDED: 310.16' KB

HOLE SIZE: 12 1/4"

CEMENT DATA: 160sxs Class "G" mixed cmt, est 7 bbls cmt to surf

PRODUCTION CASING

CSG SIZE: 5 1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 144 jts. (6164.61')

DEPTH LANDED: 6162.61' KB

HOLE SIZE: 7 7/8"

CEMENT DATA: 275 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ mix.

CEMENT TOP AT: at surface

TUBING

SIZE/GRADE/WT.: 2 7/8" / J-55 / 6.5#

NO. OF JOINTS: 182 jts (5877.51')

TUBING ANCHOR: 5889.51' KB

NO. OF JOINTS: 1 jt (32.52')

SEATING NIPPLE: 2 7/8" (1.10')

SN LANDED AT: 5924.83' KB

NO. OF JOINTS: 2 jts (65.04')

TOTAL STRING LENGTH: EOT @ 5991.42' w/ 12' KB

SUCKER RODS

POLISHED ROD: 1 1/2" x 22'

SUCKER RODS: 1-6', 1-4', & 1-2' x 3/4" pony rods, 2-3/4" plain rods, 100-3/4" scraped rods, 120-3/4" plain rods, 10-3/4" scraped rods, 6-1 1/2" weight rods.

PUMP SIZE: 2 1/2" x 1 1/2" x 16" RHAC pump w/ SM Plunger

STROKE LENGTH: 86"

PUMP SPEED, SPM: 6 SPM


LOGS: DIGL/SP/GR/CAL

FRAC JOB

07/20/04	5926-5946'	Frac CP3 sands as follows: 43,993# 20/40 sand in 456 bbls lightning Frac 17 fluid. Treated @ avg press of 1947 psi w/avg rate of 27.5 BPM. ISIP 2150 psi. Calc flush: 5924 gal. Actual flush: 5922 gal.
07/20/04	5776-5786'	Frac CP1 sands as follows: 19,621# 20/40 sand in 282 bbls lightning Frac 17 fluid. Treated @ avg press of 1990 psi w/avg rate of 24.6 BPM. ISIP 2250 psi. Calc flush: 5774 gal. Actual flush: 5775 gal.
07/20/04	5469-5479'	Frac LODC sands as follows: 35,046# 20/40 sand in 372 bbls lightning Frac 17 fluid. Treated @ avg press of 2145 psi w/avg rate of 24.7 BPM. ISIP 2500 psi. Calc flush: 5467 gal. Actual flush: 5460 gal.
07/21/04	5101-5106'	Frac B2 sands as follows: 15,946# 20/40 sand in 212 bbls lightning Frac 17 fluid. Treated @ avg press of 2358 psi w/avg rate of 24.7 BPM. ISIP 4200 psi. Calc flush: 5099 gal. Actual flush: 3780 gal.
07/21/04	4972-4979'	Frac C sands as follows: 29,454# 20/40 sand in 337 bbls lightning Frac 17 fluid. Treated @ avg press of 2344 psi w/avg rate of 30.6 BPM. ISIP 2400 psi. Calc flush: 4970 gal. Actual flush: 4998 gal.
07/21/04	4798-4839'	Frac D2 and 1 sands as follows: 148,377# 20/40 sand in 981 bbls lightning Frac 17 fluid. Treated @ avg press of 1990 psi w/avg rate of 24.5 BPM. ISIP 2500 psi. Calc flush: 4970 gal. Actual flush: 4998 gal.
07/21/04	5469-5479'	Frac DS1 sands as follows: Decision made to leave behind stage #7
07/21/04	5776-5786'	
07/21/04	5926-5946'	
07/21/04	4798-4813'	

PERFORATION RECORD

07/09/04	5926-5946'	4 JSPF	80 holes
07/20/04	5776-5786'	4 JSPF	40 holes
07/20/04	5469-5479'	4 JSPF	40 holes
07/20/04	5101-5106'	4 JSPF	20 holes
07/21/04	4972-4979'	4 JSPF	28 holes
07/21/04	4826-4839'	4 JSPF	52 holes
07/21/04	4798-4813'	4 JSPF	60 holes



Inland Resources Inc.

Ashley State 11-2-9-15

1982' FSL & 2078' FWL

NE/SW Section 2-T9S-R15E

Duchesne Co, Utah

API #43-013-32575; Lease #ML-43538

Ashley State 12-2-9-15

Spud Date: 7/1/04
Put on Production: 8/11/04
GL: 5996' KB: 6008'

Initial Production:

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8 5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts (310.87')
DEPTH LANDED: 320.87' KB
HOLE SIZE: 12 1/4"
CEMENT DATA: 150 sxs class "G" mixed cmt, est 4 bbls cmt to surf.

Cement top @ 70'

PRODUCTION

CSG SIZE: 5 1/2"
GRADE: J-55
LENGTH: 144 jts (6140.92')
DEPTH LANDED: 6138.92' KB
HOLE SIZE: 7 7/8"
CEMENT DATA: 285 sxs Prem. Lite II mixed & 400 sxs 50/50 Poz mix.
CEMENT TOP AT: 70'

TUBING

SIZE/GRADE/WT: 2 7/8" / J-55 / 6.5#
NO. OF JOINTS: 178 jts. @ 5754.34'
TUBING ANCHOR: 5766.34' KB
NO. OF JOINTS: 1 jt. (32.56')
SEATING NIPPLE: 2 7/8" (1.10')
SN LANDED AT: (5801.70') KB
NO. OF JOINTS: 1 jt. (32.52')
TOTAL STRING LENGTH: EOT @ 5835.77' W/ 12' KB

SUCKER RODS

POLISHED RODS: 1 1/2" x 22'
SUCKER RODS: 1-6", 1-2' x 3/4" pony rods, 100- 3/4" scraped rods, 116-3/4" plain rods, 10-3/4" scraped rods, 6- 1 1/2" wt. bars.
PUMP SIZE: 2 1/2" x 1 1/2" x 16" RHAC W/ SM Plunger
STROKE LENGTH: 78"
SPM: 6.5 SPM

FRAC JOB

8/05/04 5794'-5801' **Frac CP2 sands as follows:**
13,834# 20/40 sand in 254 bbls Lightning 17 frac fluid. Treated @ avg pressure of 2253 psi w/avg rate of 24.6 BPM. ISIP 1980 psi. Calc flush: 5792 gal. Actual flush: 5788 gal.

8/05/04 5374'-5394' **Frac LODC sands as follows:**
74,425# 20/40 sand in 571 bbls Lightning 17 frac fluid. Treated @ avg pressure of 2183 psi w/avg rate of 19.7 BPM. ISIP 2500 psi. Calc flush: 5372 gal. Actual flush: 5372 gal.


8/05/04 4920'-4928' **Frac C sands as follows:**
19,600# 20/40 sand in 266 bbls Lightning 17 frac fluid. Treated @ avg pressure of 2148 psi w/avg rate of 24.9 BPM. ISIP 1970 psi. Calc flush: 4918 gal. Actual flush: 4918 gal.

8/05/04 4754'-4764' **Frac D1 sands as follows:**
34,627# 20/40 sand in 369 bbls Lightning 17 frac fluid. Treated @ avg pressure of 1849 psi w/avg rate of 20 BPM. ISIP 2240 psi. Calc flush: 4752 gal. Actual flush: 4750 gal.

8/05/04 4186'-4236' **Frac GB4 sands as follows:**
114,287# 20/40 sand in 770 bbls Lightning 17 frac fluid. Treated @ avg pressure of 1796 psi w/avg rate of 24.9 BPM. ISIP 2120 psi. Calc flush: 4184 gal. Actual flush: 4074 gal.

Perforation Record

08-02-04	5794-5801'	4 JSFP	28 holes
08-05-04	5374-5394'	4 JSFP	80 holes
08-05-04	4920-4928'	4 JSFP	32 holes
08-05-04	4754-4764'	4 JSFP	40 holes
08-05-04	4223-4236'	4 JSFP	52 holes
08-05-04	4186-4200'	4 JSFP	56 holes



Inland Resources Inc.

Ashley State 12-2-9-15

1978' FSL & 638' FWL

NW/SW Section 2-T9S-R15E

Duchesne Co, Utah

API #43-013-32576; Lease #ML-43538

Ashley State 13-2-9-15

Spud Date: 6/26/04
Put on Production: 8/5/04
GL: 6084' KB: 6096'

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (311.15')
DEPTH LANDED: 321.15' KB
HOLE SIZE: 12-1/4"
CEMENT DATA: 150 sxs Class "G" cmt, est 4 bbls cmt to surf.

Cement Top @ 350'

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 145 jts. (6161.79')
DEPTH LANDED: 6159.79' KB
HOLE SIZE: 7-7/8"
CEMENT DATA: 285 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ.
CEMENT TOP AT: 350'


TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 180 jts (5849.57')
TUBING ANCHOR: 5861.57' KB
NO. OF JOINTS: 1 jts (32.45')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 5896.82' KB
NO. OF JOINTS: 2 jts (64.88')
TOTAL STRING LENGTH: EOT @ 5963.25' W/12" KB

SUCKER RODS

POLISHED ROD: 1-1/2" x 22'
SUCKER RODS: 6-1 1/2" weight bars; 10-3/4" scraped rods; 119-3/4" plain rods, 100-3/4" scraped rods, 1-8", 1-6", 1-2" x 3/4" pony rods.
PUMP SIZE: 2-1/2" x 1-1/2" x 14' RHAC pump w/ SM Plunger
STROKE LENGTH: 74"
PUMP SPEED, SPM: 7 SPM
LOGS: DIGL/SP/GR/CAL

Wellbore Diagram

FRAC JOB

7/29/04 5760'-5888' **Frac CP1,2 and3 sands as follows:**
199,069# 20/40 sand in 1341 bbls Lightning 17 Frac fluid. Treated @ avg press of 1681 psi w/avg rate of 39.2 BPM. ISIP 1900psi. Calc flush: 5758 gal. Actual flush: 5754 gal.

7/29/04 5116'-5126' **Frac B2 sands as follows:**
29,553# 20/40 sand in 323 bbls Lightning 17 Frac fluid. Treated @ avg press of 1874 psi w/avg rate of 19 BPM. ISIP 1750 psi. Calc flush: 5114 gal. Actual flush: 5158 gal.

7/30/04 4531'-4589' **Frac PB10 sands as follows:**
70,620# 20/40 sand in 525 bbls Lightning 17 Frac fluid. Treated @ avg press of 1686 psi w/avg rate of 24.7 BPM. ISIP 2100 psi. Calc flush: 4529 gal. Actual flush: 4528 gal.

7/30/04 4247'-4255' **Frac GB4 sands as follows:**
15,241# 20/40 sand in 219 bbls Lightning 17 Frac fluid. Treated @ avg press of 2014 psi w/avg rate of 24 BPM. ISIP 2200 psi. Calc flush: 4245 gal. Actual flush: 4158 gal.

DID NOT FRAC

PERFORATION RECORD

Date	Depth Range	Tool Joint	Holes
7/27/04	5874'-5888'	4 JSPF	56 holes
7/27/04	5845'-5856'	4 JSPF	44 holes
7/27/04	5828'-5838'	4 JSPF	40 holes
7/27/04	5760'-5778'	4 JSPF	72 holes
7/29/04	5116'-5126'	4 JSPF	40 holes
7/29/04	4980'-4990'	4 JSPF	40 holes
7/30/04	4579'-4589'	4 JSPF	40 holes
7/30/04	4531'-4541'	4 JSPF	40 holes
7/30/04	4247'-4255'	4 JSPF	32 holes



Ashley State 13-2-9-15
661 FSL & 670 FWL
SWSW Section 2-T9S-R15E
Duchesne Co, Utah
API #43-013-32577; Lease # ML-43538

Ashley State 14-2-9-15

Spud Date: 6/14/04
Put on Production: 8/2/04

GL: 6051' KB: 6063'

SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts (296.19')

DEPTH LANDED: 306.19' KB

HOLE SIZE: 12-1/4"

CEMENT DATA: 150 sxs Class "G" cmt, est 3 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 145 jts (6169.25')

DEPTH LANDED: 6167.25' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 300 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ.

CEMENT TOP AT: 50'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#

NO. OF JOINTS: 181 jts (5855.75')

TUBING ANCHOR: 5867.75' KB

NO. OF JOINTS: 1 jts (32.52')

SEATING NIPPLE: 2-7/8" (1.10')

SN LANDED AT: 5903.07' KB

NO. OF JOINTS: 2 jts (65.02')

TOTAL STRING LENGTH: EOT @ 5969.64' W/12"KB

SUCKER RODS

POLISHED ROD: 1-1/2" x 22'

SUCKER RODS: 6-1 1/2" weight bars, 10-3/4" scraped rods, 120-3/4" plain rods, 100-3/4" scraped rods, 1-4', 1-2" x 3/4" pony rods.

PUMP SIZE: 2-1/2" x 1-1/2" x 15.5" RHAC pump w/ SM Plunger


STROKE LENGTH: 84"

PUMP SPEED, SPM: 7 SPM

LOGS: DIGL/SP/GR/CAL

Wellbore Diagram

Cement Top @ 50'

**FRAC JOB**

7/26/04	5888'-5908'	Frac CP3 sands as follows: 79,627# 20/40 sand in 614 bbls Lightning 17 Frac fluid. Treated @ avg press of 1705 psi w/avg rate of 25.1 BPM. ISIP 2000 psi. Calc flush: 5885 gal. Actual flush: 5884 gal.
7/26/04	5662'-5746'	Frac CP1, .5 sands as follows: 59,772# 20/40 sand in 495 bbls Lightning 17 Frac fluid. Treated @ avg press of 1705 psi w/avg rate of 25.1 BPM. ISIP 1950 psi. Calc flush: 5660 gal. Actual flush: 5662 gal.
7/26/04	5395'-5415'	Frac LODC sands as follows: 64,422# 20/40 sand in 518 bbls Lightning 17 Frac fluid. Treated @ avg press of 2215 psi w/avg rate of 24.9 BPM. ISIP 2625 psi. Calc flush: 5393 gal. Actual flush: 5393 gal.
7/26/04	5072'-5092'	Frac B2 sands as follows: 39,930# 20/40 sand in 349 bbls Lightning 17 Frac fluid. Treated @ avg press of 1930 psi w/avg rate of 25.2 BPM. ISIP 2050 psi. Calc flush: 5068 gal. Actual flush: 5111 gal.
7/26/04	4954'-4972'	Frac C sands as follows: 54,885# 20/40 sand in 462 bbls Lightning 17 Frac fluid. Treated @ avg press of 2105 psi w/avg rate of 25.1 BPM. ISIP 2450 psi. Calc flush: 4952 gal. Actual flush: 4952 gal.
7/27/04	4790'-4800'	Frac D1 sands as follows: 49,940# 20/40 sand in 420 bbls Lightning 17 Frac fluid. Treated @ avg press of 1875 psi w/avg rate of 25.1 BPM. ISIP 2300 psi. Calc flush: 4788 gal. Actual flush: 4788 gal.
7/27/04	4548'-4594'	Frac PB10,11 sands as follows: 39,817# 20/40 sand in 366 bbls Lightning 17 Frac fluid. Treated @ avg press of 2300 psi w/avg rate of 25.1 BPM. ISIP 2375 psi. Calc flush: 4546 gal. Actual flush: 4544 gal.
7/27/04	4226'-4291'	Frac GB6,4 sands as follows: 70,743# 20/40 sand in 514 bbls Lightning 17 Frac fluid. Treated @ avg press of 1970 psi w/avg rate of 25.2 BPM. ISIP 2200 psi. Calc flush: 4224 gal. Actual flush: 4175 gal.

PERFORATION RECORD

7/22/04	5888'-5908'	4 JSPF	80 holes
7/26/04	5734'-5746'	4 JSPF	46 holes
7/26/04	5662'-5666'	4 JSPF	16 holes
7/26/04	5395'-5415'	4 JSPF	80 holes
7/26/04	5082'-5092'	4 JSPF	40 holes
7/26/04	5072'-5076'	4 JSPF	16 holes
7/26/04	4964'-4972'	4 JSPF	32 holes
7/26/04	4954'-4960'	4 JSPF	24 holes
7/26/04	4790'-4800'	4 JSPF	40 holes
7/27/04	4588'-4594'	4 JSPF	24 holes
7/27/04	4548'-4554'	4 JSPF	24 holes
7/27/04	4283'-4291'	4 JSPF	32 holes
7/27/04	4226'-4238'	4 JSPF	48 holes



Inland Resources Inc.

Ashley State 14-2-9-15

525' FSL & 2017' FWL

SESW Section 2-T9S-R15E

Duchesne Co, Utah

API #43-013-32578; Lease #ML-43538

Ashley State 16-2-9-15

Spud Date: 7/14/04
Put on Production: 8/20/2004

GL: 6021' KB: 6033'

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (304.2')
DEPTH LANDED: 314.2' KB
HOLE SIZE: 12-1/4"
CEMENT DATA: 150 sxs Class "G" cmt, est 4 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 144 jts. (6164.96')
DEPTH LANDED: 6158.96' KB
HOLE SIZE: 7-7/8"
CEMENT DATA: 285 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ.
CEMENT TOP AT: surface


TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 184 jts (5880.76')
TUBING ANCHOR: 5892.76' KB
NO. OF JOINTS: 1 jt (31.23')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 5926.79' KB
NO. OF JOINTS: 2 jts (64.29')
TOTAL STRING LENGTH: EOT @ 5992.64' w/ 12' KB

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' SM
SUCKER RODS: 6 1-1/2" weight bars; 10-3/4" scraped rods; 121-3/4" plain rods; 100-3/4" scraped rods; 1-4", 1-2" x 3/4" pony rods
PUMP SIZE: 2-1/2" x 1-1/2" x 14" RHAC
STROKE LENGTH: 84"
PUMP SPEED, SPM: 5 SPM
LOGS: DIGL/SP/GR/CAL

Wellbore Diagram



Initial Production: BOPD,
MCFD, BWPD

FRAC JOB

8/11/04	5920'-5928'	Frac CP3 sands as follows: 24,512# 20/40 sand in 313 bbls Lightning 17 frac fluid. Treated @ avg press of 1948 psi w/avg rate of 24.7 BPM. ISIP 2150 psi. Calc flush: 5918 gal. Actual flush: 5914 gal.
8/11/04	5700'-5752'	Frac CP1 and CP.5 sands as follows: 69,873# 20/40 sand in 560 bbls Lightning 17 frac fluid. Treated @ avg press of 1531 psi w/avg rate of 24.7 BPM. ISIP 2120 psi. Calc flush: 5698 gal. Actual flush: 5695 gal.
8/12/04	5390'-5426'	Frac LODC sands as follows: 19,377# 20/40 sand in 270 bbls Lightning 17 frac fluid. Treated @ avg press of 1885 psi w/avg rate of 24.6 BPM. ISIP 2800 psi. Calc flush: 5388 gal. Actual flush: 5166 gal.
8/12/04	4980'-4990'	Frac C sands as follows: 24,383# 20/40 sand in 289 bbls Lightning 17 frac fluid. Treated @ avg press of 1963 psi w/avg rate of 24.7 BPM. ISIP 2100 psi. Calc flush: 4978 gal. Actual flush: 4956 gal.
8/12/04	4810'-4826'	Frac D1 sands as follows: 64,732# 20/40 sand in 488 bbls Lightning 17 frac fluid. Treated @ avg press of 1774 psi w/avg rate of 24.7 BPM. ISIP 2300 psi. Calc flush: 4808 gal. Actual flush: 4595 gal.
8/12/04	4572'-4582'	Frac PB10 sands as follows: 21,7983# 20/40 sand in 247 bbls Lightning 17 frac fluid. Treated @ avg press of 2139 psi w/avg rate of 24.7 BPM. ISIP 2550 psi. Calc flush: 4570 gal. Actual flush: 4486 gal.
12/29/04		Pump change. Update rod details.

PERFORATION RECORD

8/05/04	5920'-5928'	4 JSPF	32 holes
8/11/04	5734'-5752'	4 JSPF	72 holes
8/11/04	5700'-5704'	4 JSPF	16 holes
8/11/04	5421'-5426'	4 JSPF	20 holes
8/11/04	5390'-5397'	4 JSPF	28 holes
8/12/04	4980'-4990'	4 JSPF	40 holes
8/12/04	4810'-4826'	4 JSPF	64 holes
8/12/04	4572'-4582'	4 JSPF	40 holes

NEWFIELD

Ashley State 16-2-9-15

544' FSL & 825' FEL

SESE Section 2-T9S-R15E

Duchesne Co, Utah

API #43-013-32439; Lease #ML 43538

Ashley Unit #13-1

Spud Date: 3-16-98

P&A'd: 4-4-98

GL: 5962' KB: 5974'

SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55


WEIGHT: 24#

LENGTH: 7 jts. (289')

DEPTH LANDED: 289' GL

HOLE SIZE: 12-1/4"

CEMENT DATA: 120 sxs Premium cmt, est 7 bbls to surf.

P&A Wellbore
Diagram

LOGS: DIGL/SP/GR/CAL (5946'-301')
 DSN/SDL/GR (5918'-3000')



Inland Resources Inc.

Ashley Unit #13-1

1825 FWL 1785 FNL

NENE Section 1-T9S-R15E

Duchesne Co, Utah

API #43-013-31825; Lease #U-74826

Ashley Unit #4-12-9-15

Spud Date: 11/14/2000
Put on Production: 2/17/2001
GL: 6029' KB: 6039'

Initial Production: 12.9 BOPD,
3.7 MCFD, 69.8 BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (313.48')
HOLE SIZE: 12-1/4"
CEMENT DATA: 155 sxs Class "G" cmt

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 145 jts. (6118.7')
HOLE SIZE: 7-7/8"
TOTAL DEPTH: 6129'
CEMENT DATA: 275 sk Prem. Lite II mixed & 500 sxs 50/50 POZ.
CEMENT TOP AT: 450 per CBL

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 163 jts (5268.16')
TUBING ANCHOR: 5278.16' KB
NO. OF JOINTS: 4 jts (129.58')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 5410.54' KB
NO. OF JOINTS: 2 jts (64.96')
TOTAL STRING LENGTH: EOT @ 5477.05'

SUCKER RODS

POLISHED ROD: 1-1/2" x 22'
SUCKER RODS: 6- 1 1/2" weight rods, 50 - 3/4" scraped rods, 70 - 3/4" plain rods, 89 - 3/4" scraped rods, 2-6', 1-8' x 3/4" pony rods.
PUMP SIZE: 2-1/2" x 1-1/2" x 15' RHAC
STROKE LENGTH: 84"
PUMP SPEED, SPM: 4
LOGS: Dual Laterlog, GR, SP, Spectral Density-Dual Spaced Neutron, CBL

FRAC JOB

2/13/01 5393'-5321' **Frac LODC sands as follows:**
Frac with 204,500# 20/40 sand in 1351 bbls
Viking I-25 fluid. Perfs broke down @ 2010 psi.
Treat at 2350 psi @ 30.6 BPM. ISIP 2750 psi.


2/13/01 4949'-4825' **Frac C/D-1 sands as follows:**
Frac with 171,125# 20/40 sand in 1122 bbls
Viking I-25 fluid. Perfs broke at 1200 psi with 7
BPM. Treated @ avg. 2100 psi @ 30.3 BPM.
ISIP 2500 psi

2/14/01 4570'-4596' **Frac PB-11 sands as follows:**
Frac with 88,000# 20/40 sand in 600 bbls
Viking I-25 fluid. Perfs broke down @ 2970 psi.
Treated @ 2300 psi at 30.1 BPM. ISIP 2665 psi.

7/10/02 Pump Change. Update rod details.
10/29/03 Pump Change. Update rod details.
6/25/04 Pump Change. Update rod and tubing details.
10/14/04 Parted Rods. Update rod details

PERFORATION RECORD

4570'-4582'	4 JSPF	48 holes
4591'-4596'	4 JSPF	20 holes
4806'-4825'	4 JSPF	76 holes
4949'-4960'	4 JSPF	44 holes
5312'-5321'	4 JSPF	36 holes
5393'-5428'	4 JSPF	140 holes



Ashley Unit 4-12-9-15
591 FNL & 600 FWL
NW/NW Sec. 12, T9S R15E
Duchesne, County
API# 43-013-32007; Lease# UTU74826

Ashley Fed. #1-11-9-15

Spud Date: 9/5/2001
Put on Production: 11/7/2001

GL:6050' KB: 6060'

SURFACE CASING


CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (301.82')
DEPTH LANDED: 309.82'
HOLE SIZE: 12-1/4"
CEMENT DATA: 150 sxs Class "G" cmt, est 7 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 148 jts. (6169.79')
DEPTH LANDED: 6167.29'
HOLE SIZE: 7-7/8"
CEMENT DATA: 275 sxs HiLift "G" & 450 sxs 50/50 POZ
CEMENT TOP AT: 900'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 147 jts. (4738.73')
SN LANDED AT: 4748.73'
PACKER: 4752'
TOTAL STRING LENGTH: EOT @ 4757.15'

Injection Wellbore
Diagram

Initial Production: 21.4 BOPD,
71.9 MCFD, 94.2 BWPD

FRAC JOB

11/3/01 5740'-5837' **Frac CP1.2 sands as follows:**
217,000# 20/40 sand in 1355 bbls YF125 fluid. Treated @ avg press of 2058 psi w/avg rate of 34.4 BPM. ISIP 1978 psi. Left shut in.

11/3/01 5234'-5388' **Frac A-1/LODC sands as follows:**
76,800# 20/40 sand in 602 bbls YF125 fluid. Treated @ avg press of 2470 psi w/avg rate of 28.4 BPM. ISIP 2090 psi. Left shut in.

11/3/01 4812'-5105' **Frac B/C/D-1 sands as follows:**
71,180# 20/40 sand in 590 bbls YF125 fluid. Treated @ avg press of 3420 psi w/avg rate of 28.5 BPM. ISIP 2680 psi. Open all zones and flow on 12/64" choke for 9 hours until well died.

03/12/03 **Injection Conversion**

PERFORATION RECORD

11/3/01	4812'-4818'	4 JSPF	24 holes
11/3/01	4830'-4835'	4 JSPF	20 holes
11/3/01	4964'-4968'	4 JSPF	16 holes
11/3/01	5028'-5032'	4 JSPF	16 holes
11/3/01	5099'-5105'	4 JSPF	24 holes
11/3/01	5234'-5238'	4 JSPF	16 holes
11/3/01	5242'-5246'	4 JSPF	16 holes
11/3/01	5337'-5344'	4 JSPF	28 holes
11/3/01	5384'-5388'	4 JSPF	16 holes
11/3/01	5740'-5770'	4 JSPF	120 holes
11/3/01	5812'-5831'	4 JSPF	76 holes
11/3/01	5834'-5837'	4 JSPF	12 holes



Inland Resources Inc.

Ashley Fed. #1-11-9-15

856' FNL & 475' FEL

NENE Section 11-T9S-R15E

Duchesne Co, Utah

API #43-013-32213; Lease #UTU-74826

Ashley 2-11-9-15

Spud Date: 10/19/01
Put on Production: 2/16/04

GL:6062' KB: 6074'

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (300.28')
DEPTH LANDED: 308.28' KB
HOLE SIZE: 12-1/4"
CEMENT DATA: 150 sxs Class "G" cmt mixed, est 2 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 141 jts. (6158.66')
DEPTH LANDED: 6157.16' KB
HOLE SIZE: 7-7/8"
CEMENT DATA: 350 sxs Prem. Lite II mixed & 420 sxs 50/50 POZ.
CEMENT TOP AT: 150'

TUBING


SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 184 jts (5941.70')
TUBING ANCHOR: 5954.20' KB
NO. OF JOINTS: 1 jts (32.30')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 5989.25' KB
NO. OF JOINTS: 2 jts (64.60')
TOTAL STRING LENGTH: EOT @ 6055.35'

SUCKER RODS

POLISHED ROD: 1-1/2" x 22'
SUCKER RODS: 6-1 1/2" weight bars: 10-3/4" scraped rods: 123-3/4"
plain rods: 100-3/4" scraped rods
PUMP SIZE: 2-1/2" x 1-1/2" x 15' RHAC pump w/ SM Plunger
STROKE LENGTH: 86"
PUMP SPEED, SPM: 6 SPM
LOGS: DIGL/SP/GR/CAL

Wellbore Diagram

Cement Top @ 150'



Initial Production: 113 BOPD,
300 MCFD, 28 BWPD

FRAC JOB

2/9/04 5910'-6040' **Frac CP3 and CP5 sands as follows:**
48,191# 20/40 sand in 460 bbls Lightning
frac 17 fluid. Treated @ avg press of 1740 psi
w/avg rate of 24.2 BPM. ISIP 1990 psi. Calc
flush: 5908 gal. Actual flush: 5964
gal.

2/9/04 5831'-5841' **Frac CP2 sands as follows:**
54,534# 20/40 sand in 474 bbls Lightning
frac 17 fluid. Treated @ avg press of 1865 psi
w/avg rate of 24.7 BPM. ISIP 1850 psi. Calc
flush: 5829 gal. Actual flush: 5880
gal.

2/9/04 5752'-5778' **Frac CP1 sands as follows:**
99,774# 20/40 sand in 723 bbls Lightning
frac 17 fluid. Treated @ avg press of 1943 psi
w/avg rate of 24.7 BPM. ISIP 2150 psi. Calc
flush: 5750 gal. Actual flush: 5796
gal.

2/9/04 5696'-5702' **Frac CP.5 sands as follows:**
25,008# 20/40 sand in 279 bbls Lightning
frac 17 fluid. Treated @ avg press of 2860 psi
w/avg rate of 24.7 BPM. ISIP 2220 psi. Calc
flush: 5694 gal. Actual flush: 5754
gal.

2/10/04 5060'-5096' **Frac B sands as follows:**
59,917# 20/40 sand in 478 bbls Lightning
frac 17 fluid. Treated @ avg press of 1962 psi
w/avg rate of 24.4 BPM. ISIP 2050 psi. Calc
flush: 5058 gal. Actual flush: 5082
gal.

2/10/04 4813'-4839' **Frac D1 sands as follows:**
45,539# 20/40 sand in 402 bbls Lightning
frac 17 fluid. Treated @ avg press of 1933 psi
w/avg rate of 24.6 BPM. ISIP 2160 psi. Calc
flush: 4811 gal. Actual flush: 4872
gal.

2/10/04 4575'-4585' **Frac PB11 sands as follows:**
49,766# 20/40 sand in 460 bbls Lightning
frac 17 fluid. Treated @ avg press of 1740 psi
w/avg rate of 24.2 BPM. ISIP 1990 psi. Calc
flush: 5908 gal. Actual flush: 5964
gal.

2/10/04 4326'-4332' **Frac GB6 sands as follows:**
25,591# 20/40 sand in 256 bbls Lightning
frac 17 fluid. Treated @ avg press of 2680 psi
w/avg rate of 24.8 BPM. ISIP 2200 psi. Calc
flush: 4324 gal. Actual flush: 4242
gal.

PERFORATION RECORD

Date	Interval	Tool	Holes
2/5/04	6035'-6040'	4 JSPF	20 holes
2/5/04	5910'-5919'	4 JSPF	36 holes
2/9/04	5831'-5841'	4 JSPF	40 holes
2/9/04	5752'-5778'	4 JSPF	104 holes
2/9/04	5696'-5702'	4 JSPF	24 holes
2/9/04	5372'-5380'	4 JSPF	32 holes
2/10/04	5092'-5096'	4 JSPF	16 holes
2/10/04	5060'-5068'	4 JSPF	32 holes
2/10/04	4836'-4839'	4 JSPF	12 holes
2/10/04	4813'-4821'	4 JSPF	32 holes
2/10/04	4575'-4585'	4 JSPF	40 holes
2/10/04	4326'-4332'	4 JSPF	24 holes



Inland Resources Inc.

Ashley 2-11-9-15

229' FNL & 2013' FEL

NWNE Section 11-T9S-R15E

Duchesne Co, Utah

API #43-013-32214; Lease #UTU 74826

Ashley #3-11-9-15

Spud Date: 09/25/2003
Put on Production: 11/25/2003

GL: 6081' KB: 6091'

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (291.97')
DEPTH LANDED: 301.97'
HOLE SIZE: 12-1/4"
CEMENT DATA: 150 sxs Class "G" cmt, est 3 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 140 jts. (6239.18' KB)
DEPTH LANDED: 6237.18'
HOLE SIZE: 7-7/8"
CEMENT DATA: 300 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ., with 5 Bbls. cement to pit.
CEMENT TOP AT: 100'


TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 181 jts (5932.13')
ANCHOR: 5944.13' KB
NO. OF JOINTS: 3 jts. (99.17')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 6046.05' KB
NO. OF JOINTS: 2 (66.23')
TOTAL STRING LENGTH: EOT @ 6113.78' w/ 12' KB

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' SM
SUCKER RODS: 6-1 1/2" wt. rods, 46-3/4" scraped rods,
90- 3/4" plain rods, 99- 3/4" scraped rods, 1-8', 1-6', 1-4', 1-2' x 3/4" pony rods
PUMP SIZE: 2 1/2" x 1 1/2" x 16" RHAC rod pump w/ SM plunger
STROKE LENGTH: 86"
PUMP SPEED, SPM: 4 SPM
LOGS: CNL/CDL/GR, DIFL/SP/GR/CAL

Wellbore Diagram

FRAC JOB

11/13/03	5972'-6042'	Frac CP4 & CP5 sands as follows: 43,000# 20/40 sand in 411 bbls Viking I-25 fluid. Treated @ avg press of 2235 psi w/avg rate of 24.5 BPM. ISIP 2120 psi. Calc. Flush: 5970 gals. Actual Flush: 6006 gals.
11/13/03	5822'-5907'	Frac CP3 & CP2 sands as follows: 79,409# 20/40 sand in 604 bbls Viking I-25 fluid. Treated @ avg press of 2375 psi w/avg rate of 24.7 BPM. ISIP 2260 psi. Calc. Flush: 5820 gals. Actual Flush: 5859 gals.
11/13/03	5714'-5753'	Frac CP1 sands as follows: 70,000# 20/40 sand in 562 bbls Viking I-25 fluid. Treated @ avg press of 1930 psi w/avg rate of 24.6 BPM. ISIP 1930 psi. Calc. Flush: 5712 gals. Actual Flush: 5712 gals.
11/13/03	5033'-5041'	Frac B1 sands as follows: 31,000# 20/40 sand in 318 bbls Viking I-25 fluid. Treated @ avg press of 2260 psi w/avg rate of 24.4 BPM. ISIP 1995 psi. Calc. Flush: 5031 gals. Actual Flush: 5040 gals.
11/14/03	4777'-4824'	Frac D1 sands as follows: 54,408# 20/40 sand in 459 bbls Viking I-25 fluid. Treated @ avg press of 2125 psi w/avg rate of 24.3 BPM. ISIP 2480 psi. Calc. Flush: 4775 gals. Actual Flush: 4788 gals.
11/14/03	4545'-4600'	Frac PB sands as follows: 147,224# 20/40 sand in 992 bbls Viking I-25 fluid. Treated @ avg press of 2150 psi w/avg rate of 24.5 BPM. ISIP 2280 psi. Calc. Flush: 4543 gals. Actual Flush: 4537 gals.
12/01/04		Tubing leak. Update rod detail.

PERFORATION RECORD

11/10/03	6036'-6042'	4 JSPF	24 holes
11/10/03	6016'-6020'	4 JSPF	16 holes
11/10/03	5972'-5980'	4 JSPF	32 holes
11/13/03	5890'-5907'	2 JSPF	34 holes
11/13/03	5882'-5886'	2 JSPF	8 holes
11/13/03	5822'-5828'	2 JSPF	12 holes
11/13/03	5735'-5753'	2 JSPF	36 holes
11/13/03	5714'-5724'	2 JSPF	20 holes
11/13/03	5033'-5041'	4 JSPF	32 holes
11/13/03	4810'-4824'	4 JSPF	56 holes
11/13/03	4777'-4784'	4 JSPF	28 holes
11/14/03	4592'-4600'	2 JSPF	16 holes
11/14/03	4545'-4574'	2 JSPF	58 holes

NEWFIELD

Ashley #3-11-9-15

656' FNL & 1980' FWL

NE/NW Section 11-T9S-R15E

Duchesne Co, Utah

API #43-013-32294; Lease #UTU-74826

RAP 12 /03/04

Ashley 4-11-9-15

Spud Date: 10/9/03

Put on Production: 2/6/04

GL: 6119' KB: 6120'

SURFACE CASING

CSG SIZE: 8-5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts. (294.98')

DEPTH LANDED: 304.98' KB

HOLE SIZE: 12-1/4"

CEMENT DATA: 150sxs Class "G" cmt, est 4 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 141 jts. (6043.55')

DEPTH LANDED: 6042.05' KB

HOLE SIZE: 7-7/8"

CEMENT DATA: 350 sxs Prem. Lite II mixed & 420 sxs 50/50 POZ mix.

CEMENT TOP AT: 160'

TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#

NO. OF JOINTS: 181 jts (5849.01')

TUBING ANCHOR: 5861.51' KB

NO. OF JOINTS: 1 jts (32.32')

SEATING NIPPLE: 2-7/8" (1 10')

SN LANDED AT: 5896.63' KB

NO. OF JOINTS: 1 jts (32.46')

TOTAL STRING LENGTH: EOT @ 5930.64' W/12.5' KB

SUCKER RODS

POLISHED ROD: 1-1/2" x 22'

SUCKER RODS: 6-1 1/2" weight rods, 10-3/4" scraped rods, 120-3/4" plain rods, 99-3/4" scraped rods, 1-8", 1-6", 1-4", 1-2" x 3/4" pony rods.


PUMP SIZE: 2-1/2" x 1-1/2" x 16" RHAC pump w/ SM Plunger

STROKE LENGTH: 70"

PUMP SPEED, SPM: 6 SPM

LOGS: DIGL/SP/GR/CAL

Wellbore Diagram

Initial Production: 52 BOPD,
116 MCFD, 18 BWPDFRAC JOB

2/2/04 5902'-5920'

Frac CP3 sands as follows:

69,393# 20/40 sand in 561 bbls lightning Frac 17 fluid. Treated @ avg press of 1925 psi w/avg rate of 24.6 BPM. ISIP 2180 psi. Calc flush: 5900 gal. Actual flush: 5943 gal.

2/2/04 5676'-5682'

Frac Stray sands as follows:

25146# 20/40 sand in 295bbls lightning Frac 17 fluid. Treated @ avg press of 2463 psi w/avg rate of 24.5 BPM. ISIP 2280 psi. Calc flush: 5674 gal. Actual flush: 5670 gal.

2/2/04 5095'-5102'

Frac B2 sands as follows:

24,847# 20/40 sand in 281 bbls lightning Frac 17 fluid. Treated @ avg press of 2466 psi w/avg rate of 24.5 BPM. ISIP 2430 psi. Calc flush: 5093 gal. Actual flush: 5095 gal.

2/2/04 4962'-4976'

Frac C sands as follows:

53,353# 20/40 sand in 394 bbls lightning Frac 17 fluid. Treated @ avg press of 2900 psi w/avg rate of 24.3 BPM. ISIP 4200 psi. Screened out.

PERFORATION RECORD

1/29/04	5902'-5920'	4 JSPF	72 holes
2/2/04	5676'-5682'	4 JSPF	24 holes
2/2/04	5095'-5102'	7 JSPF	28 holes
2/2/04	4972'-4976'	4 JSPF	16 holes
2/2/04	4962'-4968'	6 JSPF	24 holes



Inland Resources Inc.

Ashley 4-11-9-15

602' FWL & 578' FNL

NWNW Section 11-T9S-R15E

Duchesne Co, Utah

API #43-013-32295; Lease #UTU-74826

Ashley 6-11-9-15

Spud Date: 10/8/03
Put on Production: 1/29/04
GL: 6078' KB: 6090.5'

Initial Production: 115 BOPD, 95 MCFD,
20 BWPD

Wellbore Diagram

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts (302.2')
DEPTH LANDED: 312.2'
HOLE SIZE: 12-1/4"
CEMENT DATA: 150 sxs Class "G" cmt, est 3.5 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 142 jts (6119.63')
DEPTH LANDED: 6118.13' KB
HOLE SIZE: 7-7/8"
CEMENT DATA: 300 sxs Premilite II & 480 sxs 50/50 POZ
CEMENT TOP AT: 992'

TUBING

SIZE/GRADE/WT: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 179 jts (5891.72')
TUBING ANCHOR: 5903.72' KB
NO. OF JOINTS: 1 jt. (33.03')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 5939.50' KB
NO. OF JOINTS: 2 jts (66.01')
TOTAL STRING LENGTH: EOT @ 6007.01'

SUCKER RODS


POLISHED ROD: 1-1 1/2" x 22'
SUCKER RODS: 6-1 1/2" weighted bars, 10-3/4" scraped rods, 121-3/4" plain rods, 100-3/4" scraped rods, 1-2", 1-4", 1-8" x 3/4" pony rods.
PUMP SIZE: 2-1/2" x 1-3/4" x 12' x 15.5' RHAC
STROKE LENGTH: 72"
PUMP SPEED, SPM: 6 SPM
LOGS: DIGL/SP/GR/CAL

FRAC JOB

1/19/04	5961'-6025'	Frac CP4 and CP5 sands as follows: 60,129# 20/40 sand in 496 bbls Lightning frac 17 fluid. Treated @ avg press of 2150 psi w/avg rate of 24.8 BPM. ISIP 2150 psi. Calc. flush: 5959 gal. Actual flush: 6006 gal.
1/19/04	5878'-5889'	Frac CP3 sands as follows: 55,678# 20/40 sand in 482 bbls Lightning frac 17 fluid. Treated @ avg press of 3000 psi w/avg rate of 24 BPM. ISIP 2300 psi. Calc. flush: 5876 gal. Actual flush: 5922 gal.
1/20/04	5698'-5744'	Frac CP1 sands as follows: 59,279# 20/40 sand in 496 bbls Lightning frac 17 fluid. Treated @ avg press of 1900 psi w/avg rate of 24.6 BPM. ISIP 1930 psi. Calc. flush: 5696 gal. Actual flush: 5695 gal.
1/20/04	5353'-5363'	Frac LODC sands as follows: 59,350# 20/40 sand in 491 bbls Lightning frac 17 fluid. Treated @ avg press of 2550 psi w/avg rate of 24.4 BPM. ISIP 2600 psi. Calc. flush: 5351 gal. Actual flush: 5351 gal.
1/20/04	4991'-4999'	Frac B.5 sands as follows: 39,909# 20/40 sand in 375 bbls Lightning frac 17 fluid. Treated @ avg press of 2000 psi w/avg rate of 24.7 BPM. ISIP 1980 psi. Calc. flush: 4989 gal. Actual flush: 4990 gal.
1/21/04	4920'-4930'	Frac C sands as follows: 39,586# 20/40 sand in 370 bbls Lightning frac 17 fluid. Treated @ avg press of 2000 psi w/avg rate of 24.5 BPM. ISIP 2150 psi. Calc. flush: 4918 gal. Actual flush: 4914 gal.
1/21/04	4529'-4537'	Frac PB10 sands as follows: 38,952# 20/40 sand in 360 bbls Lightning frac 17 fluid. Treated @ avg press of 2230 psi w/avg rate of 24.6 BPM. ISIP 2560 psi. Calc. flush: 4527 gal. Actual flush: 4528 gal.
1/21/04	4215'-4224'	Frac GB4 sands as follows: 40,842# 20/40 sand in 357 bbls Lightning frac 17 fluid. Treated @ avg press of 2400 psi w/avg rate of 24.7 BPM. ISIP 2150 psi. Calc. flush: 4213 gal. Actual flush: 4200 gal.
1/27/04	5810'-5820'	Frac CP2 sands as follows: 30,400# 20/40 sand in 295 bbls Lightning frac 17 fluid. Treated @ avg press of 3960 psi w/avg rate of 14.2 BPM. ISIP 2150 psi. Calc. flush: 1483 gal. Actual flush: 1386 gal.

PERFORATION RECORD

1/15/04	6020'-6025'	4 JSPF	20 holes
1/15/04	5961'-5973'	4 JSPF	48 holes
1/19/04	5878'-5889'	4 JSPF	44 holes
1/19/04	5810'-5820'	4 JSPF	40 holes
1/20/04	5731'-5744'	4 JSPF	52 holes
1/20/04	5698'-5709'	4 JSPF	44 holes
1/20/04	5353'-5363'	4 JSPF	40 holes
1/20/04	4991'-4999'	4 JSPF	32 holes
1/20/04	4920'-4930'	4 JSPF	40 holes
1/21/04	4529'-4537'	4 JSPF	32 holes
1/21/04	4215'-4224'	4 JSPF	36 holes



Inland Resources Inc.

Ashley 6-11-9-15

1864' FNL & 1916' FWL

SENW Section 11-T9S-R15E

Duchesne Co, Utah

API #43-013-32297; Lease #UTU-74826

Ashley 7-11-9-15

Spud Date: 7/8/02
 Put on production:
 GL: 6078' KB: 6088'

SURFACE CASING


CSG SIZE: 8-5/8"
 GRADE: J-55
 WEIGHT: 24#
 LENGTH: 7 jts. (301.44')
 DEPTH LANDED: 309.44'
 HOLE SIZE: 12-1/4"
 CEMENT DATA: 150 sxs Class "G" cmt, est 7 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
 GRADE: J-55
 WEIGHT: 15.5#
 LENGTH: 139 jts. (6208.05')
 DEPTH LANDED: 6205.65'
 HOLE SIZE: 7-7/8"
 CEMENT DATA: 275 sxs PremLite II & 500 sxs 50/50 POZ.
 CEMENT TOP AT: 285'

TUBING

SIZE/GRADE/WT.: 2 3/8" / J-55 / 4.7#
 NO. OF JOINTS: 128 jts (4153.03')
 SEATING NIPPLE: 2 3/8" (1 10")
 SN LANDED AT: 4163.78' KB
 PACKER: 4169.28'
 TOTAL STRING LENGTH: EOT @ 4173.28'

Injector Wellbore
DiagramFRAC JOB

8/19/04 6133-6140' **Frac BS sands as follows:**
 29,476# of 20/40 sand in 324 bbls Lightning
 17 frac fluid. Treated @ avg. pressure of
 2630 psi w/avg. rate of 24.5 BPM.
 Screened out.
 8/27/04 Set packer Ready for MIT.

PERFORATION RECORD

8/16/04	6133-6140'	4 JSPF	28 holes
8/25/04	5857-5862'	4 JSPF	20 holes
8/25/04	5791-5800'	4 JSPF	36 holes
8/25/04	5716-5729'	4 JSPF	52 holes
8/25/04	5651-5655'	4 JSPF	16 holes
8/25/04	5292-5301'	4 JSPF	36 holes
8/25/04	4218-4225'	4 JSPF	28 holes



Inland Resources Inc.

Ashley 7-11-9-15

2151' FNL & 2135' FEL

SWNE Section 11-T9S-R15E

Duchesne Co, Utah

API #43-013-32215; Lease #UTU-74826

Ashley #8-11-9-15

Spud Date: 9/13/2001
Put on Production: 11/10/2001

GL: 6083' KB: 6093'

SURFACE CASING

CSG SIZE: 8-5/8"
GRADE: J-55
WEIGHT: 24#
LENGTH: 7 jts. (293.84')
DEPTH LANDED: 301.84'
HOLE SIZE: 12-1/4"
CEMENT DATA: 150 sxs Class "G" cmt, est 7 bbls cmt to surf.

PRODUCTION CASING

CSG SIZE: 5-1/2"
GRADE: J-55
WEIGHT: 15.5#
LENGTH: 137 jts. (6112.28')
DEPTH LANDED: 6107.28'
HOLE SIZE: 7-7/8"
CEMENT DATA: 275 sxs HiLift "G" & 450 sxs 50/50 POZ
CEMENT TOP AT: ? per CBL


TUBING

SIZE/GRADE/WT.: 2-7/8" / J-55 / 6.5#
NO. OF JOINTS: 165 jts (5321.57')
TUBING ANCHOR: 5331.57'
NO. OF JOINTS: 3 jts (96.80')
SEATING NIPPLE: 2-7/8" (1.10')
SN LANDED AT: 5431.17' KB
NO. OF JOINTS: 1 jt (32.25')
TOTAL STRING LENGTH: EOT @ 5464.97'

SUCKER RODS

POLISHED ROD: 1-1/2" x 22' SM
SUCKER RODS: 6-1 1/2" weight bars; 10-3/4" scraped rods; 110-3/4" plain rods; 90-3/4" scraped rods.
PUMP SIZE: 2-1/2" x 1-1/2" x 15.5" RHAC
STROKE LENGTH: 76"
PUMP SPEED, SPM: 5 SPM
LOGS: DIGL/SP/GR/CAL

Wellbore Diagram



Initial Production: 55.8 BOPD,
35.9 MCFD, 30.5 BWPD

FRAC JOB

11/7/01 5307'-5359' **Frac A-3/LODC sand as follows:**
36,400# 20/40 sand in 361 bbls YF125 fluid. Treated @ avg press of 2374 psi w/avg rate of 26.9 BPM. ISIP 2495 psi. Left shut in.

11/7/01 4970'-5099' **Frac B/C sand as follows:**
88,800# 20/40 sand in 694 bbls YF125 fluid. Treated @ avg press of 2332 psi w/avg rate of 28.2 BPM. Screened out. Left shut in.

11/7/01 4803'-4828' **Frac D-1 sand as follows:**
41,760# 20/40 sand in 377 bbls YF125 fluid. Treated @ avg press of 2328 psi w/avg rate of 25.8 BPM. ISIP 2050 psi. Opened all zones and flowed on 12/64" choke for 4 hours until well died.

12/20/02 Pump change. Updated rod details.

9/23/04 Pump change. Update rod details.

PERFORATION RECORD

Date	Depth Range	Tool	Holes
11/7/01	5354'-5359'	4 JSPF	20 holes
11/7/01	5307'-5311'	4 JSPF	16 holes
11/7/01	5091'-5099'	4 JSPF	32 holes
11/7/01	5020'-5031'	4 JSPF	44 holes
11/7/01	4970'-4976'	4 JSPF	24 holes
11/7/01	4826'-4828'	4 JSPF	08 holes
11/7/01	4803'-4813'	4 JSPF	40 holes



Inland Resources Inc.

Ashley 8-11-9-15

1975' FNL & 737' FEL

SENE Section 11-T9S-R15E

Duchesne Co, Utah

API #43-013-32216; Lease #UTU-74826

Attachment F
Page 1 of 6

Analytical Laboratory Report for:



Chemical Services

NEWFIELD PRODUCTION COMPANY

Account Representative:
Arnold, Joe

Production Water Analysis

Listed below please find water analysis report from: JOHNSON WATER LINE, JOHNSON STATION #2 CHARGE PUMP

Lab Test No: 2005400163

Sample Date:

01/10/2005

Specific Gravity: 1.002

TDS: 674

pH: 8.20

Cations:	mg/L	as:
Calcium	80.00	(Ca ⁺⁺)
Magnesium	56.00	(Mg ⁺⁺)
Sodium	0	(Na ⁺)
Iron	0.70	(Fe ⁺⁺)
Manganese	0.00	(Mn ⁺⁺)
Anions:	mg/L	as:
Bicarbonate	366	(HCO ₃ ⁻)
Sulfate	100	(SO ₄ ⁻)
Chloride	71	(Cl ⁻)
Gases:		
Carbon Dioxide		(CO ₂)
Hydrogen Sulfide	0	(H ₂ S)

NEWFIELD PRODUCTION COMPANY **Lab Test No: 2005400163**

DownHole SAT™ Scale Prediction
@ 50 deg. F



Chemical Services

Mineral Scale	Saturation Index	Momentary Excess (lbs/1000 bbls)
Calcite (CaCO ₃)	5.02	1.13
Aragonite (CaCO ₃)	4.41	1.09
Witherite (BaCO ₃)	0	-4.08
Strontianite (SrCO ₃)	0	-.99
Magnesite (MgCO ₃)	2.13	.628
Anhydrite (CaSO ₄)	.0183	-369.47
Gypsum (CaSO ₄ *2H ₂ O)	.0429	-249.59
Barite (BaSO ₄)	0	-.024
Celestite (SrSO ₄)	0	-49.8
Silica (SiO ₂)	0	-28.21
Brucite (Mg(OH) ₂)	< 0.001	-.737
Magnesium silicate	0	-60.59
Siderite (FeCO ₃)	11.14	.0732
Halite (NaCl)	< 0.001	-136816
Thenardite (Na ₂ SO ₄)	< 0.001	-35132
Iron sulfide (FeS)	0	-.0163

Interpretation of DHSat Results:

The Saturation Index is calculated for each mineral species independently and is a measure of the degree of supersaturation (driving force for precipitation) under the conditions modeled. This value ranges from 0 to infinity with 1.0 representing a condition of equilibrium where scale will neither dissolve nor precipitate. Values less than 1.0 are undersaturated and values greater than 1.0 are supersaturated. The scale is logarithmic, i.e. a Saturation Index of 3 is 10 times more saturated than a value of 2.

The Momentary excess is a measure of how much scale would have to precipitate to bring the system back to a non-scaling condition. This value ranges from negative (dissolving) infinity to positive (precipitating) infinity. The Momentary Excess represents the amount of scale possible while the Saturation Level represents the probability that scale will form.

Page 3 of 6

Analytical Laboratory Report for:



Chemical Services

NEWFIELD PRODUCTION COMPANY

Account Representative:
Arnold, Joe

Production Water Analysis

Listed below please find water analysis report from: Run A, ASHLEY 15-2-9-15 WATER TANK

Lab Test No: 2005400471 Sample Date: 01/18/2005
Specific Gravity: 1.008
TDS: 10651
pH: 8.40

Cations:	mg/L	as:
Calcium	48.00	(Ca ⁺⁺)
Magnesium	44.00	(Mg ⁺⁺)
Sodium	3726	(Na ⁺)
Iron	3.40	(Fe ⁺⁺)
Manganese	0.00	(Mn ⁺⁺)
Anions:	mg/L	as:
Bicarbonate	1830	(HCO ₃ ⁻)
Sulfate	400	(SO ₄ ⁻)
Chloride	4600	(Cl ⁻)
Gases:		
Carbon Dioxide		(CO ₂)
Hydrogen Sulfide	6	(H ₂ S)

Page 4 of 6

NEWFIELD PRODUCTION
COMPANY

Lab Test No: 2005400471

DownHole SAT™ Scale Prediction
@ 140 deg. F**Chemical Services**

Mineral Scale	Saturation Index	Momentary Excess (lbs/1000 bbls)
Calcite (CaCO ₃)	26.69	21.92
Aragonite (CaCO ₃)	22.06	21.49
Witherite (BaCO ₃)	0	-1.83
Strontianite (SrCO ₃)	0	-.498
Magnesite (MgCO ₃)	32.27	24.23
Anhydrite (CaSO ₄)	.0187	-450.37
Gypsum (CaSO ₄ *2H ₂ O)	.0148	-586.94
Barite (BaSO ₄)	0	-.137
Celestite (SrSO ₄)	0	-62.84
Silica (SiO ₂)	0	-91.26
Brucite (Mg(OH) ₂)	.0334	-1.64
Magnesium silicate	0	-125.3
Siderite (FeCO ₃)	5083	1.51
Halite (NaCl)	< 0.001	-186824
Thenardite (Na ₂ SO ₄)	< 0.001	-49949
Iron sulfide (FeS)	701.28	1.15

Interpretation of DHSat Results:

The Saturation Index is calculated for each mineral species independently and is a measure of the degree of supersaturation (driving force for precipitation) under the conditions modeled. This value ranges from 0 to infinity with 1.0 representing a condition of equilibrium where scale will neither dissolve nor precipitate. Values less than 1.0 are undersaturated and values greater than 1.0 are supersaturated. The scale is logarithmic, i.e. a Saturation Index of 3 is 10 times more saturated than a value of 2.

The Momentary excess is a measure of how much scale would have to precipitate to bring the system back to a non-scaling condition. This value ranges from negative (dissolving) infinity to positive (precipitating) infinity. The Momentary Excess represents the amount of scale possible while the Saturation Level represents the probability that scale will form.

DownHole SAT(tm)
MIXED WATER CHEMISTRY

Page 5 of 6

1) Johnson Water

2) Ash 15-2-9-15

Report Date: 01-24-2005

CATIONS

Calcium (as Ca)	160.00
Magnesium (as Mg)	66.50
Barium (as Ba)	0.00
Strontium (as Sr)	0.00
Sodium (as Na)	2066
Iron (as Fe)	1.80
Manganese (as Mn)	0.00

ANIONS

Chloride (as Cl)	2550
Sulfate (as SO4)	250.00
Dissolved CO2 (as CO2)	15.42
Bicarbonate (as HCO3)	1296
Carbonate (as CO3)	207.99
H2S (as H2S)	3.00

PARAMETERS

pH	8.39
Temperature (°F)	130.00
Density(g/mL)	1.00
Pressure(atm)	1.00
Calculated T.D.S.	6618
Molar Conductivity	8631

BJ Chemical Services
Roosevelt, Utah

DownHole SAT (tm)
MIXED WATER DEPOSITION POTENTIAL INDICATORS

1) Johnson Water

2) Ash 15-2-9-15

Report Date: 01-24-2005

SATURATION LEVEL		MOMENTARY EXCESS (Lbs/1000 Barrels)	
Calcite (CaCO ₃)	91.33	Calcite (CaCO ₃)	25.59
Aragonite (CaCO ₃)	75.93	Aragonite (CaCO ₃)	25.50
Witherite (BaCO ₃)	0.00	Witherite (BaCO ₃)	-1.71
Strontianite (SrCO ₃)	0.00	Strontianite (SrCO ₃)	-0.427
Magnesite (MgCO ₃)	46.22	Magnesite (MgCO ₃)	21.05
Anhydrite (CaSO ₄)	0.0503	Anhydrite (CaSO ₄)	-369.73
Gypsum (CaSO ₄ *2H ₂ O)	0.0441	Gypsum (CaSO ₄ *2H ₂ O)	-453.64
Barite (BaSO ₄)	0.00	Barite (BaSO ₄)	-0.133
Magnesium silicate	0.00	Magnesium silicate	-112.01
Iron hydroxide (Fe(OH) ₃)	< 0.001	Iron hydroxide (Fe(OH) ₃)	< 0.001
Iron sulfide (FeS)	304.76	Iron sulfide (FeS)	0.665

SIMPLE INDICES		BOUND IONS		TOTAL	FREE
Langelier	2.31	Calcium	160.00		96.44
Stiff Davis Index	2.44	Barium	0.00		0.00
		Carbonate	207.99		44.73
		Phosphate	0.00		0.00
		Sulfate	250.00		202.99

OPERATING CONDITIONS

Temperature (°F)	130.00
Time (mins)	3.00

BJ Chemical Services
Roosevelt, Utah

Attachment "G"

**Ashley State #15-2-9-15
Proposed Maximum Injection Pressure**

Frac Interval (feet)		Avg. Depth (feet)	ISIP (psi)	Calculated Frac Gradient	Pmax	
Top	Bottom			(psi/ft)		
5880	5900	5890	2050	0.78	2037	
5670	5701	5686	2015	0.79	2003	←
5360	5380	5370	2330	0.87	2318	
4664	4674	4669	2800	1.03	2790	
4545	4556	4551	2500	0.98	2490	
				Minimum	<u>2003</u>	

Calculation of Maximum Surface Injection Pressure

$P_{max} = (Frac\ Grad - (0.433 * 1.005)) \times \text{Depth of Top Perf}$
 where pressure gradient for the fresh water is .433 psi/ft and
 specific gravity of the injected water is 1.005.

$Frac\ Gradient = (ISIP + (0.433 * \text{Top Perf.})) / \text{Top Perf.}$

Please note: These are existing perforations; additional perforations may be added during the actual conversion procedure.



Attachment G-1
Page 1 of 5

DAILY COMPLETION REPORT

WELL NAME: Ashley State 15-2-9-15

Report Date: July 24, 2004

Completion Day: 02a

Present Operation: Completion

Rig: Rigless

WELL STATUS

Surf Csg: 8 5/8 @ 313' Prod Csg: 5 1/2 Wt: 15.5# @ 6150' Csg PBTD: 6076' WL
Tbg: Size: Wt: Grd: Pkr/EOT @: BP/Sand PBTD:

PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
CP3 sds	5880-5900'	4/80			

CHRONOLOGICAL OPERATIONS

Date Work Performed: July 23, 2004

SITP: SICP: 110

Day2a.

RU BJ Services "Ram Head" frac flange. RU BJ & frac CP3 sds, stage #1 w/ 54,059#'s of 20/40 sand in 494 bbls Lightning 17 frac fluid. Open well w/ 110 psi on casing. Perfs broke down @ 2570 psi, back to 1874 psi. Treated @ ave pressure of 1663, w/ ave rate of 24.9 bpm, w/ 8 ppg of sand. Spot 5 bbls 15% HCL in flush for next stage. ISIP was 2050. 640 bbls EWTR. Leave pressure on well.

See day2b.

Starting fluid load to be recovered:	146	Starting oil rec to date:	0		
Fluid lost/recovered today:	494	Oil lost/recovered today:			
Ending fluid to be recovered:	640	Cum oil recovered:	0		
IFL:	FFL:	FTP:	Choke:	Final Fluid Rate:	Final oil cut:

STIMULATION DETAIL

Base Fluid used: Lightning 17 Job Type: Sand frac
Company: BJ Services
Procedure or Equipment detail: CP3 sds down casing

COSTS

Weatherford BOP	\$30
Weatherford Services	\$650
Betts frac water	\$720
IPC Fuel gas	\$150
BJ Services CP3 sds	\$13,870
IPC Supervision	\$60

5376 gals of pad

2944 gals w/ 1-5 ppg of 20/40 sand

5872 gals w/ 5-8 ppg of 20/40 sand

681 gals w/ 8 ppg of 20/40 sand

Flush w/ 5876 gals of slick water

Flush called @ blender to include 2 bbls pump/line volume

Max TP: 2186	Max Rate: 24.9	Total fluid pmpd: 494 bbls	
Avg TP: 1663	Avg Rate: 24.9	Total Prop pmpd: 54,059#'s	
ISIP: 2050	5 min:	10 min:	FG: .78
Completion Supervisor:	Ron Shuck		

DAILY COST: \$15,480

TOTAL WELL COST: \$287,393



DAILY COMPLETION REPORT

WELL NAME: Ashley State 15-2-9-15

Report Date: July 24, 2004

Completion Day: 02b

Present Operation: Completion

Rig: Rigless

WELL STATUS

Surf Csg: 8 5/8 @ 313' Prod Csg: 5 1/2 Wt: 15.5# @ 6150' Csg PBTD: 6076' WL
Tbg: Size: Wt: Grd: Pkr/EOT @: BP/Sand PBTD: 5750'

PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
			CP3 sds	5880-5900'	4/80
CP.5 sds	5670-5674'	4/16			
CP1 sds	5698-5701'	4/12			

CHRONOLOGICAL OPERATIONS

Date Work Performed: July 23, 2004

SITP: SICP: 1800

Day2b.

RU Patterson WLT, mast & lubricator. RIH w/ Weatherford 5-1/2" composite flow-through frac plug & 4' & 3' perf guns. Set plug @ 5750'. Perforate CP1 sds @ 5698-5701' & CP.5 sds @ 5670-5674' w/ 4" Port guns (19 gram, .41"HE) w/ 4 spf for total of 28 shots. RU BJ & frac stage #2 w/ 34,304#'s of 20/40 sand in 375 bbls Lightning 17 frac fluid. Open well w/ 1800 psi on casing. Perfs broke down @ 4200 psi, back to 2021 psi. Treated @ ave pressure of 1869, w/ ave rate of 24.6 bpm, w/ up to 8 ppg of sand. Spot 5 bbls 15% HCL in flush for next stage. ISIP was 2015. 1015 bbls EWTR. Leave pressure on well.

See day2c.

Starting fluid load to be recovered:	640	Starting oil rec to date:	0
Fluid lost/recovered today:	375	Oil lost/recovered today:	
Ending fluid to be recovered:	1015	Cum oil recovered:	0
IFL:		Choke:	
FFL:		Final Fluid Rate:	
FTP:		Final oil cut:	

STIMULATION DETAIL

Base Fluid used: Lightning 17 Job Type: Sand frac

Company: BJ Services

Procedure or Equipment detail: CP1 & CP.5 sds down casing

3654 gals of pad

2194 gals w/ 1-5 ppg of 20/40 sand

4232 gals w/ 5-8 ppg of 20/40 sand

Flush w/ 5670 gals of slick water

COSTS

Weatherford BOP \$30

Weatherford Services \$2,200

Betts frac water \$460

IPC Fuel gas \$100

BJ Services CP1&.5 sd \$9,520

IPC Supervision \$60

Patterson CP1&CP.5 \$2,000

Flush called @ blender to include 2 bbls pump/line volume

Max TP: 4200 Max Rate: 24.6 Total fluid pmpd: 375 bbls

Avg TP: 1869 Avg Rate: 24.6 Total Prop pmpd: 34,304#'s

ISIP: 2015 5 min: 10 min: FG: .79

Completion Supervisor: Ron Shuck

DAILY COST: \$14,370

TOTAL WELL COST: \$310,763



Page 3 of 5

DAILY COMPLETION REPORT

WELL NAME: Ashley State 15-2-9-15

Report Date: July 24, 2004

Completion Day: 02c

Present Operation: Completion

Rig: Rigless

WELL STATUS

Surf Csg: 8 5/8 @ 313' Prod Csg: 5 1/2 Wt: 15.5# @ 6150' Csg PBTD: 6076' WL
Tbg: Size: Wt: Grd: Pkr/EOT @: BP/Sand PBTD: 5480'
KB @ 12' Plugs 5750'

PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
			CP3 sds	5880-5900'	4/80
LODC sds	5360-5380'	4/80			
CP.5 sds	5670-5674'	4/16			
CP1 sds	5698-5701'	4/12			

CHRONOLOGICAL OPERATIONS

Date Work Performed: July 23, 2004

SITP: SICP: 1490

Day2c.

RU Patterson WLT. RIH w/ composite frac plug & 10' perf guns. Set plug @ 5480'. Perforate LODC sds @ 5360-5380' w/ 4 spf for total of 80 shots. RU BJ & frac stage #3 w/ 39,721#'s of 20/40 sand in 371 bbls Lightning 17 frac fluid. Open well w/ 1490 psi on casing. Perfs broke down @ 3422 psi, back to 1811 psi. Treated @ ave pressure of 2028, w/ ave rate of 19.4 bpm, w/ up to 8 ppg of sand. Spot 5 bbls 15% HCL in flush for next stage. ISIP was 2330. 1386 bbls EWTR. Leave pressure on well.

See day2d.

Starting fluid load to be recovered:	1015	Starting oil rec to date:	0
Fluid lost/recovered today:	371	Oil lost/recovered today:	
Ending fluid to be recovered:	1386	Cum oil recovered:	0
IFL:	FFL:	FTP:	Choke:
		Final Fluid Rate:	Final oil cut:

STIMULATION DETAIL

Base Fluid used: Lightning 17 Job Type: Sand frac
Company: BJ Services
Procedure or Equipment detail: LODC sds down casing

3192 gals of pad
2500 gals w/ 1-5 ppg of 20/40 sand
4531 gals w/ 5-8 ppg of 20/40 sand
Flush w/ 5359 gals of slick water

Flush called @ blender to include 2 bbls pump/line volume

Max TP: 3359	Max Rate: 19.4	Total fluid pmpd: 371 bbls
Avg TP: 2028	Avg Rate: 19.4	Total Prop pmpd: 39,721#'s
ISIP: 2330	5 min:	10 min:
		FG: .87
Completion Supervisor: Ron Shuck		

COSTS

Weatherford BOP	\$30
Weatherford Services	\$2,200
Betts frac water	\$500
IPC Fuel gas	\$110
BJ Services LODC sd	\$10,280
IPC Supervision	\$60
Patterson LODC sds	\$2,900
DAILY COST:	\$16,080
TOTAL WELL COST:	\$317,843



Page 4 of 5

DAILY COMPLETION REPORT

WELL NAME: Ashley State 15-2-9-15 Report Date: July 24, 2004 Completion Day: 02d
Present Operation: Completion Rig: Rigless

WELL STATUS

Surf Csg: 8 5/8 @ 313' Prod Csg: 5 1/2 Wt: 15.5# @ 6150' Csg PBD: 6076' WL
Tbg: Size: Wt: Grd: Pkr/EOT @: BP/Sand PBD: 4780'
KB @ 12' Plugs 5750' 5480'

PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
DS1 sds	<u>4664-4674'</u>	<u>4/40</u>	CP3 sds	<u>5880-5900'</u>	<u>4/80</u>
LODC sds	<u>5360-5380'</u>	<u>4/80</u>			
CP.5 sds	<u>5670-5674'</u>	<u>4/16</u>			
CP1 sds	<u>5698-5701'</u>	<u>4/12</u>			

CHRONOLOGICAL OPERATIONS

Date Work Performed: July 23, 2004 SITP: SICP: 1850

Day2d.

RU Patterson WLT. RIH w/ composite frac plug & 10' perf guns. Set plug @ 4780'. Perforate DS1 sds @ 4664-4674' w/ 4 spf for total of 40 shots. RU BJ & frac stage #4 w/ 29,245#'s of 20/40 sand in 300 bbls Lightning 17 frac fluid. Open well w/ 1850 psi on casing. Perfs broke down @ 2600 psi, back to 1893 psi. Treated @ ave pressure of 2265, w/ ave rate of 24.8 bpm, w/ up to 8 ppg of sand. Spot 5 bbls of 15% HCL in flush for next stage. ISIP was 2800. 1686 bbls EWTR. Leave pressure on well.

See day2e.

Starting fluid load to be recovered: 1386 Starting oil rec to date: 0
Fluid lost/recovered today: 300 Oil lost/recovered today:
Ending fluid to be recovered: 1686 Cum oil recovered: 0
IFL: FFL: FTP: Choke: Final Fluid Rate: Final oil cut:

STIMULATION DETAIL

Base Fluid used: Lightning 17 Job Type: Sand frac
Company: BJ Services
Procedure or Equipment detail: DS1 sds down casing

COSTS

Weatherford BOP	<u>\$30</u>
Weatherford Services	<u>\$2,200</u>
Betts frac water	<u>\$390</u>
IPC Fuel gas	<u>\$80</u>
BJ Services DS1 sd	<u>\$8,400</u>
IPC Supervision	<u>\$60</u>
Patterson DS1 sds	<u>\$2,200</u>

2940 gals of pad1875 gals w/ 1-5 ppg of 20/40 sand3081 gals w/ 5-8 ppg of 20/40 sandFlush w/ 4704 gals of slick water**Flush called @ blender to include 2 bbls pump/line volume**

Max TP: 2963 Max Rate: 24.9 Total fluid pmpd: 300 bbls
Avg TP: 2265 Avg Rate: 24.8 Total Prop pmpd: 29,245#'s
ISIP: 2800 5 min: 10 min: FG: 1.03
Completion Supervisor: Ron Shuck

DAILY COST: \$13,360
TOTAL WELL COST: \$331,203



DAILY COMPLETION REPORT

WELL NAME: Ashley State 15-2-9-15 Report Date: July 24, 2004 Completion Day: 02e
Present Operation: Completion Rig: Rigless

WELL STATUS

Surf Csg: 8 5/8 @ 313' Prod Csg: 5 1/2 Wt: 15.5# @ 6150' Csg PBTD: 6076' WL
Tbg: Size: Wt: Grd: Pkr/EOT @: BP/Sand PBTD: 4600'
KB @ 12' Plugs 5750' 5480' 4780'

PERFORATION RECORD

Zone	Perfs	SPF/#shots	Zone	Perfs	SPF/#shots
PB10 sds	4545-4556'	4/44	CP3 sds	5880-5900'	4/80
DS1 sds	4664-4674'	4/40			
LODC sds	5360-5380'	4/80			
CP.5 sds	5670-5674'	4/16			
CP1 sds	5698-5701'	4/12			

CHRONOLOGICAL OPERATIONS

Date Work Performed: July 23, 2004 SITP: SICP: 1425

Day2e.

RU Patterson WLT. RIH w/ composite frac plug & 11' perf guns. Set plug @ 4600". Perforate PB10 sds @ 4545-4556' w/ 4 spf for total of 44 shots. RU BJ & frac stage #5 w/ 28,142#'s of 20/40 sand in 296 bbls Lightning 17 frac fluid. Open well w/ 1425 psi on casing. Perfs broke down @ 4200 psi, back to 1618 psi. Treated @ ave pressure of 2360, w/ ave rate of 24.7 bpm, w/ up to 8 ppg of sand. ISIP was 2500. 1982 bbls EWTR. RD BJ & WLT. Begin immediate flow back on well @ 1800 psi w/ 12/64 choke. Well flowed for 4.5 hours & died w/ 268 bbls rec'd (14% of frac). SIFN.

Starting fluid load to be recovered: 1982 Starting oil rec to date: 0
Fluid lost/recovered today: 268 Oil lost/recovered today:
Ending fluid to be recovered: 1714 Cum oil recovered: 0
IFL: FFL: FTP: Choke: Final Fluid Rate: Final oil cut:

STIMULATION DETAIL

Base Fluid used: Lightning 17 Job Type: Sand frac

Company: BJ Services

Procedure or Equipment detail: PB10 sds down casing

2772 gals of pad

1569 gals w/ 1-5 ppg of 20/40 sand

3639 gals w/ 5-8 ppg of 20/40 sand

Flush w/ 4452 gals of slick water

COSTS

Weatherford BOP	\$30
Weatherford Services	\$2,200
Betts frac water	\$340
IPC Fuel gas	\$70
BJ Services PB10 sd	\$7,600
IPC Supervision	\$60
Patterson PB10 sds	\$2,200
Flow back hand	\$230
Betts water transfere	\$50

Max TP: 4200 Max Rate: 24.7 Total fluid pmpd: 296 bbls

Avg TP: 2360 Avg Rate: 24.7 Total Prop pmpd: 28,142#'s

ISIP: 2500 5 min: 10 min: FG: .98

Completion Supervisor: Ron Shuck

DAILY COST: \$12,780

TOTAL WELL COST: \$343,983

ATTACHMENT H
WORK PROCEDURE FOR PLUGGING AND ABANDONMENT

1. Set CIBP @ 4450'.
2. Plug #1 Set 100' plug on top of CIBP using 12 sx Class G cement.
3. Plug #2 Set 200' plug from 2000'-2200' with 25 sx Class "G" cement.
4. Plug #3 Pump 42 sx Class G cement down 5-1/2" casing to 363'.

The approximate cost to plug and abandon this well is \$33,025.

Ashley State 15-2-9-15

Spud Date: 6/14/04

Put on Production: 7/28/04

GL: 6020' KB: 6032'

Initial Production: BOPD,
MCFD, BWPDProposed P & A
Wellbore DiagramSURFACE CASING

CSG SIZE: 8 5/8"

GRADE: J-55

WEIGHT: 24#

LENGTH: 7 jts. (303.01')

DEPTH LANDED: 313.01' KB

HOLE SIZE: 12 1/4"

CEMENT DATA: 150sxs Class "G" mixed cmt, est 4 bbls cmt to surf.

Cement Top @ 80'

Pump 42 sx Class G Cement down 5 -1/2" casing to 363'

Casing Shoe @ 313'

PRODUCTION CASING

CSG SIZE: 5 1/2"

GRADE: J-55

WEIGHT: 15.5#

LENGTH: 144 jts. (6152.43')

DEPTH LANDED: 6150.43' KB

HOLE SIZE: 7 7/8"

CEMENT DATA: 300 sxs Prem. Lite II mixed & 400 sxs 50/50 POZ mix.

CEMENT TOP AT: 80'

200' Balanced Plug (25 sx) Class G Cement over water
zone 2000' - 2200'

100' (12 sx) Class G Cement plug on top of CIBP

CIBP @ 4450'

4545-4556'

4664-4674'

5360-5380'

5670-5674'

5698-5701'

5880-5900'

Top of Fill & PBTD @ 6126'

SHOE @ 6150'

TD @ 6160'

NEWFIELD

Ashley State 15-2-9-15

537' FNL & 2051' FEL

SW/SE Section 2-T9S-R15E

Duchesne Co, Utah

API #43-013-32579; Lease #ML-43538

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged well, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NUMBER: ML43538
2. NAME OF OPERATOR: Newfield Production Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME: ASHLEY PA A
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: ASHLEY STATE 15-2-9-15
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 537 FSL 2051 FEL		8. WELL NAME and NUMBER: ASHLEY STATE 15-2-9-15
5. PHONE NUMBER: 435.646.3721		9. API NUMBER: 4301332579
10. FIELD AND POOL, OR WILDCAT: Monument Butte		
QTR/QTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SW/SE, 2, T9S, R15E		COUNTY: Duchesne
		STATE: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input checked="" type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARITLY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input type="checkbox"/> OTHER: -
	<input checked="" type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Newfield Production proposes to convert the above mentioned well from a producing oil well to an injection well.

NAME (PLEASE PRINT) David Gerbig

TITLE Operations Engineer

SIGNATURE



DATE

2-21-05

(This space for State use only)

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML43538

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:

ASHLEY PA A

1. TYPE OF WELL:

OIL WELL ☒

GAS WELL ☐

OTHER

8. WELL NAME and NUMBER:

ASHLEY STATE 15-2-9-15

2. NAME OF OPERATOR:

Newfield Production Company

9. API NUMBER:

4301332579

3. ADDRESS OF OPERATOR:

Route 3 Box 3630

CITY Myton

STATE UT

ZIP 84052

PHONE NUMBER

435.646.3721

10. FIELD AND POOL, OR WILDCAT:

Monument Butte

4. LOCATION OF WELL:

FOOTAGES AT SURFACE: 537 FSL 2051 FEL

COUNTY: Duchesne

QTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SW/SE, 2, T9S, R15E

STATE: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF ACTION

TYPE OF SUBMISSION

☒ NOTICE OF INTENT
(Submit in Duplicate)

Approximate date work will

☐ SUBSEQUENT REPORT
(Submit Original Form Only)

Date of Work Completion:

☐ ACIDIZE

☐ ALTER CASING

☐ CASING REPAIR

☐ CHANGE TO PREVIOUS PLANS

☐ CHANGE TUBING

☐ CHANGE WELL NAME

☐ CHANGE WELL STATUS

☐ COMMINGLE PRODUCING FORMATIONS

☒ CONVERT WELL TYPE

☐ DEEPEN

☐ FRACTURE TREAT

☐ NEW CONSTRUCTION

☐ OPERATOR CHANGE

☐ PLUG AND ABANDON

☐ PLUG BACK

☐ PRODUCTION (START/STOP)

☐ RECLAMATION OF WELL SITE

☐ RECOMPLETE - DIFFERENT FORMATION

☐ REPERFORATE CURRENT FORMATION

☐ SIDETRACK TO REPAIR WELL

☐ TEMPORARITLY ABANDON

☐ TUBING REPAIR

☐ VENT OR FLAIR

☐ WATER DISPOSAL

☐ WATER SHUT-OFF

☐ OTHER: -


12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

Newfield Production proposes to convert the above mentioned well from a producing oil well to an injection well.

NAME (PLEASE PRINT) David Gerbig

TITLE Operations Engineer

SIGNATURE



DATE

2-21-05


(This space for State use only)

the Ten Commandments serve as the basis for the laws of the United States and should be recognized as such.

point," Lynn continued. "How could anything be more obviously religious?"

Mat Staver, president and gen-

when she apparently passed out, went off the right side of the road eventually came to a stop after a front end impact in a ditch, according to Highway Patrol reports. Serawop sustained a broken neck and head in the collision and died after being taken by ambulance to the Uintah Medical Center, the report stated.



LEGAL NOTICES

Your Right To Know!

Continued from
previous page

cial Disposal Facility. The adjudicative proceeding will be conducted informally according to Utah Admin. Rule R649-10, Administrative Procedures.

The facility will be constructed as surface evaporation pits with oil skimming and handling equipment for the disposal of produced water.

Any person desiring to object to the proposed application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for this proceeding is John R. Baza, Associate Director at PO Box 145801, Salt Lake City, Utah 84114-5801, phone number (801) 538-5340. If such a protest or notice of intervention is received, a hearing will be scheduled in accordance with the aforementioned administrative procedure rule. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 28th day of February 2005.

STATE OF UTAH
DIVISION OF OIL,
GAS & MINING

John R. Baza

Associate Director

Published in the Uintah
Basin Standard March 8,
2005.

NOTICE OF AGENCY ACTION CAUSE NO. UIC 319

BEFORE THE DIVISION OF OIL, GAS AND MINING, DEPARTMENT OF NATURAL RESOURCES, STATE OF UTAH

IN THE MATTER OF

THE APPLICATION OF Newfield Exploration Company FOR ADMINISTRATIVE APPROVAL OF THE Ashley State 9-2-9-15, Ashley State 15-2-9-15 and the Ashley Federal 11-15-9-15 WELLS LOCATED IN SECTIONS 2 and 15, TOWNSHIP 9 South, RANGE 15 East, Duchesne COUNTY, UTAH, AS CLASS II INJECTION WELLS

THE STATE OF UTAH TO ALL PERSONS INTERESTED IN THE ABOVE ENTITLED MATTER.

Notice is hereby given that the Division of Oil, Gas and Mining (the "Division") is commencing an informal adjudicative proceeding to consider the application of Newfield Exploration Company for administrative approval of the Ashley State 9-2-9-15, Ashley State 15-2-9-15 and the Ashley Federal 11-15-9-15 wells, located in Sections 2 and 15, Township 9 South, Range 15 East, Duchesne County, Utah, for conversion to Class II injection wells. The adjudicative proceeding will be conducted informally according to Utah Admin. Rule R649-10, Administrative Procedures.

Selective zones in the Green River Formation will be used for water injection. The maximum requested injection pressure and rate will be determined based on fracture gradient information submitted by Newfield Exploration Company.

Any person desiring to object to the proposed application or otherwise intervene in the proceeding, must file a written protest or notice of intervention with the Division within fifteen days following publication of this notice. The Division's Presiding Officer for this proceeding is John R. Baza, Associate Director at PO Box 145801, Salt Lake City, Utah 84114-5801, phone number (801) 538-5340. If such a protest or notice of intervention is received, a

hearing will be scheduled in accordance with the aforementioned administrative procedure rule. Protestants and/or interveners should be prepared to demonstrate at the hearing how this matter affects their interests.

Dated this 2nd day of March, 2005.

STATE OF UTAH
DIVISION OF OIL,
GAS & MINING

John R. Baza

Associate Director

Published in the Uintah
Basin Standard March 8,
2005.

REQUEST FOR PROPOSALS MOBILE HOME DEMOLITION AND REMOVAL SERVICES DUCHESNE COUNTY

Duchesne County is seeking the services of a qualified contractor to demolish and remove old mobile homes at the request of various property owners within the County. Proposals to provide this service must be received by the Duchesne County Commission no later than 5:00 PM on March 22, 2005. Faxed copies will not be accepted. All copies must be in a sealed envelope addressed to:

Andrea Arnold
Duchesne County Commission

PO Box 270

Duchesne, UT 84021

For a copy of the complete Request for Proposals, contact Mike Hyde, Duchesne County Planning Department, 435-738-1151 or

at
mhyde@co.duchesne.ut.us.

Published in the Uintah
Basin Standard March 8 and
15, 2005.

Bail reduced for accused rapist

A Vernal man accused of raping a close female relative had his bail cut in half last week by 8th District Court Judge John Anderson.

Brett Christensen, 31, was initially held in the Uintah County Jail on \$20,000 bond. The amount was lowered to \$10,000 on Tuesday at a bail hearing. Despite the reduction, Christensen told the court he would not be able to post bail. A short date was set for a preliminary hearing in the case.

According to court records, Christensen and the alleged victim went to a Vernal area bar on Feb. 17. The two became intoxicated, the woman told police, before accepting an invitation to another man's apartment when the bar closed.

During a videotaped statement to Vernal Police Detective Bob Taylor, the woman said she passed out at the apartment during the early morning hours of Feb. 18. When she awoke, she was naked from the waist down, and Christensen - himself partially clothed - was next to her on the bed. The woman said she knew

Christensen had sex with her when she was unconscious, an apartment to call police.

Christensen was later arrested by Taylor, and according to the detective confessed to her with the alleged victim was unconscious.

A preliminary hearing was set for Wednesday, March 9.



Brett Christensen

NOTICE OF ANNUAL MEETING OF MEMBERS

Members of Moon Lake Electric Association, Inc.

Notice is hereby given that the Annual Meeting of the Moon Lake Electric Association, Inc., will be held at High School in Roosevelt, Duchesne County, Utah, on Thursday, April 21, 2005, at 7:00 p.m. for the following purposes:

- 1) To elect Directors for the Board of Directors of Moon Lake Electric Association, Inc., to represent Districts each for a 3-year term.
- 2) Presentation of reports to the members.
- 3) For consideration of such other business as may come before said meeting.

Signed this 23rd day of February 2005.

Rondal R. McKee
Secretary-Treasurer



State of Utah

Department of Natural Resources

MICHAEL R. STYLER
Executive Director

Division of Oil, Gas & Mining

MARY ANN WRIGHT
Acting Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

April 20, 2005

Newfield Exploration Company
1401 17th Street, Suite 1000
Denver, Colorado 80202

Re: Ashley Unit Well: Ashley 15-2-9-15, Section 2, Township 9 South,
Range 15 East, Duchesne County, Utah


Gentlemen:

Pursuant to Utah Admin. Code R649-5-3-3, the Division of Oil, Gas and Mining (the "Division") issues its administrative approval for conversion of the referenced well to a Class II injection well. Accordingly, the following stipulations shall apply for full compliance with this approval:

1. Compliance with all applicable requirements for the operation, maintenance and reporting for Underground Injection Control ("UIC") Class II injection wells pursuant to Utah Admin. Code R649-1 et seq.
2. Conformance with all conditions and requirements of the complete application submitted by Newfield Exploration Company.
3. A casing\tubing pressure test shall be conducted prior to commencing injection.

If you have any questions regarding this approval or the necessary requirements, please contact Brad Hill or Dan Jarvis at this office.

Sincerely,


John R. Baza
Associate Director

BGH:jc

cc: Dan Jackson, Environmental Protection Agency
Bureau of Land Management, Vernal District Office
SITLA, Salt Lake Office
Newfield Production Co., Myton

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

5. LEASE DESIGNATION AND SERIAL NUMBER:
ML43538

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

6. IF INDIAN, ALLOTTEE OR TRIBE NAME:

7. UNIT or CA AGREEMENT NAME:
ASHLEY PA A

1. TYPE OF WELL: OIL WELL ☒ GAS WELL ☐ OTHER

8. WELL NAME and NUMBER:
ASHLEY STATE 15-2-9-15

2. NAME OF OPERATOR:
Newfield Production Company

9. API NUMBER:
4301332579

3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052 PHONE NUMBER 435.646.3721

10. FIELD AND POOL, OR WILDCAT:
Monument Butte

4. LOCATION OF WELL:
FOOTAGES AT SURFACE: 537 FSL 2051 FEL

COUNTY: Duchesne

OTR/OTR. SECTION. TOWNSHIP. RANGE. MERIDIAN: SW/SE, 2, T9S, R15E

STATE: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
	SubDate	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will 	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLAIR
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 11/16/2005	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/STOP)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: - Injection Conversion
	<input checked="" type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The subject well was converted from a producing well to an injection well on 11-16-05. On 11-15-05 Dennis Ingram with the State was contacted concerning the initial MIT on the above listed well. Permission was given at that time to perform the test on 11-16-05. On 11-16-05 the csg was pressured up to 1355 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The ybg pressure was 125 psig during the test. There was a State representative available to witness the test. (Dennis Ingram) API #43-013-32579.

NAME (PLEASE PRINT) Callie Duncan

TITLE Production Clerk

SIGNATURE

Callie Duncan

DATE 11/17/2005

(This space for State use only)

RECEIVED

NOV 18 2005

DIV. OF OIL, GAS & MINING

Mechanical Integrity Test
Casing or Annulus Pressure Test

Inland Production Company

Rt. 3 Box 3630
Myton, UT 84052
435-646-3721

Witness: [Signature] Date 11/16/05 Time 10:00 am/pm
Test Conducted by: Matthew Berbach
Others Present: _____

Well: Ashley Shale 15-2-9-15

Field: Ashley Unit UTU735200A

Well Location: SW/SE Sec 2, T9S, R15E

API No: 43-013-32579

Time	Casing Pressure	
0 min	<u>1355</u>	psig
5	<u>1355</u>	psig
10	<u>1355</u>	psig
15	<u>1355</u>	psig
20	<u>1355</u>	psig
25	<u>1355</u>	psig
30 min	<u>1355</u>	psig
35	_____	psig
40	_____	psig
45	_____	psig
50	_____	psig
55	_____	psig
60 min	_____	psig

Tubing pressure: 125 psig

Result:

Pass

Fail

Signature of Witness:

Signature of Person Conducting Test: [Signature]

STATE OF UTAH
DIVISION OF OIL GAS AND MINING

INJECTION WELL - PRESSURE TEST

Well Name: <u>AS # 15-2-9-15</u>	API Number: <u>43-013-32579</u>
Qtr/Qtr: <u>SW/SE</u> Section: <u>2</u>	Township: <u>9S</u> Range: <u>15E</u>
Company Name: <u>NEWFIELD</u>	
Lease: State <u>ML-43538</u> Fee _____	Federal _____ Indian _____
Inspector: <u>L. M. L. J. J. J.</u>	Date: <u>11-16-05</u>

Initial Conditions:

Tubing - Rate: 0 Bbl Pressure: 125 psiCasing/Tubing Annulus - Pressure: 1355 psi

Conditions During Test:


Time (Minutes)	Annulus Pressure	Tubing Pressure
0	<u>1355</u>	<u>125</u>
5	<u>1355</u>	<u>125</u>
10	<u>1355</u>	<u>125</u>
15	<u>1355</u>	<u>125</u>
20	<u>1355</u>	<u>125</u>
25	<u>1355</u>	<u>125</u>
30	<u>1355</u>	<u>125</u>

Results: Pass/Fail

Conditions After Test:

Tubing Pressure: 128 psiCasing/Tubing Annulus Pressure: 1355 psiCOMMENTS: Tested because of conversion @ 10:15 AM
also record on Barton Chart

Operator Representative





State of Utah

**Department of
Natural Resources**

MICHAEL R. STYLER
Executive Director

**Division of
Oil, Gas & Mining**

JOHN R. BAZA
Division Director

JON M. HUNTSMAN, JR.
Governor

GARY R. HERBERT
Lieutenant Governor

UNDERGROUND INJECTION CONTROL PERMIT


Cause No. UIC-319

Operator: Newfield Production Company
Well: Ashley State 15-2-9-15
Location: Section 2, Township 9 South, Range 15 East
County: Duchesne
API No.: 43-013-32579
Well Type: Enhanced Recovery (waterflood)

Stipulations of Permit Approval

1. Approval for conversion to Injection Well issued on April 20, 2005.
2. Maximum Allowable Injection Pressure: 2,003 psig
3. Maximum Allowable Injection Rate: (restricted by pressure limitation)
4. Injection Interval: Green River Formation
(4,073' - 6,085')

Approved by:



Gil Hunt
Associate Director

11-21-05
Date

cc: Dan Jackson Environmental Protection Agency
Bureau of Land Management, Vernal
SITLA, Salt Lake City

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER <input type="checkbox"/>		5. LEASE DESIGNATION AND SERIAL NUMBER ML43538
2. NAME OF OPERATOR: Newfield Production Company		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: ASHLEY PA A
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 537 FSL 2051 FEL		8. WELL NAME and NUMBER ASHLEY STATE 15-2-9-15
PHONE NUMBER 435.646.3721		9. API NUMBER: 4301332579
10. FIELD AND POOL, OR WILDCAT: Monument Butte		
QTR/OTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: SW/SE, 2, T9S, R15E		COUNTY: Duchesne
		STATE: Utah

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION	SubDate	TYPE OF ACTION
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input checked="" type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input checked="" type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/STOP) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLAIR <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: - Put Well on Injection
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 12/21/2005			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

The above referenced well was put on injection at 11:20 a.m. on 12/21/05.

NAME (PLEASE PRINT) Mandie Crozier	TITLE Regulatory Specialist
SIGNATURE <i>Mandie Crozier</i>	DATE 12/29/2005

(This space for State use only.)

RECEIVED
JAN 03 2006
DIV. OF OIL, GAS & MINING

STATE OF UTAH
DEPARTMENT OF NATURAL RESOURCES
DIVISION OF OIL, GAS AND MINING

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL: OIL WELL <input checked="" type="checkbox"/> GAS WELL <input type="checkbox"/> OTHER		5. LEASE DESIGNATION AND SERIAL NUMBER: UTAH STATE ML-43538
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: Route 3 Box 3630 CITY Myton STATE UT ZIP 84052		7. UNIT or CA AGREEMENT NAME: GMBU
4. LOCATION OF WELL: FOOTAGES AT SURFACE: 537 FSL 2051 FEL		8. WELL NAME and NUMBER: ASHLEY STATE 15-2-9-15
OTR/OTR. SECTION, TOWNSHIP, RANGE, MERIDIAN: SWSE, 2, T9S, R15E		9. API NUMBER: 4301332579
COUNTY: DUCHESNE		10. FIELD AND POOL, OR WILDCAT: GREATER MB UNIT
STATE: UT		


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/STOP) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLAIR <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: - Five Year MIT
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of Work Completion: 10/07/2010			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

On 10/04/2010 Dennis Ingram with the State of Utah DOGM was contacted concerning the 5 Year MIT on the above listed well. Permission was given at that time to perform the test on 10/04/2010. On 10/07/2010 the casing was pressured up to 1430 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 1905 psig during the test. There was a State representative available to witness the test - Dennis Ingram.

API# 43-013-32579

NAME (PLEASE PRINT) <u>Lucy Chavez-Naupoto</u>	TITLE <u>Administrative Assistant</u>
SIGNATURE 	DATE <u>10/12/2010</u>

(This space for State use only)

RECEIVED
OCT 14 2010
DIV. OF OIL, GAS & MINING

Mechanical Integrity Test Casing or Annulus Pressure Test

Newfield Production Company

Rt. 3 Box 3630

Myton, UT 84052

435-646-3721

Witness: Dennis Ingram Date 10/1/10 Time 11:00 am pm

Test Conducted by: Cole Harris

Others Present: Eric Park

Well: Ashley State 15-2-9-15

Field: Monument Butte

Well Location: SW/SE Sec. 2, T9S, R15E API No: 43-013-32579

Duchesne County


<u>Time</u>	<u>Casing Pressure</u>	
0 min	<u>1430</u>	psig
5	<u>1430</u>	psig
10	<u>1430</u>	psig
15	<u>1430</u>	psig
20	<u>1430</u>	psig
25	<u>1430</u>	psig
30 min	<u>1430</u>	psig
35		psig
40		psig
45		psig
50		psig
55		psig
60 min		psig

Tubing pressure: 1905 psig

Result: Pass Fail

Signature of Witness: Dennis Ingram

Signature of Person Conducting Test: Cole Harris



GRAPHIC CONTROLS CORPORATION
BUFFALO, NEW YORK

CHART NO. MC M-2500-H
10-7-10

METER _____

CHART PUT ON
11:00 AM

TAKEN OFF
4:30 PM

LOCATION Ashby State 15-2-9-15

REMARKS 5 Year MIT
Cole Har. 3

PRINTED IN U.S.A.

STATE OF UTAH DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		FORM 9
SUNDRY NOTICES AND REPORTS ON WELLS Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		5. LEASE DESIGNATION AND SERIAL NUMBER: ML-43538
1. TYPE OF WELL Water Injection Well		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
2. NAME OF OPERATOR: NEWFIELD PRODUCTION COMPANY		7. UNIT or CA AGREEMENT NAME: GMBU (GRRV)
3. ADDRESS OF OPERATOR: Rt 3 Box 3630 , Myton, UT, 84052		8. WELL NAME and NUMBER: ASHLEY ST 15-2-9-15
4. LOCATION OF WELL FOOTAGES AT SURFACE: 0537 FSL 2051 FEL QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: Qtr/Qtr: SWSE Section: 02 Township: 09.0S Range: 15.0E Meridian: S		9. API NUMBER: 43013325790000
PHONE NUMBER: 435 646-4825 Ext		9. FIELD and POOL or WILDCAT: MONUMENT BUTTE
COUNTY: DUCHESNE		STATE: UTAH
11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA		
TYPE OF SUBMISSION	TYPE OF ACTION	
<input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:	<input type="checkbox"/> ACIDIZE	
<input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 9/4/2015	<input type="checkbox"/> ALTER CASING	
<input type="checkbox"/> SPUD REPORT Date of Spud:	<input type="checkbox"/> CASING REPAIR	
<input type="checkbox"/> DRILLING REPORT Report Date:	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	
	<input type="checkbox"/> CHANGE TUBING	
	<input type="checkbox"/> CHANGE WELL STATUS	
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	
	<input type="checkbox"/> DEEPEN	
	<input type="checkbox"/> FRACTURE TREAT	
	<input type="checkbox"/> OPERATOR CHANGE	
	<input type="checkbox"/> PLUG AND ABANDON	
	<input type="checkbox"/> PRODUCTION START OR RESUME	
	<input type="checkbox"/> RECLAMATION OF WELL SITE	
	<input type="checkbox"/> REPERFORATE CURRENT FORMATION	
	<input type="checkbox"/> SIDETRACK TO REPAIR WELL	
	<input type="checkbox"/> TUBING REPAIR	
	<input type="checkbox"/> VENT OR FLARE	
	<input type="checkbox"/> WATER SHUTOFF	
	<input type="checkbox"/> SI TA STATUS EXTENSION	
	<input type="checkbox"/> WILDCAT WELL DETERMINATION	
	<input checked="" type="checkbox"/> OTHER	
	OTHER: <input type="text" value="5 YR MIT"/>	
12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc. On 09/02/2015 Richard Powell with the State of Utah DOGM was contacted concerning the 5 Year MIT on the above listed well. On 09/04/2015 the casing was pressured up to 1233 psig and charted for 30 minutes with no pressure loss. The well was not injecting during the test. The tubing pressure was 1790 psig during the test. There was a State representative available to witness the test - Mark Jones.		
Accepted by the Utah Division of Oil, Gas and Mining FOR RECORD ONLY September 15, 2015		
NAME (PLEASE PRINT) Lucy Chavez-Naupoto	PHONE NUMBER 435 646-4874	TITLE Water Services Technician
SIGNATURE N/A	DATE 9/14/2015	

Mechanical Integrity Test Casing or Annulus Pressure Test

Newfield Production Company

Rt. 3 Box 3630

Myton, UT 84052

435-646-3721

Witness: Mark Jones Date 9/4/15 Time 2:00 am ☒ pm
Test Conducted by: Johnny Daniels
Others Present: _____

Well: 15-29-15Field: Monument Butte


Well Location: SW/SE Sec. 2, T9S, R15E API No: 43013-32579
Duchesne County

<u>Time</u>	<u>Casing Pressure</u>	
0 min	<u>1237</u>	psig
5	<u>1235</u>	psig
10	<u>1234</u>	psig
15	<u>1234</u>	psig
20	<u>1233</u>	psig
25	<u>1233</u>	psig
30 min	_____	psig
35	_____	psig
40	_____	psig
45	_____	psig
50	_____	psig
55	_____	psig
60 min	_____	psig

Tubing pressure: 1790 psigResult: Pass FailSignature of Witness: Mark Jones USOGMSignature of Person Conducting Test: Johnny Daniels

15-2-9-15

9/8/2015 7:02:58 AM



NEWFIELD



Schematic

43-013-32579

Well Name: Ashley 15-2-9-15

Surface Legal Location 02-9S-15E		API/UWI 43013325790000	Well RC 500151829	Lease	State/Province Utah	Field Name GMBU CTB2	County Duchesne
Spud Date	Rig Release Date	On Production Date 7/28/2004	Original KB Elevation (ft) 6,032	Ground Elevation (ft) 6,020	Total Depth All (TVD) (ftKB)	PBTD (All) (ftKB)	Original Hole - 6,126.0

Most Recent Job

Job Category Testing	Primary Job Type	Secondary Job Type N/A	Job Start Date 9/4/2015	Job End Date 9/4/2015
-------------------------	------------------	---------------------------	----------------------------	--------------------------

TD: 6,160.0

Vertical - Original Hole, 3/29/2016 10:23:13 AM

MD (ftKB)	TVD (ftKB)	Incl (°)	DLS	DLS (°...)	Vertical schematic (actual)
12.1					
80.1					
306.1					
307.1					1; Surface; 8 5/8 in; 8.097 in; 12-307 ftKB; 294.88 ft
4,476.0					2-1; Tubing; 2 7/8; 2.441; 12-4,476; 4,464.10
4,477.4					2-2; Pump Seating Nipple; 2 7/8; 2.441; 4,476-4,477; 1.10
4,484.9					2-3; Packer; 5 1/2; 4.950; 4,477-4,485; 7.49
4,485.9					2-4; Cross Over; 2 7/8; 2.441; 4,485-4,486; 1.10
4,544.9					
4,556.1					Perforated; 4,545-4,556; 7/23/2004
4,664.0					
4,673.9					Perforated; 4,664-4,674; 7/23/2004
5,359.9					
5,379.9					Perforated; 5,360-5,380; 7/23/2004
5,669.9					
5,673.9					Perforated; 5,670-5,674; 7/23/2004
5,879.9					
5,899.9					Perforated; 5,880-5,900; 7/23/2004
6,123.7					
6,124.3					
6,126.0					
6,149.3					
6,149.9					2; Production; 5 1/2 in; 4.950 in; 12-6,150 ftKB; 6,137.85 ft
6,160.1					

NEWFIELD



Newfield Wellbore Diagram Data Ashley 15-2-9-15

Surface Legal Location 02-9S-15E		API/LWI/ 43013325790000		Lease	
County Duchesne		State/Province Utah		Basin	
Well Start Date 6/14/2004		Spud Date		Field Name GMBU CTB2	
Original KB Elevation (ft) 6,032		Ground Elevation (ft) 6,020		Final Rig Release Date	
Total Depth (ftKB) 6,160.0		Total Depth All (TVD) (ftKB)		On Production Date 7/28/2004	
				PBTD (All) (ftKB) Original Hole - 6,126.0	

Casing Strings

Csg Des	Run Date	OD (in)	ID (in)	Wt/Len (lb/ft)	Grade	Set Depth (ftKB)
Surface	6/14/2004	8 5/8	8.097	24.00	J-55	307
Production	7/2/2004	5 1/2	4.950	15.50	J-55	6,150

Cement

String: Surface, 307ftKB 6/18/2004

Cementing Company BJ Services Company		Top Depth (ftKB) 12.0	Bottom Depth (ftKB) 307.0	Full Return?	Vol Cement Ret (bbl)
Fluid Description 2% CaCL2 + 1/4#/sk Cello-Flake mixed		Fluid Type Lead	Amount (sacks) 150	Class G	Estimated Top (ftKB) 12.0

String: Production, 6,150ftKB 7/2/2004

Cementing Company BJ Services Company		Top Depth (ftKB) 80.0	Bottom Depth (ftKB) 6,160.0	Full Return?	Vol Cement Ret (bbl)
Fluid Description 10% gel + 3% KCL, 3#'s/sk CSE + 2# sk/kolseal + 1/2#'s/sk Cello Flake		Fluid Type Lead	Amount (sacks) 300	Class PREMLITE II	Estimated Top (ftKB) 80.0
Fluid Description 2% Gel + 3% KCL, .5%EC1, 1/4# sk C.F. 2% gel. 3% SM mixed		Fluid Type Lead	Amount (sacks) 400	Class 50/50 POZ	Estimated Top (ftKB) 2,500.0

Tubing Strings

Tubing Description Tubing					Run Date 11/10/2005		Set Depth (ftKB) 4,485.9	
Item Des	Jts	OD (in)	ID (in)	Wt: (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)
Tubing	140	2 7/8	2.441	6.50	J-55	4,464.10	12.1	4,476.2
Pump Seating Nipple	1	2 7/8	2.441			1.10	4,476.2	4,477.3
Packer	1	5 1/2	4.950			7.49	4,477.3	4,484.8
Cross Over	1	2 7/8	2.441			1.10	4,484.8	4,485.9

Rod Strings

Rod Description				Run Date		Set Depth (ftKB)	
Item Des	Jts	OD (in)	Wt (lb/ft)	Grade	Len (ft)	Top (ftKB)	Btm (ftKB)

Perforation Intervals

Stage#	Zone	Top (ftKB)	Btm (ftKB)	Shot Dens (shots/ft)	Phasing (*)	Nom Hole Dia (in)	Date
5	CP3, Original Hole	4,545	4,556	4			7/23/2004
4	CP.5, Original Hole	4,664	4,674	4			7/23/2004
3	LODC, Original Hole	5,360	5,380	4			7/23/2004
2	DS1, Original Hole	5,670	5,674	4			7/23/2004
1	PB10, Original Hole	5,880	5,900	4			7/23/2004

Stimulations & Treatments

Stage#	ISIP (psi)	Frac Gradient (psi/ft)	Max Rate (bbl/min)	Max PSI (psi)	Total Clean Vol (bbl)	Total Slurry Vol (bbl)	Vol Recov (bbl)
2	2,015	0.79	24.6	4,200			
2	2,015	0.79	24.6	4,200			
2	2,015	0.79	24.6	4,200			
2	2,015	0.79	24.6	4,200			
2	2,015	0.79	24.6	4,200			

Proppant

Stage#	Total Prop Vol Pumped (lb)	Total Add Amount
2		Proppant White Sand 185471 lb
2		Proppant White Sand 185471 lb
2		Proppant White Sand 185471 lb
2		Proppant White Sand 185471 lb
2		Proppant White Sand 185471 lb